Proposal: 260096 **Let Date:** April 09, 2026 **Call Order:** 575
J/P Num: 35141(04) **Proj. Num:** SBR-272N(466)SB
Counties: TULSA
Description: BRIDGE REHABILITATION
SH-51: OVER THE ARKANSAS RIVER,
0.85 MILES SOUTH OF THE US-412 INTERSECTION
IN THE CITY OF SAND SPRINGS.
PROJECT LENGTH = 0.393 MILES

Line #		Item Description	Quantity	Unit
0001	BRIDGE 'A' - NBI NO. 19511			
0010	501(G)1800	CLSM BACKFILL	2.000	CY
0020	509 0100	SPECIAL CONCRETE FINISH	1,651.000	SY
0030	512(A)3200	PAINTING EXISTING STRUCTURES	1.000	LSUM
0040	517 9110	ELASTOMERIC COATING	420.000	SF
0050	518(C)0400	RAPID CURE JOINT SEALANT	116.000	LF
0060	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	332.000	LF
0070	520(C)1400	EPOXY RESIN, ABOVE WATER	26.400	GAL
0080	521(A)2200	PNEUMATICALLY PLACED MORTAR	35.100	SY
0090	523(A)3200	SEALER CRACK PREPARATION	978.000	LF
0100	523(B)3300	SEALER RESIN	11.000	GAL
0110	523(C)3400	DECK AREA SEALED (FLOODCOATS)	9,579.000	SY
0120	524(A)4200	(SP) CARBON FIBER-REINFORCED POLYMER	163.000	SF
0130	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	19.000	SY
0140	540 8120	(PL)REPAIR BRIDGE ITEM (TYPE A)	1.000	EA
0002	TRAFFIC CONTROL			
0150	857(C)9420	REMOVABLE PAVEMENT MARKING TAPE(ARROWS)	2.000	EA
0160	876(A)3210	(PL)TRUCK MOUNTED ATTENUATOR	120.000	SD
0170	880(A)6220	ARROW DISPLAY(TYPE C)	120.000	SD
0180	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,200.000	SD
0190	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,200.000	SD
0200	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,920.000	SD
0210	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	960.000	SD
0220	880(E)6600	WARNING LIGHTS(TYPE A)	3,360.000	SD
0230	880(F)6700	DRUMS	8,400.000	SD
0240	880(G)6805	CHANNELIZER CONES	9,000.000	SD
0250	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	134.000	SD
0003	SIGNING AND STRIPING			
0260	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	5,500.000	LF
0004	CONSTRUCTION			
0280	641 2100	MOBILIZATION	1.000	LSUM