Proposal: 260101 **Let Date:** April 16, 2026 **Call Order:** 600
J/P Num: 38213(04) **Proj. Num:** STP-205C(142)3P
Counties: BECKHAM
Description: RESURFACE (ASPHALT)
SH-55: FROM THE SH-34 JUNCTION,
EXTEND EAST NEAR CARTER.
PROJECT LENGTH = 5.94 MILES

	Line #		Item Description	Quantity	Unit
0001	ROADWAY				
	0010	407(C)7400	(SP) POLYMER MOD. CATIONIC RAPID SET - 1S	23,686.970	GAL
	0020	411(C)1400	SUPERPAVE, TYPE S4(PG 76-28 OK)	15,855.810	TON
	0030	412 3100	COLD MILLING PAVEMENT	3,811.470	SY
	0040	413(A)4210	RUMBLE STRIP-CENTERLINE HMA-CON	28,500.000	LF
	0050	413(B)4310	RUMBLE STRIP-METHOD HMA-CYC	56,000.000	LF
0002	TRAFFIC SIGNING AND STRIPING				
	0060	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	101,000.000	LF
	0070	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	222.000	LF
0003	TRAFFIC CONTROL				
	0080	857(E)9620	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	2,792.000	EA
	0090	880(J)7100	(SP) CONSTRUCTION TRAFFIC CONTROL	40.000	SD
	0100	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	108.000	SD