Proposal: 260107 **Let Date:** April 16, 2026 **Call Order:** 630
J/P Num: 33744(04) **Proj. Num:** NHPPI-3500-(216)PM
Counties: MURRAY
Description: RESURFACE (ASPHALT)
I-35: FROM 5.4 MILES SOUTH OF THE US-77
INTERCHANGE, EXTEND NORTH NEAR DAVIS.
PROJECT LENGTH = 6.434 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	405 5100	PERMEABLE FRICTION COURSE	9,986.000	TON
0020	407(B)7300	TACK COAT	42,742.000	GAL
0030	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	2,569.000	TON
0040	411(F)1700	STONE MATRIX ASPHALT	15,203.000	TON
0050	411(I)2010	SUPERPAVE, TYPE S4(PATCH)(PG76-28OK)	830.000	TON
0060	411(L)2433	BMD, TYPE B4 (PG 76-28 E)	20,290.000	TON
0070	412 3100	COLD MILLING PAVEMENT	176,045.000	SY
0080	518(C)0400	RAPID CURE JOINT SEALANT	178.000	LF
0090	518(D)0500	ELASTOMERIC MORTAR	51.000	CF
0100	619(B)6396	REMOVAL OF GUARDRAIL	9,022.000	LF
0110	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	7,938.000	LF
0120	623(F)1764	GUARDRAIL TRAIL END TURNDOWN (31")	6.000	EA
0130	623(G)1820	GUARDRAIL END TREATMENT (31")	16.000	EA
0140	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	14.000	EA
0002	TRAFFIC CONTROL			
0150	857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	162,000.000	LF
0160	858(A)0216	PAVE.MARKERS CLASS A TYPE 2-A	5,295.000	EA
0170	858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	2,700.000	EA
0180	876(A)3210	(PL)TRUCK MOUNTED ATTENUATOR	200.000	SD
0190	880(A)6220	ARROW DISPLAY(TYPE C)	90.000	SD
0200	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	990.000	SD
0210	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	720.000	SD
0220	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,530.000	SD
0230	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	630.000	SD
0240	880(E)6607	WARNING LIGHTS(TYPE B)	1,710.000	SD
0250	880(E)6610	WARNING LIGHTS(TYPE C)	11,880.000	SD
0260	880(E)6616	WARNING LIGHTS(TYPE D)	9,900.000	SD
0270	880(F)6700	DRUMS	9,900.000	SD
0280	880(G)6805	CHANNELIZER CONES	11,880.000	SD
0290	880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	750.000	HOUR
0300	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	208.000	SD
0003	TRAFFIC SIGNING AND STRIPING			
0310	413(B)4310	RUMBLE STRIP-METHOD HMA-CYC	70,520.000	LF
0320	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	110,000.000	LF
0330	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	7,000.000	LF
0004	STAKING			
0340	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0350	641 2110	MOBILIZATION	1.000	LSUM