Proposal:260108 **Let Date:**April 16, 2026 **Call Order:**635
J/P Num:36359(04) **Proj. Num:**NHPP-251N(201)AD
Counties:MUSKOGEE
Description:PEDESTRIAN IMPROVEMENTS
US-64B: FROM THE INTERSECTION OF US-62B,
EXTEND SOUTH IN THE CITY OF MUSKOGEE.
PROJECT LENGTH = 0.276 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	303(A)1200	AGGREGATE BASE TYPE A	433.000	CY
0020	609(A)4210	CONC.CURB(4" BARRIER-INTEGRAL)	94.000	LF
0030	609(A)4230	CONC.CURB(6" BARRIER-INTEGRAL)	67.000	LF
0040	609(B)4355	2'-8" COMB.CRB.& GUT.(4" MNTBLE)	80.000	LF
0050	609(B)4375	2'-8" COMB.CRB.& GUT.(8" BARRIER)	2,293.000	LF
0060	610(A)5200	4" CONCRETE SIDEWALK	2,063.000	SY
0070	610(B)5300	6" CONCRETE DRIVEWAY (H.E.S.)	302.000	SY
0080	610(I)6000	TACTILE WARNING DEVICE-NEW	277.000	SF
0090	612(F)3700	METER BOXES ADJUST TO GRADE	28.000	EA
0100	619(B)6356	REMOVAL OF CURB AND GUTTER	1,970.000	LF
0110	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	160.000	SY
0120	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	41.000	SY
0130	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	325.000	SY
0140	619(B)6392	REMOVAL OF EXISTING STRUCTURES	13.000	EA
0150	619(B)6404	REMOVAL OF SIDEWALK	1,747.000	SY
0160	622(A)0200	PIPE RAILING	16.000	LF
0170	631(A)9210	(SP)REMOVABLE BOLLARD	1.000	EA
0002	SIGNING AND STRIPING			
0180	805(A)3200	REMOVAL OF SIGN FOOTING	1.000	EA
0190	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	25.000	EA
0200	836 7100	REGULATORY OR WARNING SIGN ASSEMBLY	2.000	EA
0210	850(A)1200	SHEET ALUMINUM SIGNS	9.500	SF
0220	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	759.000	LF
0230	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	494.000	LF
0003	TRAFFIC SIGNAL			
0240	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	95.000	LF
0260	803(A)1210	PULL BOX(SIZE I)	2.000	EA
0270	804(A)2200	STRUCTURAL CONCRETE	2.800	CY
0280	804(B)2300	REINFORCING STEEL	270.000	LB
0300	805(A)3256	(PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1.000	LSUM
0305	805(B)3300	(PL)RESET OF PULL BOX	6.000	EA
0310	806(B)4400	6' MTG.HT.TS PED.POLE(G.STL.)	2.000	EA
0320	806(B)4412	12' MTG.HT.TS PED.POLE(G.STL.)	4.000	EA
0330	811 9130	1/C NO.10 ELECT.COND.	600.000	LF
0340	830 2100	PEDESTRIAN PUSH BUTTON	8.000	EA
0350	831 3116	1WAY2SEC.ADJ.PED.SIG.HD.S-20	8.000	EA
0360	834(A)6200	2/C TRAFFIC SIGNAL ELECTRICAL CABLE	150.000	LF
0370	834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	250.000	LF
0380	834(A)6235	21/C TRAFFIC SIGNAL ELECTRICAL CABLE	300.000	LF

Proposal:260108 **Let Date:**April 16, 2026 **Call Order:**635
J/P Num:36359(04) **Proj. Num:**NHPP-251N(201)AD
Counties:MUSKOGEE
Description:PEDESTRIAN IMPROVEMENTS
US-64B: FROM THE INTERSECTION OF US-62B,
EXTEND SOUTH IN THE CITY OF MUSKOGEE.
PROJECT LENGTH = 0.276 MILES

Line #		Item Description	Quantity	Unit
0004	TRAFFIC CONTROL			
0390	880(A)6220	ARROW DISPLAY(TYPE C)	150.000	SD
0400	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,275.000	SD
0410	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	3,750.000	SD
0420	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	750.000	SD
0430	880(E)6600	WARNING LIGHTS(TYPE A)	1,200.000	SD
0440	880(F)6700	DRUMS	9,900.000	SD
0450	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	28.000	SD
0005	STAKING			
0460	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
0470	641 2110	MOBILIZATION	1.000	LSUM