Proposal:260109 **Let Date:**April 16, 2026 **Call Order:**640
J/P Num:12972(04) **Proj. Num:**STP-054B(154)PM
Counties:OKFUSKEE
Description:WIDEN AND RESURFACE
US-75: FROM 0.4 MILES WEST OF THE SH-84 JUNCTION, EXTEND NORTH NEAR WELEETKA.
PROJECT LENGTH = 4.3189 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	87,914.000	CY
0030	202(E)2600	SELECT BORROW	2,000.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	12,487.000	LF
0060	221(C)2400	TEMPORARY SEDIMENT FILTER	10.000	EA
0070	221(E)2600	TEMPORARY SILT DIKE	3,019.000	LF
0080	221(F)2710	TEMPORARY ROCK FILTER DAM TYPE 2	25.000	CY
0090	230(A)7200	SOLID SLAB SODDING	128,013.000	SY
0100	233(A)0200	VEGETATIVE MULCHING	26.500	AC
0110	241 3100	MOWING	53.000	AC
0120	303(A)1200	AGGREGATE BASE TYPE A	14,933.000	CY
0130	307(K)4200	STABILIZED SUBGRADE	73,491.000	SY
0140	325 0100	SEPARATOR FABRIC	83,322.000	SY
0150	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	5,659.000	TON
0160	407(B)7300	TACK COAT	22,312.000	GAL
0170	408 8100	PRIME COAT	46,909.000	GAL
0180	409(A)9200	FABRIC REINFORCEMENT	110,558.000	SY
0190	409(B)9300	BITUMINOUS BINDER	27,640.000	GAL
0200	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	20,994.000	TON
0210	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	26,396.000	TON
0220	412 3100	COLD MILLING PAVEMENT	60,810.000	SY
0230	414(E)5600	FULL DEPTH P.C.C. PATCH (PLACEMENT)	200.000	SY
0240	414(G)5800	P.C. CONCRETE FOR PAVEMENT	50.000	CY
0250	509(A)0200	CLASS AA CONCRETE	621.000	CY
0260	509(D)0500	CLASS C CONCRETE	20.000	CY
0270	511(A)2200	REINFORCING STEEL	87,602.000	LB
0280	601(A)1100	TYPE I PLAIN RIPRAP	225.000	TON
0290	609(B)4360	2'-8" COMB.CRB.& GUT.(6" BARRIER)	1,198.000	LF
0300	609(B)4370	2'-8" COMB.CRB.& GUT.(6" MNTBLE)	3,156.000	LF
0310	610(A)5200	4" CONCRETE SIDEWALK	578.000	SY
0320	610(B)5320	8" CONCRETE DRIVEWAY	107.000	SY
0330	610(I)6000	TACTILE WARNING DEVICE-NEW	40.000	SF
0340	611(G)7786	INLET CI DES. 3 (STD)	1.000	EA
0350	611(G)7798	INLET CI DES. 3 (2B)	2.000	EA
0360	611(G)7806	INLET CI DES. 3 (2D)	2.000	EA
0370	611(G)8004	INLET CDI RCB DES. 2	2.000	EA
0380	611(G)9004	INLET CDI RCP DES. 2	2.000	EA
0390	611(G)9008	INLET CDI RCP DES. 3	1.000	EA
0400	611(H)0422	ADD'L DEPTH IN INLET CI DES. 3	12.920	VF
0410	611(H)0524	ADD'L DEPTH IN INLET CDI RCB DES. 2	0.830	VF
0420	611(H)0684	ADD'L DEPTH IN INLET CDI RCP DES. 2	13.250	VF
0430	613(A)5208	18" R.C.PIPE CLASS III	250.000	LF
0440	613(A)5216	24" R.C.PIPE CLASS III	453.000	LF
0450	613(A)5220	30" R.C.PIPE CLASS III	127.000	LF
0460	613(A)5224	36" R.C.PIPE CLASS III	258.000	LF
0470	613(A)5366	36" X 22" R.C.PIPE ARCH CLASS A-III	172.000	LF

Proposal:260109 **Let Date:**April 16, 2026 **Call Order:**640
J/P Num:12972(04) **Proj. Num:**STP-054B(154)PM
Counties:OKFUSKEE
Description:WIDEN AND RESURFACE
US-75: FROM 0.4 MILES WEST OF THE SH-84 JUNCTION, EXTEND NORTH NEAR WELEETKA.
PROJECT LENGTH = 4.3189 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0480	613(A)5412	29" X 45" R.C.PIPE ELL. CLASS HE-III	694.000	LF
0490	613(A)5416	34" X 53" R.C.PIPE ELL. CLASS HE-III	86.000	LF
0500	613(B)5508	18" CORR. GALV. STEEL PIPE	949.000	LF
0510	613(B)5516	24" CORR. GALV. STEEL PIPE	738.000	LF
0520	613(B)5604	21" X 15" CORR. GALV. STEEL PIPE ARCH	434.000	LF
0530	613(B)5616	35" X 24" CORR. GALV. STEEL PIPE ARCH	74.000	LF
0540	613(J)6400	EDGE DRAIN CONDUIT-PERFORATED	4,353.000	LF
0550	613(L)6636	36" X 22" PREFAB. CULVERT END SEC., ARCH	2.000	EA
0560	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	4.000	EA
0570	613(L)6724	30" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0580	613(L)6728	36" PREFAB. CULVERT END SEC., ROUND	6.000	EA
0590	613(L)6812	29" X 45" PREFAB. CULVERT END SEC., ELLI	18.000	EA
0600	613(L)6816	34" X 53" PREFAB. CULVERT END SEC., ELLI	2.000	EA
0610	613(M)6960	TYPE A4 CULVERT END TREATMENT	70.000	EA
0620	613(M)6964	TYPE B4 CULVERT END TREATMENT	47.000	EA
0630	613(M)6984	TYPE BB4 CULVERT END TREATMENT	2.000	EA
0640	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0650	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	1,707.000	SY
0660	619(B)6376	REMOVAL OF CONC.PAV.W/ASPH.OVERLAY	200.000	SY
0670	619(B)6396	REMOVAL OF GUARDRAIL	935.000	LF
0680	619(B)6404	REMOVAL OF SIDEWALK	305.000	SY
0690	619(C)6600	SAWING PAVEMENT	45,632.000	LF
0700	620(C)8400	(SP) CONTRACTOR HEALTH AND SAFETY PLAN	1.000	LSUM
0710	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	338.000	LF
0720	623(G)1820	GUARDRAIL END TREATMENT (31")	2.000	EA
0730	624(A)3200	FENCE-STYLE WWF	829.000	LF
0740	624(C)3400	FENCE-STYLE SWF (4 BARBED WIRE)	1,309.000	LF
0750	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	9,196.000	LF
0760	624(C)3410	FENCE-STYLE SWF (6 BARBED WIRE)	4,380.000	LF
0770	624(E)3600	FENCE-STYLE CLF (4'HIGH, CLASS A)	197.000	LF
0780	629(A)7200	MAILBOX INSTALLATION-SINGLE	20.000	EA
0790	629(B)7300	MAILBOX INSTALLATION-MULTIPLE	7.000	EA
0800	629(C)7400	REMOVAL OF MAILBOX INSTALLATION	35.000	EA
0810	629(E)7600	MAILBOX	35.000	EA

Proposal:260109 **Let Date:**April 16, 2026 **Call Order:**640
J/P Num:12972(04) **Proj. Num:**STP-054B(154)PM
Counties:OKFUSKEE
Description:WIDEN AND RESURFACE
US-75: FROM 0.4 MILES WEST OF THE SH-84 JUNCTION, EXTEND NORTH NEAR WELEETKA.
PROJECT LENGTH = 4.3189 MILES

Line #		Item Description	Quantity	Unit
0002	TRAFFIC			
0820	823 6100	(SP)PORTABLE TRAFFIC SIGNAL SYSTEM	90.000	SD
0830	857(A)9200	CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE)	78,763.000	LF
0840	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	2,000.000	LF
0850	876(A)3210	(PL)TRUCK MOUNTED ATTENUATOR	600.000	SD
0860	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	1,000.000	LF
0870	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	1,000.000	LF
0880	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	4,200.000	SD
0890	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	2,400.000	SD
0900	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	5,400.000	SD
0910	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,200.000	SD
0920	880(E)6607	WARNING LIGHTS(TYPE B)	9,600.000	SD
0930	880(F)6700	DRUMS	3,000.000	SD
0940	880(G)6805	CHANNELIZER CONES	272,100.000	SD
0950	880(I)7000	FLAGGER	300.000	SD
0960	880(W)7700	PILOT CAR	1.000	LSUM
0970	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	628.000	SD
0003	SIGN AND STRIPE			
0980	413(C)4410	RUMBLE STRIP-CENTERLINE PCC-CON	18,800.000	LF
0990	413(F)4700	SINUSOIDAL RUMBLE STRIP	37,600.000	LF
1000	805(A)3248	(PL)REMOVAL OF EXISTING SIGNS	1.000	LSUM
1010	850(A)1200	SHEET ALUMINUM SIGNS	579.000	SF
1020	851(C)2430	2 1/2" SQUARE TUBE POST	1,152.000	LF
1030	853 5125	DELINEATORS(TYPE 2, CODE 3)	19.000	EA
1040	853 5175	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	10.000	EA
1050	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	78,763.000	LF
1060	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	50.000	LF
0004	STAKING			
1070	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
1080	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
1090	641 2110	MOBILIZATION	1.000	LSUM