Proposal:260112 **Let Date:**April 16, 2026 **Call Order:**655
J/P Num:31080(04) **Proj. Num:**NHPP-019N(176)PM
Counties:TULSA
Description:BRIDGE REHABILITATION
US-64: OVER MAIN ST, 49TH W AVE, AND 33RD W AVE
IN THE CITY OF SAND SPRINGS AND TULSA.
PROJECT LENGTH = 0.069 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	50.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	25.000	CY
0040	221(B)2300	TEMPORARY SILT FENCE	500.000	LF
0050	221(E)2600	TEMPORARY SILT DIKE	14.000	LF
0060	230(A)7200	SOLID SLAB SODDING	252.000	SY
0070	232(A)9200	SEEDING METHOD A	0.050	AC
0080	233(A)0200	VEGETATIVE MULCHING	0.050	AC
0090	242 4101	STABILIZED CONSTRUCTION EXIT	4.000	EA
0100	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	107.000	TON
0110	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	106.000	SY
0120	414(G)5800	P.C. CONCRETE FOR PAVEMENT	35.200	CY
0130	504(E)5520	42" F-SHAPED PARAPET	100.000	LF
0140	509(D)0500	CLASS C CONCRETE	2.750	CY
0150	511(B)2300	EPOXY COATED REINFORCING STEEL	7,273.000	LB
0160	609(B)4300	COMBINED CURB & GUTTER(4" MOUNTABLE)	44.000	LF
0170	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	460.000	SY
0180	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	169.000	SY
0190	619(B)6396	REMOVAL OF GUARDRAIL	1,047.000	LF
0200	619(B)6400	REMOVAL OF CURB	198.000	LF
0210	619(B)6436	REMOVAL OF CONCRETE DITCH LINER	54.000	LF
0220	619(C)6600	SAWING PAVEMENT	1,824.000	LF
0230	623 1100	(PL)GUARDRAIL CURBING	1.000	EA
0240	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	512.500	LF
0250	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	13.000	EA
0260	853 5100	DELINEATORS(TYPE 1, CODE 1)	18.000	EA

Proposal:260112 **Let Date:**April 16, 2026 **Call Order:**655
J/P Num:31080(04) **Proj. Num:**NHPP-019N(176)PM
Counties:TULSA
Description:BRIDGE REHABILITATION
US-64: OVER MAIN ST, 49TH W AVE, AND 33RD W AVE
IN THE CITY OF SAND SPRINGS AND TULSA.
PROJECT LENGTH = 0.069 MILES

Line #		Item Description	Quantity	Unit
0002	BRIDGE 'A' - NBI NO. 17235			
0270	415 7100	CONCRETE JOINT SEALING	432.000	LF
0280	501(G)1800	CLSM BACKFILL	60.000	CY
0290	504(A)5200	APPROACH SLAB	176.700	SY
0300	504(B)5300	SAW-CUT GROOVING	631.200	SY
0310	504(E)5520	42" F-SHAPED PARAPET	355.500	LF
0320	509 0100	SPECIAL CONCRETE FINISH	58.000	SY
0330	509(A)0210	CLASS AA CONCRETE	174.100	CY
0340	509(D)0510	CLASS C CONCRETE	1.700	CY
0350	510(D)1500	GRAFFITI TREATMENT	250.000	SF
0360	511(B)2310	EPOXY COATED REINFORCING STEEL	55,280.000	LB
0370	512(A)3200	PAINTING EXISTING STRUCTURES	1.000	LSUM
0380	512(B)3300	COLLECTION AND HANDLING OF WASTE	1.000	LSUM
0390	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	588.000	SY
0400	517 9110	ELASTOMERIC COATING	792.000	SF
0410	518(B)0300	SEALED EXPANSION JOINTS	76.840	LF
0420	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	335.000	LF
0430	520(C)1400	EPOXY RESIN, ABOVE WATER	5.200	GAL
0440	521(A)2200	PNEUMATICALLY PLACED MORTAR	14.000	SY
0450	523(A)3200	SEALER CRACK PREPARATION	345.000	LF
0460	523(B)3300	SEALER RESIN	8.400	GAL
0470	524(A)4200	(SP) CARBON FIBER-REINFORCED POLYMER	414.000	SF
0480	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	27.000	SY
0490	545 0100	(PL)REPLACE BRIDGE ITEMS	1.000	LSUM
0500	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM

Proposal:260112 **Let Date:**April 16, 2026 **Call Order:**655
J/P Num:31080(04) **Proj. Num:**NHPP-019N(176)PM
Counties:TULSA
Description:BRIDGE REHABILITATION
US-64: OVER MAIN ST, 49TH W AVE, AND 33RD W AVE
IN THE CITY OF SAND SPRINGS AND TULSA.
PROJECT LENGTH = 0.069 MILES

Line #		Item Description	Quantity	Unit
0003	BRIDGE 'B' - NBI NO. 17236			
0510	415 7100	CONCRETE JOINT SEALING	480.000	LF
0520	501(G)1800	CLSM BACKFILL	72.500	CY
0530	504(A)5200	APPROACH SLAB	206.900	SY
0540	504(B)5300	SAW-CUT GROOVING	803.700	SY
0550	504(E)5520	42" F-SHAPED PARAPET	352.200	LF
0560	509 0100	SPECIAL CONCRETE FINISH	98.000	SY
0570	509(A)0210	CLASS AA CONCRETE	187.500	CY
0580	510(C)1450	SLOPE WALL (5")	174.000	SY
0590	510(D)1500	GRAFFITI TREATMENT	250.000	SF
0600	511 2100	MECHANICAL SPLICES	580.000	EA
0610	511(B)2310	EPOXY COATED REINFORCING STEEL	59,320.000	LB
0620	512(A)3200	PAINTING EXISTING STRUCTURES	1.000	LSUM
0630	512(B)3300	COLLECTION AND HANDLING OF WASTE	1.000	LSUM
0640	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	633.000	SY
0650	517 9110	ELASTOMERIC COATING	828.000	SF
0660	518(B)0300	SEALED EXPANSION JOINTS	98.750	LF
0670	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	174.000	LF
0680	520(C)1400	EPOXY RESIN, ABOVE WATER	2.700	GAL
0690	521(A)2200	PNEUMATICALLY PLACED MORTAR	17.000	SY
0700	523(A)3200	SEALER CRACK PREPARATION	177.000	LF
0710	523(B)3300	SEALER RESIN	2.800	GAL
0720	524(A)4200	(SP) CARBON FIBER-REINFORCED POLYMER	942.000	SF
0730	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	27.000	SY
0740	545 0100	(PL)REPLACE BRIDGE ITEMS	1.000	LSUM
0750	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM

Proposal:260112 **Let Date:**April 16, 2026 **Call Order:**655
J/P Num:31080(04) **Proj. Num:**NHPP-019N(176)PM
Counties:TULSA
Description:BRIDGE REHABILITATION
US-64: OVER MAIN ST, 49TH W AVE, AND 33RD W AVE
IN THE CITY OF SAND SPRINGS AND TULSA.
PROJECT LENGTH = 0.069 MILES

Line #		Item Description	Quantity	Unit
0004	BRIDGE 'C' - NBI NO. 18545			
0760	415 7100	CONCRETE JOINT SEALING	1,116.000	LF
0770	501(G)1800	CLSM BACKFILL	141.000	CY
0780	504(A)5200	APPROACH SLAB	412.400	SY
0790	504(B)5300	SAW-CUT GROOVING	1,161.600	SY
0800	504(E)5520	42" F-SHAPED PARAPET	485.800	LF
0810	509 0100	SPECIAL CONCRETE FINISH	50.000	SY
0820	509(A)0210	CLASS AA CONCRETE	262.500	CY
0830	509(D)0510	CLASS C CONCRETE	1.200	CY
0840	510(D)1500	GRAFFITI TREATMENT	250.000	SF
0850	511 2100	MECHANICAL SPLICES	778.000	EA
0860	511(B)2310	EPOXY COATED REINFORCING STEEL	86,070.000	LB
0870	512(A)3200	PAINTING EXISTING STRUCTURES	1.000	LSUM
0880	512(B)3300	COLLECTION AND HANDLING OF WASTE	1.000	LSUM
0890	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	856.000	SY
0900	517 9110	ELASTOMERIC COATING	1,062.000	SF
0910	518(B)0300	SEALED EXPANSION JOINTS	106.000	LF
0920	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	171.000	LF
0930	520(C)1400	EPOXY RESIN, ABOVE WATER	2.900	GAL
0940	521(A)2200	PNEUMATICALLY PLACED MORTAR	21.000	SY
0950	523(A)3200	SEALER CRACK PREPARATION	763.000	LF
0960	523(B)3300	SEALER RESIN	26.300	GAL
0970	524(A)4200	(SP) CARBON FIBER-REINFORCED POLYMER	609.000	SF
0980	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	50.000	SY
0990	601(B)1230	TYPE I-A PLAIN RIPRAP	30.000	TON
1000	601(C)1310	TYPE I-A FILTER BLANKET	15.000	TON
1010	601(I)1700	FILTER FABRIC (RIPRAP)	49.000	SY
1020	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM

Proposal:260112 **Let Date:**April 16, 2026 **Call Order:**655
J/P Num:31080(04) **Proj. Num:**NHPP-019N(176)PM
Counties:TULSA
Description:BRIDGE REHABILITATION
US-64: OVER MAIN ST, 49TH W AVE, AND 33RD W AVE
IN THE CITY OF SAND SPRINGS AND TULSA.
PROJECT LENGTH = 0.069 MILES

Line #		Item Description	Quantity	Unit
0005	BRIDGE 'D' - NBI NO. 18546			
1030	415 7100	CONCRETE JOINT SEALING	1,116.000	LF
1040	501(G)1800	CLSM BACKFILL	131.800	CY
1050	504(A)5200	APPROACH SLAB	412.400	SY
1060	504(B)5300	SAW-CUT GROOVING	1,161.600	SY
1070	504(E)5520	42" F-SHAPED PARAPET	485.800	LF
1080	509 0100	SPECIAL CONCRETE FINISH	50.000	SY
1090	509(A)0210	CLASS AA CONCRETE	261.700	CY
1100	510(D)1500	GRAFFITI TREATMENT	250.000	SF
1110	511 2100	MECHANICAL SPLICES	778.000	EA
1120	511(B)2310	EPOXY COATED REINFORCING STEEL	86,030.000	LB
1130	512(A)3200	PAINTING EXISTING STRUCTURES	1.000	LSUM
1140	512(B)3300	COLLECTION AND HANDLING OF WASTE	1.000	LSUM
1150	512(C)3400	TREATING PACK RUST WITH PENETRAT. SEALER	3.000	EA
1160	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	856.000	SY
1170	517 9110	ELASTOMERIC COATING	1,062.000	SF
1180	518(B)0300	SEALED EXPANSION JOINTS	106.000	LF
1190	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	61.000	LF
1200	520(C)1400	EPOXY RESIN, ABOVE WATER	1.300	GAL
1210	521(A)2200	PNEUMATICALLY PLACED MORTAR	14.000	SY
1220	523(A)3200	SEALER CRACK PREPARATION	763.000	LF
1230	523(B)3300	SEALER RESIN	26.300	GAL
1240	524(A)4200	(SP) CARBON FIBER-REINFORCED POLYMER	609.000	SF
1250	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	22.000	SY
1260	545 0100	(PL)REPLACE BRIDGE ITEMS	1.000	LSUM
1270	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM

Proposal:260112 **Let Date:**April 16, 2026 **Call Order:**655
J/P Num:31080(04) **Proj. Num:**NHPP-019N(176)PM
Counties:TULSA
Description:BRIDGE REHABILITATION
US-64: OVER MAIN ST, 49TH W AVE, AND 33RD W AVE
IN THE CITY OF SAND SPRINGS AND TULSA.
PROJECT LENGTH = 0.069 MILES

Line #		Item Description	Quantity	Unit
0006	BRIDGE 'E' - NBI NO. 18460			
1280	501(G)1800	CLSM BACKFILL	174.800	CY
1290	504(A)5200	APPROACH SLAB	553.000	SY
1300	504(B)5300	SAW-CUT GROOVING	718.900	SY
1310	504(E)5520	42" F-SHAPED PARAPET	296.700	LF
1320	509 0100	SPECIAL CONCRETE FINISH	724.000	SY
1330	509(A)0210	CLASS AA CONCRETE	71.000	CY
1340	510(D)1500	GRAFFITI TREATMENT	5,107.000	SF
1350	511 2100	MECHANICAL SPLICES	394.000	EA
1360	511(B)2310	EPOXY COATED REINFORCING STEEL	23,420.000	LB
1370	512(A)3200	PAINTING EXISTING STRUCTURES	1.000	LSUM
1380	512(B)3300	COLLECTION AND HANDLING OF WASTE	1.000	LSUM
1390	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	666.000	SY
1400	517 9110	ELASTOMERIC COATING	450.000	SF
1410	518(B)0300	SEALED EXPANSION JOINTS	72.680	LF
1420	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	150.000	LF
1430	520(C)1400	EPOXY RESIN, ABOVE WATER	2.300	GAL
1440	521(A)2200	PNEUMATICALLY PLACED MORTAR	24.000	SY
1450	523(A)3200	SEALER CRACK PREPARATION	150.000	LF
1460	523(B)3300	SEALER RESIN	2.800	GAL
1470	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	19.000	SY
1480	545 0100	(PL)REPLACE BRIDGE ITEMS	1.000	LSUM
1490	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
0007	TRAFFIC CONTROL			
1500	857(C)9405	REMOVABLE PAVEMENT MARKING TAPE(6" WIDE)	41,453.000	LF
1510	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	17,731.000	LF
1520	858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	1,642.000	EA
1530	858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	930.000	EA
1540	871(B)2300	CONST.ZONE IMPACT ATTEN.	690.000	SD
1550	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	2,925.000	LF
1560	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	2,925.000	LF
1570	880(A)6220	ARROW DISPLAY(TYPE C)	480.000	SD
1580	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	9,006.000	SD
1590	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	2,668.000	SD
1600	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	2,950.000	SD
1610	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	768.000	SD
1620	880(E)6607	WARNING LIGHTS(TYPE B)	6,718.000	SD
1630	880(F)6700	DRUMS	26,280.000	SD
1640	880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	1,000.000	HOUR
1650	882 8100	(SP)SMART WORK ZONE SYSTEM	270.000	SD
1660	882 8105	(SP)SMART WK. ZONE SYS.-PORT.CHNG.MSG.SN	4,320.000	SD
1670	882 8110	(SP)SMART WK. ZONE SYS.-PORT.TRAF.SENSOR	2,160.000	SD
1680	882 8115	(SP)SMART WK ZONE SYS-PAN-TILT-ZOOM CMRA	540.000	SD
1690	882 8120	(SP)SMART WK. ZONE SYS.-WEBSITE SYSTEM	270.000	SD
1700	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	1,436.000	SD

Proposal:260112 **Let Date:**April 16, 2026 **Call Order:**655
J/P Num:31080(04) **Proj. Num:**NHPP-019N(176)PM
Counties:TULSA
Description:BRIDGE REHABILITATION
US-64: OVER MAIN ST, 49TH W AVE, AND 33RD W AVE
IN THE CITY OF SAND SPRINGS AND TULSA.
PROJECT LENGTH = 0.069 MILES

Line #		Item Description	Quantity	Unit
0008	TRAFFIC SIGNING AND STRIPING			
1710	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	14,194.000	LF
0009	TRAFFIC LIGHTING			
1720	802(A)0210	1" GALV.STEEL ELECT.COND. EXPOSED	750.000	LF
1730	802(E)0600	JUNCTION BOX(6" X 6" X 4")	13.000	EA
1740	803(A)1210	PULL BOX(SIZE I)	2.000	EA
1750	805(D)3504	(PL)REMOVE & RESET LIGHT POLE	3.000	EA
1760	809(B)7300	UNDERPASS LUMINAIRE	11.000	EA
1770	811 9130	1/C NO.10 ELECT.COND.	1,800.000	LF
0010	STAKING			
1780	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0011	CONSTRUCTION			
1790	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
1800	640(A)1200	FIELD OFFICE	1.000	EA
1810	641 2100	MOBILIZATION	1.000	LSUM