Proposal: 260116 **Let Date:** April 09, 2026 **Call Order:** 508

J/P Num: 39188(04) **Proj. Num:** MC-208C(147)MD

Counties: CADDO

Description: RESURFACE (ASPHALT)

US-277/SH-19: US-277: FROM 2.2 MILES SOUTH OF THE SH-19 INTERSECTION AND FROM 3.3 MILES NORTHEAST OF THE SH-8 INTERSECTION. SH-19: FROM 0.7 MILES WEST OF THE US-277 INTERSECTION.

PROJECT LENGTH = 3.70 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	411(C)1420	SUPERPAVE, TYPE S4(PG 70-28 OK)	6,700.000	TON
0020	411(H)1900	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	100.000	TON
0030	412 3100	COLD MILLING PAVEMENT	60,000.000	SY
0002	TRAFFIC			
0040	413(B)4300	RUMBLE STRIP-METHOD HMA-CYC GROUP	6.000	EAGP
0050	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	78,200.000	LF
0060	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	260.000	LF
0070	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	320.000	LF
0080	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,100.000	SD
0090	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	500.000	SD
0100	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,000.000	SD
0110	880(E)6600	WARNING LIGHTS(TYPE A)	1,500.000	SD
0120	880(G)6805	CHANNELIZER CONES	9,000.000	SD
0130	880(I)7000	FLAGGER	30.000	SD
0140	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	220.000	SD