Proposal:260122 **Let Date:**April 09, 2026 **Call Order:**563
J/P Num:30562(04) **Proj. Num:**STP-268C(124)PM
Counties:SEQUOYAH
Description:GRADE, DRAIN, AND SURFACE
SH-10A: FROM 1.5 MILES EAST OF THE SH-10 INTERSECTION,
EXTEND EAST NEAR TENKILLER STATE PARK.
PROJECT LENGTH = 4.368 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	129,723.000	CY
0030	202(C)2400	ROCK EXCAVATION	12,560.000	CY
0040	202(D)2500	UNCLASSIFIED BORROW	3,000.000	CY
0050	202(J)3110	QUARRY STONE EMBANKMENT	39,900.000	TON
0060	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0070	221(B)2300	TEMPORARY SILT FENCE	15,723.000	LF
0080	221(C)2400	TEMPORARY SEDIMENT FILTER	28.000	EA
0090	221(E)2600	TEMPORARY SILT DIKE	2,338.000	LF
0100	221(F)2710	TEMPORARY ROCK FILTER DAM TYPE 2	66.000	CY
0110	221(K)3203	TEMPORARY SEDIMENT CONTROL DEVICE	1.000	LSUM
0120	229 6100	DITCH LINER PROTECTION	1,838.000	LF
0130	230(A)7200	SOLID SLAB SODDING	122,214.000	SY
0140	232(A)9200	SEEDING METHOD A	7.000	AC
0150	233(A)0200	VEGETATIVE MULCHING	14.000	AC
0160	241 3100	MOWING	28.000	AC
0170	242 4101	STABILIZED CONSTRUCTION EXIT	6.000	EA
0180	303(A)1200	AGGREGATE BASE TYPE A	24,254.000	CY
0190	325 0100	SEPARATOR FABRIC	111,314.000	SY
0200	326(B)1300	GEOGRID REINFORCEMENT	111,314.000	SY
0210	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	11,145.000	TON
0220	407(B)7300	TACK COAT	25,749.000	GAL
0230	408 8100	PRIME COAT	67,916.000	GAL
0240	409(A)9200	FABRIC REINFORCEMENT	2,624.000	SY
0250	409(B)9300	BITUMINOUS BINDER	738.000	GAL
0260	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	42,084.000	TON
0270	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	15,127.000	TON
0280	412 3100	COLD MILLING PAVEMENT	6,999.000	SY
0290	413(A)4210	RUMBLE STRIP-CENTERLINE HMA-CON	20,520.000	LF
0300	413(B)4310	RUMBLE STRIP-METHOD HMA-CYC	40,991.000	LF
0310	501(G)1810	CLSM BACKFILL	10.000	CY
0320	509(A)0200	CLASS AA CONCRETE	12.000	CY
0330	509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	5.000	CY
0340	509(D)0500	CLASS C CONCRETE	249.000	CY
0350	601(B)1220	TYPE I-A PLAIN RIPRAP	256.000	TON
0360	601(C)1300	TYPE I-A FILTER BLANKET	74.000	TON
0370	609(A)4270	CONC.CURB(8" BARRIER-INTEGRAL)	185.000	LF
0380	609(B)4355	2'-8" COMB.CRB.& GUT.(4" MNTBLE)	1,285.000	LF
0390	609(B)4375	2'-8" COMB.CRB.& GUT.(8" BARRIER)	2,729.000	LF
0400	610(B)5310	6" CONCRETE DRIVEWAY	1,724.000	SY
0410	610(C)5400	4" CONCRETE DIVIDING STRIP	31.000	SY
0420	611(A)7210	MANHOLE (4' DIA.)	2.000	EA
0430	611(A)7215	MANHOLE (5' DIA.)	1.000	EA
0440	611(B)7247	ADD'L DEPTH PRECAST RND 5' MANHOLE	2.000	VF
0450	611(G)0354	INLET (SMD-TYPE 2)	15.000	EA
0460	611(G)0358	INLET (SMD-TYPE 2A)	3.000	EA

Proposal:260122 **Let Date:**April 09, 2026 **Call Order:**563
J/P Num:30562(04) **Proj. Num:**STP-268C(124)PM
Counties:SEQUOYAH
Description:GRADE, DRAIN, AND SURFACE
SH-10A: FROM 1.5 MILES EAST OF THE SH-10 INTERSECTION,
EXTEND EAST NEAR TENKILLER STATE PARK.
PROJECT LENGTH = 4.368 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0470	611(G)0362	INLET (SMD-TYPE 2B)	1.000	EA
0480	611(G)7754	INLET CI DES. 2 (STD)	2.000	EA
0490	611(G)7758	INLET CI DES. 2 (B)	8.000	EA
0500	611(G)7770	INLET CI DES. 2 (2B)	1.000	EA
0510	611(H)0414	ADD'L DEPTH IN INLET CI DES. 2	25.000	VF
0520	611(L)1600	JUNCTION BOXES	219.000	CF
0530	613(A)5208	18" R.C.PIPE CLASS III	1,950.000	LF
0540	613(A)5216	24" R.C.PIPE CLASS III	228.000	LF
0550	613(A)5220	30" R.C.PIPE CLASS III	106.000	LF
0560	613(A)5224	36" R.C.PIPE CLASS III	554.000	LF
0570	613(A)5228	42" R.C.PIPE CLASS III	232.000	LF
0580	613(A)5350	22" X 13" R.C.PIPE ARCH CLASS A-III	1,516.000	LF
0590	613(A)5358	28" X 18" R.C.PIPE ARCH CLASS A-III	780.000	LF
0600	613(A)5366	36" X 22" R.C.PIPE ARCH CLASS A-III	478.000	LF
0610	613(A)5370	43" X 26" R.C.PIPE ARCH CLASS A-III	88.000	LF
0620	613(B)5516	24" CORR. GALV. STEEL PIPE	52.000	LF
0630	613(B)5524	30" CORR. GALV. STEEL PIPE	20.000	LF
0640	613(B)5532	42" CORR. GALV. STEEL PIPE	32.000	LF
0650	613(B)5604	21" X 15" CORR. GALV. STEEL PIPE ARCH	92.000	LF
0660	613(B)5612	28" X 20" CORR. GALV. STEEL PIPE ARCH	98.000	LF
0670	613(H)6200	6" PERFORATED PIPE UNDERDRAIN ROUND	1,639.000	LF
0680	613(I)6305	6" NON-PERF.PIPE UNDERDRAIN RND.	547.000	LF
0690	613(J)6400	EDGE DRAIN CONDUIT-PERFORATED	1,585.000	LF
0700	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0710	613(L)6724	30" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0720	613(M)6900	TYPE A3 CULVERT END TREATMENT	5.000	EA
0730	613(M)6904	TYPE B3 CULVERT END TREATMENT	1.000	EA
0740	613(M)6912	TYPE D3 CULVERT END TREATMENT	4.000	EA
0750	613(M)6960	TYPE A4 CULVERT END TREATMENT	17.000	EA
0760	613(M)6964	TYPE B4 CULVERT END TREATMENT	8.000	EA
0770	613(M)6968	TYPE C4 CULVERT END TREATMENT	4.000	EA
0780	613(M)6972	TYPE D4 CULVERT END TREATMENT	4.000	EA
0790	613(M)6992	TYPE DD4 CULVERT END TREATMENT	2.000	EA
0800	613(M)7004	TYPE A6 CULVERT END TREATMENT	61.000	EA
0810	613(M)7008	TYPE B6 CULVERT END TREATMENT	25.000	EA
0820	613(M)7012	TYPE C6 CULVERT END TREATMENT	2.000	EA
0830	613(Q)7500	OUTLET LATERAL HEADWALL	4.000	EA
0840	616(P)4160	18" HDPE PIPE	926.000	LF
0850	616(P)4164	24" HDPE PIPE	92.000	LF
0860	616(P)4170	30" HDPE PIPE	146.000	LF
0870	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0880	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	82,579.000	SY
0890	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	851.000	SY
0900	619(C)6600	SAWING PAVEMENT	11,208.000	LF
0910	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	2,450.000	LF
0920	623(G)1820	GUARDRAIL END TREATMENT (31")	6.000	EA

Proposal:260122 **Let Date:**April 09, 2026 **Call Order:**563
J/P Num:30562(04) **Proj. Num:**STP-268C(124)PM
Counties:SEQUOYAH
Description:GRADE, DRAIN, AND SURFACE
SH-10A: FROM 1.5 MILES EAST OF THE SH-10 INTERSECTION,
EXTEND EAST NEAR TENKILLER STATE PARK.
PROJECT LENGTH = 4.368 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0930	624 3100	(PL) ORNAMENTAL FENCE	370.000	LF
0940	624(A)3200	FENCE-STYLE WWF	24.000	LF
0950	624(B)3330	GATES-STYLE WWF (4.5'HIGH X 10'LONG)	2.000	EA
0960	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	500.000	LF
0970	628(B)7300	HIGH-TENSION CABLE BARRIER(TL-4)	1,327.000	LF
0980	628(C)7400	END ANCHORS	6.000	EA
0990	628(E)7600	CABLE BARRIER TENSION METER	3.000	EA
1000	629(A)7200	MAILBOX INSTALLATION-SINGLE	32.000	EA
1010	629(B)7300	MAILBOX INSTALLATION-MULTIPLE	13.000	EA
1020	629(C)7400	REMOVAL OF MAILBOX INSTALLATION	65.000	EA
1030	629(E)7600	MAILBOX	65.000	EA
1040	853 5175	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	60.000	EA

Proposal:260122 **Let Date:**April 09, 2026 **Call Order:**563
J/P Num:30562(04) **Proj. Num:**STP-268C(124)PM
Counties:SEQUOYAH
Description:GRADE, DRAIN, AND SURFACE
SH-10A: FROM 1.5 MILES EAST OF THE SH-10 INTERSECTION,
EXTEND EAST NEAR TENKILLER STATE PARK.
PROJECT LENGTH = 4.368 MILES

Line #		Item Description	Quantity	Unit
0002	WATERLINE RELOCATION			
1050	221(B)2300	TEMPORARY SILT FENCE	25,000.000	LF
1060	230(A)7200	SOLID SLAB SODDING	3,000.000	SY
1070	232(A)9200	SEEDING METHOD A	12.000	AC
1080	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	35.000	TON
1090	414(G)5800	P.C. CONCRETE FOR PAVEMENT	300.000	CY
1100	613(S)7700	STANDARD BEDDING MATERIAL, CLASS B	1,680.000	CY
1110	616(B)2320	2" POLYVINYL CHLORIDE (PVC) PIPE	855.000	LF
1120	616(B)2328	3" POLYVINYL CHLORIDE (PVC) PIPE	2,149.000	LF
1130	616(B)2332	4" POLYVINYL CHLORIDE (PVC) PIPE	6,217.000	LF
1140	616(B)2336	6" POLYVINYL CHLORIDE (PVC) PIPE	3,912.000	LF
1150	616(B)2340	8" POLYVINYL CHLORIDE (PVC) PIPE	2,762.000	LF
1160	616(B)2344	10" POLYVINYL CHLORIDE (PVC) PIPE	6,772.000	LF
1170	616(D)2534	2" AIR RELIEF VALVE ASSEMBLY & METER CAN	8.000	EA
1180	616(D)2630	2" GATE VALVE	30.000	EA
1190	616(D)2642	4" GATE VALVE	47.000	EA
1200	616(D)2646	6" GATE VALVE	20.000	EA
1210	616(D)2650	8" GATE VALVE	12.000	EA
1220	616(D)2654	10" GATE VALVE	9.000	EA
1230	616(E)2905	1" CORPORATION STOPS	15.000	EA
1240	616(F)3005	METER INSTALLATION 5/8"	44.000	EA
1250	616(G)3100	FIRE HYDRANTS	3.000	EA
1260	616(I)3300	2" STEEL CASING	400.000	LF
1270	616(I)3306	4" STEEL CASING	2,647.000	LF
1280	616(I)3309	6" STEEL CASING	330.000	LF
1290	616(I)3312	8" STEEL CASING	1,075.000	LF
1300	616(I)3318	12" STEEL CASING	635.000	LF
1310	616(I)3324	16" STEEL CASING	480.000	LF
1320	616(I)3327	18" STEEL CASING	320.000	LF
1330	616(O)3901	CONNECT TO EXISTING WATER LINE	39.000	EA
1340	616(P)4101	1" POLYETHYLENE WATER SERVICE PIPE	1,000.000	LF
1350	616(P)4108	2" HDPE PIPE	2,647.000	LF
1360	616(P)4116	3" HDPE PIPE	330.000	LF
1370	616(P)4128	4" HDPE PIPE	1,075.000	LF
1380	616(P)4136	6" HDPE PIPE	810.000	LF
1390	616(P)4140	6" HDPE PIPE (BORED)	130.000	LF
1400	616(P)4148	8" HDPE PIPE	480.000	LF
1410	616(P)4152	10" HDPE PIPE	320.000	LF
1420	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	200.000	SY

Proposal:260122 **Let Date:**April 09, 2026 **Call Order:**563
J/P Num:30562(04) **Proj. Num:**STP-268C(124)PM
Counties:SEQUOYAH
Description:GRADE, DRAIN, AND SURFACE
SH-10A: FROM 1.5 MILES EAST OF THE SH-10 INTERSECTION,
EXTEND EAST NEAR TENKILLER STATE PARK.
PROJECT LENGTH = 4.368 MILES

Line #		Item Description	Quantity	Unit
0003	SIGNING AND STRIPING			
1430	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	66.000	EA
1440	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	19.000	EA
1450	850(A)1200	SHEET ALUMINUM SIGNS	556.430	SF
1460	851(C)2420	2 1/4" SQUARE TUBE POST	1,132.000	LF
1470	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	91,026.000	LF
1480	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	60.000	LF
1490	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	191.000	LF
0004	TRAFFIC CONTROL			
1500	857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	326,200.000	LF
1510	857(C)9405	REMOVABLE PAVEMENT MARKING TAPE(6" WIDE)	81,550.000	LF
1520	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	362,200.000	LF
1530	858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	10,000.000	EA
1540	858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	10,000.000	EA
1550	871(B)2300	CONST.ZONE IMPACT ATTEN.	2,410.000	SD
1560	871(C)2410	RELOCATION OF IMPACT ATTENUATOR	66.000	EA
1570	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	6,000.000	LF
1580	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	25,000.000	LF
1590	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	4,940.000	SD
1600	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	11,530.000	SD
1610	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	6,030.000	SD
1620	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	5,010.000	SD
1630	880(E)6600	WARNING LIGHTS(TYPE A)	16,050.000	SD
1640	880(F)6700	DRUMS	17,820.000	SD
1650	880(G)6805	CHANNELIZER CONES	11,400.000	SD
1660	880(I)7000	FLAGGER	840.000	SD
1670	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	1,000.000	SD
0005	STAKING			
1680	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
1690	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
1700	641 2110	MOBILIZATION	1.000	LSUM