Proposal:260130 **Let Date:**May 14, 2026 **Call Order:**810
J/P Num:20953(04) **Proj. Num:**STP-108C(099)PM
Counties:CADDO, GRADY
Description:GRADE, DRAIN, AND SURFACE
US-277: FROM 4.2 MILES NE OF THE SH-8 JUNCTION,
EXTEND EAST NEAR CEMENT.
PROJECT LENGTH = 3.770 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	487,404.000	CY
0030	202(C)2400	ROCK EXCAVATION	8,247.000	CY
0040	202(D)2500	UNCLASSIFIED BORROW	82,046.000	CY
0050	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0060	221(B)2300	TEMPORARY SILT FENCE	33,054.000	LF
0070	221(E)2600	TEMPORARY SILT DIKE	2,681.000	LF
0080	221(F)2700	TEMPORARY ROCK FILTER DAM TYPE 1	8.000	CY
0090	221(F)2710	TEMPORARY ROCK FILTER DAM TYPE 2	6.000	CY
0100	221(G)2800	TEMPORARY FIBER LOG	17,774.000	LF
0110	221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	3.000	EA
0120	229 6100	DITCH LINER PROTECTION	15,052.870	LF
0130	230(A)7200	SOLID SLAB SODDING	237,827.000	SY
0140	232(A)9200	SEEDING METHOD A	2.510	AC
0150	232(B)9300	SEEDING METHOD B	49.130	AC
0160	233(A)0200	VEGETATIVE MULCHING	51.640	AC
0170	241 3100	MOWING	98.260	AC
0180	242 4101	STABILIZED CONSTRUCTION EXIT	4.000	EA
0190	303(A)1200	AGGREGATE BASE TYPE A	21,626.000	CY
0200	307(K)4200	STABILIZED SUBGRADE	119,489.000	SY
0210	310(B)5300	SUBGRADE, METHOD B	7,884.000	SY
0220	326(C)1100	(SP) WOVEN GEOSYNTHETIC REINFORCEMENT FABRIC	110,942.000	SY
0230	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	16,334.000	TON
0240	407(B)7300	TACK COAT	16,784.000	GAL
0250	408 8100	PRIME COAT	70,386.000	GAL
0260	411(B)1320	SUPERPAVE, TYPE S3(PG 70-28 OK)	8,610.000	TON
0270	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	25,369.000	TON
0280	411(C)1420	SUPERPAVE, TYPE S4(PG 70-28 OK)	5,743.000	TON
0290	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	9,966.000	TON
0300	411(H)1900	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	298.000	TON
0310	412 3100	COLD MILLING PAVEMENT	44,342.000	SY
0320	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	86.000	CY
0330	504(E)5520	42" F-SHAPED PARAPET	156.800	LF
0340	509(A)0200	CLASS AA CONCRETE	676.800	CY
0350	509(D)0500	CLASS C CONCRETE	2,799.090	CY
0360	511(A)2200	REINFORCING STEEL	89,420.000	LB
0370	511(B)2300	EPOXY COATED REINFORCING STEEL	7,180.000	LB
0380	514(J)6100	TEMPORARY SHEET PILING	1.000	LSUM
0390	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	92.000	SY
0400	601(B)1220	TYPE I-A PLAIN RIPRAP	1,101.580	TON
0410	601(C)1300	TYPE I-A FILTER BLANKET	334.740	TON
0420	601(I)1700	FILTER FABRIC (RIPRAP)	1,244.000	SY
0430	609(B)4370	2'-8" COMB.CRB.& GUT.(6" MNTBLE)	1,284.000	LF
0440	611(A)7210	MANHOLE (4' DIA.)	4.000	EA
0450	611(B)7300	ADD'L.DEPTH IN MANHOLE (4' DIA.)	11.320	VF
0460	611(G)0354	INLET (SMD-TYPE 2)	6.000	EA

Proposal:260130 **Let Date:**May 14, 2026 **Call Order:**810
J/P Num:20953(04) **Proj. Num:**STP-108C(099)PM
Counties:CADDO, GRADY
Description:GRADE, DRAIN, AND SURFACE
US-277: FROM 4.2 MILES NE OF THE SH-8 JUNCTION,
EXTEND EAST NEAR CEMENT.
PROJECT LENGTH = 3.770 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0470	611(G)7710	INLET CI DES. 1 (STD)	1.000	EA
0480	611(G)7966	INLET GPI TYPE 2 (DES. 10)	1.000	EA
0490	611(H)0410	ADD'L DEPTH IN INLET CI DES. 1	1.250	VF
0500	611(H)0474	ADD'L DEPTH IN INLET GPI TYPE 2	2.710	VF
0510	613(A)5208	18" R.C.PIPE CLASS III	1,844.950	LF
0520	613(A)5216	24" R.C.PIPE CLASS III	211.000	LF
0530	613(A)5220	30" R.C.PIPE CLASS III	240.000	LF
0540	613(A)5224	36" R.C.PIPE CLASS III	207.000	LF
0550	613(A)5264	18" R.C.PIPE CLASS IV	160.000	LF
0560	613(A)5314	24" R.C.PIPE CLASS V	513.000	LF
0570	613(A)5318	36" R.C.PIPE CLASS V	999.000	LF
0580	613(A)5322	42" R.C.PIPE CLASS V	235.000	LF
0590	613(A)5350	22" X 13" R.C.PIPE ARCH CLASS A-III	45.000	LF
0600	613(B)5508	18" CORR. GALV. STEEL PIPE	546.000	LF
0610	613(B)5528	36" CORR. GALV. STEEL PIPE	48.000	LF
0620	613(J)6400	EDGE DRAIN CONDUIT-PERFORATED	225.000	LF
0630	613(K)6500	EDGE DRAIN OUTLET LATERAL-NONPERFORATED	100.000	LF
0640	613(L)6612	22" X 13" PREFAB. CULVERT END SEC., ARCH	4.000	EA
0650	613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	45.000	EA
0660	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	14.000	EA
0670	613(L)6724	30" PREFAB. CULVERT END SEC., ROUND	6.000	EA
0680	613(L)6728	36" PREFAB. CULVERT END SEC., ROUND	9.000	EA
0690	613(L)6732	42" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0700	613(Q)7500	OUTLET LATERAL HEADWALL	1.000	EA
0710	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0720	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	30,768.000	SY
0730	619(B)6396	REMOVAL OF GUARDRAIL	360.000	LF
0740	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	350.000	LF
0750	623(G)1820	GUARDRAIL END TREATMENT (31")	4.000	EA
0760	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	4.000	EA
0770	624(A)3200	FENCE-STYLE WWF	1,522.000	LF
0780	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	31,474.000	LF
0790	624(C)3410	FENCE-STYLE SWF (6 BARBED WIRE)	3,369.000	LF
0002	BRIDGE 'A' - NBI NO. 02099			
0800	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0003	BRIDGE 'B' - NBI NO. 23976			
0810	545 0111	(PL)REPLACE BRIDGE ITEM (TYPE A)	4.000	EA

Proposal:260130 **Let Date:**May 14, 2026 **Call Order:**810
J/P Num:20953(04) **Proj. Num:**STP-108C(099)PM
Counties:CADDO, GRADY
Description:GRADE, DRAIN, AND SURFACE
US-277: FROM 4.2 MILES NE OF THE SH-8 JUNCTION,
EXTEND EAST NEAR CEMENT.
PROJECT LENGTH = 3.770 MILES

Line #		Item Description	Quantity	Unit
0004	TRAFFIC PERMANENT			
0820	413(A)4200	RUMBLE STRIP-METHOD HMA-CON	18,113.000	LF
0830	413(B)4310	RUMBLE STRIP-METHOD HMA-CYC	35,986.000	LF
0840	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	21.000	EA
0850	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	2.000	EA
0860	850(A)1200	SHEET ALUMINUM SIGNS	400.200	SF
0870	851(C)2430	2 1/2" SQUARE TUBE POST	655.000	LF
0880	853 5175	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	20.000	EA
0890	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	117,819.000	LF
0900	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	146.000	LF
0005	TRAFFIC TEMPORARY			
0910	857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	9,929.000	LF
0920	857(C)9405	REMOVABLE PAVEMENT MARKING TAPE(6" WIDE)	2,235.000	LF
0930	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	5,507.000	LF
0940	871(B)2300	CONST.ZONE IMPACT ATTEN.	1,180.000	SD
0950	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	900.000	LF
0960	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	2,650.000	LF
0970	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	21,055.000	SD
0980	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	22,925.000	SD
0990	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	15,965.000	SD
1000	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	18,565.000	SD
1010	880(D)6500	VERTICAL PANELS	6,345.000	SD
1020	880(E)6600	WARNING LIGHTS(TYPE A)	47,255.000	SD
1030	880(F)6700	DRUMS	3,517.000	SD
1040	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	1,800.000	SD
0006	STAKING			
1050	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0007	CONSTRUCTION			
1060	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
1070	640(A)1210	FIELD OFFICE	1.000	EA
1080	641 2110	MOBILIZATION	1.000	LSUM