Proposal: 260140 **Let Date:** April 16, 2026 **Call Order:** 685
J/P Num: 39240(04) **Proj. Num:** MC-3500(220)MD
Counties: LOGAN
Description: RESURFACE (ASPHALT)
I-35: AT THE INTERSECTION OF SH-33,
EXTEND NORTH AND SOUTH NEAR GUTHRIE.
PROJECT LENGTH = 1.050 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(H)2900	EARTHWORK	1.000	LSUM
0020	221(B)2300	TEMPORARY SILT FENCE	100.000	LF
0030	230(A)7200	SOLID SLAB SODDING	125.000	SY
0040	407(C)7500	NT TACK MATERIAL	2,500.000	GAL
0050	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	50.000	TON
0060	411(C)1420	SUPERPAVE, TYPE S4(PG 70-28 OK)	2,800.000	TON
0070	412 3100	COLD MILLING PAVEMENT	25,000.000	SY
0002	TRAFFIC			
0080	805(D)3536	(PL)REMOVE & RESET GROUND MOUNTED SIGN	1.000	EA
0090	828(B)0300	LOOP DETECTOR WIRE	1,800.000	LF
0100	853 5155	DELINEATORS(TYPE 2, CODE 3, FLEXIBLE)	3.000	EA
0110	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	15,500.000	LF
0120	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	7,500.000	LF
0130	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	80.000	LF
0140	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	6.000	EA
0150	857(E)9630	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-2	1,000.000	EA
0160	858(A)0264	PAVE.MARKERS CLASS C TYPE 2-A	170.000	EA
0170	876(A)3210	(PL)TRUCK MOUNTED ATTENUATOR	60.000	SD
0180	880(A)6210	ARROW DISPLAY(TYPE B)	180.000	SD
0190	880(A)6220	ARROW DISPLAY(TYPE C)	180.000	SD
0200	880(J)7100	(SP) CONSTRUCTION TRAFFIC CONTROL	60.000	SD
0210	880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	2,000.000	HOUR
0220	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	240.000	SD
0003	CONSTRUCTION			
0230	641 2110	MOBILIZATION	1.000	LSUM