Proposal: 260141 **Let Date:** May 07, 2026 **Call Order:** 718
J/P Num: 38010(04) **Proj. Num:** TAP-220D(122)TP
Counties: CUSTER
Description: PEDESTRIAN AND BIKE IMPROVEMENTS
CITY STREETS (N MISSOURI ST/W ROH ST/W ORIENT ST): AT MULTIPLE LOCATIONS IN THE CITY OF THOMAS.
PROJECT LENGTH = 0.85 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(A)2200	UNCLASSIFIED EXCAVATION	200.000	CY
0020	202(D)2500	UNCLASSIFIED BORROW	200.000	CY
0030	221(B)2300	TEMPORARY SILT FENCE	628.330	LF
0040	230(A)7200	SOLID SLAB SODDING	12,322.390	SY
0050	303(A)1200	AGGREGATE BASE TYPE A	162.850	CY
0060	325 0100	SEPARATOR FABRIC	100.000	SY
0070	326(B)1300	GEOGRID REINFORCEMENT	100.000	SY
0080	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	80.000	TON
0090	414(E)5600	FULL DEPTH P.C.C. PATCH (PLACEMENT)	79.510	SY
0100	414(G)5800	P.C. CONCRETE FOR PAVEMENT	17.750	CY
0110	509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	24.000	CY
0120	609(A)4250	CONC.CURB(6" MNTBLE-INTEGRAL)	61.590	LF
0130	610(A)5200	4" CONCRETE SIDEWALK	2,319.690	SY
0140	610(B)5310	6" CONCRETE DRIVEWAY	779.740	SY
0150	610(I)6000	TACTILE WARNING DEVICE-NEW	350.000	SF
0160	612(I)4000	WATER METER RESET	1.000	EA
0170	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0180	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	12.110	SY
0190	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	136.700	SY
0200	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	169.370	SY
0210	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	197.330	SY
0220	619(B)6386	REMOVAL OF GRAVEL DRIVEWAY	224.320	SY
0230	619(B)6404	REMOVAL OF SIDEWALK	1,185.580	SY
0240	622(A)0200	PIPE RAILING	44.000	LF
0002	TRAFFIC			
0250	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	12.000	EA
0260	850(A)1200	SHEET ALUMINUM SIGNS	37.380	SF
0270	851(C)2415	2" SQUARE TUBE POST	84.000	LF
0280	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	568.840	LF
0290	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	2,350.000	SD
0300	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,500.000	SD
0310	880(E)6610	WARNING LIGHTS(TYPE C)	9,400.000	SD
0320	880(F)6700	DRUMS	9,400.000	SD
0330	880(G)6805	CHANNELIZER CONES	9,400.000	SD
0340	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	328.000	SD
0003	STAKING			
0350	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0004	CONSTRUCTION			
0360	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0370	641 2110	MOBILIZATION	1.000	LSUM