Proposal: 260145 **Let Date:** June 11, 2026 **Call Order:** 115
J/P Num: 33919(04) **Proj. Num:** STP-222D(053)CI
Counties: DEWEY
Description: BRIDGE AND APPROACHES
COUNTY ROAD (EW 0610 RD): OVER CAMP CREEK,
6.33 MILES WEST OF US-183 JUNCTION NEAR SEILING.
PROJECT LENGTH = 0.189 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(H)2900	EARTHWORK	1.000	LSUM
0030	221(B)2300	TEMPORARY SILT FENCE	800.000	LF
0040	221(E)2600	TEMPORARY SILT DIKE	300.000	LF
0050	230(A)7200	SOLID SLAB SODDING	5,700.000	SY
0060	233(A)0200	VEGETATIVE MULCHING	1.190	AC
0070	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	615.000	TON
0080	509(D)0500	CLASS C CONCRETE	10.000	CY
0090	601(B)1200	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	253.000	TON
0100	613(B)5508	18" CORR. GALV. STEEL PIPE	50.000	LF
0110	613(B)5516	24" CORR. GALV. STEEL PIPE	60.000	LF
0120	613(M)6900	TYPE A3 CULVERT END TREATMENT	2.000	EA
0130	613(M)6904	TYPE B3 CULVERT END TREATMENT	2.000	EA
0002	BRIDGE 'A'			
0140	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	320.000	CY
0150	501(F)1700	GRANULAR BACKFILL	280.000	CY
0160	503(A)4230	PRESTRESSED CONCRETE BEAMS (TYPE III)	319.000	LF
0170	504(D)5410	CONCRETE RAIL (TR3)	270.500	LF
0180	506(A)7200	STRUCTURAL STEEL	660.000	LB
0190	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	4.000	EA
0200	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	4.000	EA
0210	509(A)0210	CLASS AA CONCRETE	71.100	CY
0220	509(B)0320	CLASS A CONCRETE	172.600	CY
0230	511(A)2210	REINFORCING STEEL	39,540.000	LB
0240	514(A)5210	PILES, FURNISHED (HP 10X42)	144.000	LF
0250	514(A)5220	PILES, FURNISHED (HP 12X53)	448.000	LF
0260	514(B)5310	PILES, DRIVEN (HP 10X42)	144.000	LF
0270	514(B)5320	PILES, DRIVEN (HP 12X53)	448.000	LF
0280	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0290	601(B)1210	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	1,803.000	TON
0300	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	66.000	LF
0310	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	40.000	LF
0320	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0330	623(F)1748	GUARDRAIL ANCHOR UNIT (TYPE II)	4.000	EA
0003	TRAFFIC			
0340	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	480.000	SD
0350	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	720.000	SD
0360	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,200.000	SD
0370	880(E)6600	WARNING LIGHTS(TYPE A)	2,640.000	SD
0004	STAKING			
0380	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM

Proposal: 260145 **Let Date:** June 11, 2026 **Call Order:** 115
J/P Num: 33919(04) **Proj. Num:** STP-222D(053)CI
Counties: DEWEY
Description: BRIDGE AND APPROACHES
COUNTY ROAD (EW 0610 RD): OVER CAMP CREEK,
6.33 MILES WEST OF US-183 JUNCTION NEAR SEILING.
PROJECT LENGTH = 0.189 MILES

Line #		Item Description	Quantity	Unit
0005	CONSTRUCTION			
0390	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0400	641 2110	MOBILIZATION	1.000	LSUM