Proposal: 260147 **Let Date:** June 11, 2026 **Call Order:** 125
J/P Num: 34237(04) **Proj. Num:** STP-238C(104)PM
Counties: KIOWA
Description: BRIDGE AND APPROACHES
SH-54: OVER OTTER CREEK, 1.6 MILES NORTH
OF THE SH-49 JUNCTION NEAR COOPERTON.
PROJECT LENGTH = 0.407 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	11,528.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	500.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	1,510.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	1,092.000	LF
0070	221(F)2710	TEMPORARY ROCK FILTER DAM TYPE 2	54.000	CY
0080	230(A)7200	SOLID SLAB SODDING	32,019.000	SY
0090	233(A)0200	VEGETATIVE MULCHING	6.620	AC
0100	241 3100	MOWING	13.240	AC
0110	307(K)4200	STABILIZED SUBGRADE	10,786.000	SY
0130	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	40.000	TON
0140	407(B)7300	TACK COAT	2,278.000	GAL
0150	408 8100	PRIME COAT	4,493.000	GAL
0160	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	4,551.000	TON
0170	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	1,134.000	TON
0180	509(D)0500	CLASS C CONCRETE	101.000	CY
0190	601(A)1100	TYPE I PLAIN RIPRAP	33.000	TON
0200	613(A)5208	18" R.C.PIPE CLASS III	54.000	LF
0210	613(A)5224	36" R.C.PIPE CLASS III	216.000	LF
0220	613(A)5350	22" X 13" R.C.PIPE ARCH CLASS A-III	50.000	LF
0230	613(A)5366	36" X 22" R.C.PIPE ARCH CLASS A-III	60.000	LF
0240	613(H)6210	8" PERFORATED PIPE UNDERDRAIN ROUND	188.000	LF
0250	613(I)6315	8" NON-PERF.PIPE UNDERDRAIN RND.	63.000	LF
0260	613(M)6992	TYPE DD4 CULVERT END TREATMENT	2.000	EA
0270	613(M)7004	TYPE A6 CULVERT END TREATMENT	4.000	EA
0280	613(M)7008	TYPE B6 CULVERT END TREATMENT	2.000	EA
0290	613(Q)7500	OUTLET LATERAL HEADWALL	1.000	EA
0300	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0310	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	6,923.000	SY
0320	619(B)6396	REMOVAL OF GUARDRAIL	662.000	LF
0330	624(C)3410	FENCE-STYLE SWF (6 BARBED WIRE)	1,127.000	LF
0340	629(D)7500	REMOVE AND RESET MAILBOX	2.000	EA
0002	BRIDGE			
0350	202(A)2210	UNCLASSIFIED EXCAVATION	1,760.000	CY
0360	501(A)1210	STRUCTURAL EXCAVATION UNCLASSIFIED	371.000	CY
0370	502 3101	TEMPORARY EARTH RETAINAGE	50.000	LF
0380	509(A)0210	CLASS AA CONCRETE	734.600	CY
0390	511(A)2210	REINFORCING STEEL	121,610.000	LB
0400	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0003	TRAFFIC SIGNING AND STRIPING			
0410	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	8,000.000	LF

Proposal: 260147 **Let Date:** June 11, 2026 **Call Order:** 125
J/P Num: 34237(04) **Proj. Num:** STP-238C(104)PM
Counties: KIOWA
Description: BRIDGE AND APPROACHES
SH-54: OVER OTTER CREEK, 1.6 MILES NORTH
OF THE SH-49 JUNCTION NEAR COOPERTON.
PROJECT LENGTH = 0.407 MILES

Line #		Item Description	Quantity	Unit
0004	TRAFFIC CONTROL			
0420	413(A)4210	RUMBLE STRIP-CENTERLINE HMA-CON	2,158.000	LF
0430	823 6100	(SP)PORTABLE TRAFFIC SIGNAL SYSTEM	210.000	SD
0440	828 0110	(PL)DETECTION SYSTEM (RADAR)	1.000	LSUM
0450	857(A)9200	CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE)	10,852.000	LF
0460	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	11,082.000	LF
0470	858(A)0216	PAVE.MARKERS CLASS A TYPE 2-A	208.000	EA
0480	871(B)2300	CONST.ZONE IMPACT ATTEN.	840.000	SD
0490	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	2,472.000	LF
0500	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	2,412.000	LF
0510	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	3,780.000	SD
0520	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	840.000	SD
0530	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	5,250.000	SD
0540	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	3,780.000	SD
0550	880(E)6607	WARNING LIGHTS(TYPE B)	10,500.000	SD
0560	880(G)6805	CHANNELIZER CONES	7,350.000	SD
0570	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	448.000	SD
0005	STAKING			
0580	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
0590	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0600	641 2110	MOBILIZATION	1.000	LSUM