Proposal:260149 **Let Date:**June 11, 2026 **Call Order:**135
J/P Num:27108(04) **Proj. Num:**NHPP-013N(237)FP
Counties:MUSKOGEE
Description:GRADE, DRAIN, SURFACE AND BRIDGE
US-69: FROM 0.52 MILES NORTH OF THE SH-165 INTERCHANGE,
EXTEND NORTH IN THE CITY OF MUSKOGEE.
PROJECT LENGTH = 2.463 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	64,230.000	CY
0030	202(E)2600	SELECT BORROW	3,000.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	6,421.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	1,247.000	LF
0070	221(F)2700	TEMPORARY ROCK FILTER DAM TYPE 1	28.000	CY
0080	221(G)2800	TEMPORARY FIBER LOG	3,024.000	LF
0090	221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	37.000	EA
0100	230(A)7200	SOLID SLAB SODDING	108,628.000	SY
0110	233(A)0200	VEGETATIVE MULCHING	46.000	AC
0120	241 3100	MOWING	46.000	AC
0130	303(A)1200	AGGREGATE BASE TYPE A	33,483.000	CY
0140	317 7100	CEMENT TREATED BASE	141,679.000	SY
0150	326(C)1100	(SP) WOVEN GEOSYNTHETIC REINFORCEMENT FABRIC	175,321.000	SY
0160	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	26,805.000	TON
0170	408 8100	PRIME COAT	93,730.000	GAL
0180	411(I)2005	SUPERPAVE, TYPE S4(PATCH)(PG70-28OK)	246.000	TON
0190	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	32,060.000	SY
0200	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	107,917.000	SY
0210	414(G)5800	P.C. CONCRETE FOR PAVEMENT	47,006.000	CY
0220	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	12.000	CY
0230	504(F)5600	HANDRAILING	685.000	LF
0240	509(A)0200	CLASS AA CONCRETE	336.000	CY
0250	509(D)0500	CLASS C CONCRETE	39.000	CY
0260	510(C)1420	SLOPE WALL (4")	300.000	SY
0270	510(D)1510	MSE RETAINING WALL	604.500	SY
0280	511(B)2300	EPOXY COATED REINFORCING STEEL	26,488.000	LB
0290	601(B)1220	TYPE I-A PLAIN RIPRAP	80.000	TON
0300	601(C)1300	TYPE I-A FILTER BLANKET	20.000	TON
0310	609(A)4230	CONC.CURB(6" BARRIER-INTEGRAL)	7,722.000	LF
0320	610(A)5200	4" CONCRETE SIDEWALK	5,207.000	SY
0330	610(B)5300	6" CONCRETE DRIVEWAY (H.E.S.)	13,272.000	SY
0340	610(B)5320	8" CONCRETE DRIVEWAY	1,180.000	SY
0350	610(C)5430	DECORATIVE MEDIAN CONCRETE	2,347.000	SY
0360	611(A)7210	MANHOLE (4' DIA.)	1.000	EA
0370	611(A)7215	MANHOLE (5' DIA.)	2.000	EA
0380	611(A)7230	MANHOLE (8' DIA.)	3.000	EA
0390	611(B)7320	ADD'L.DEPTH IN MANHOLE (8' DIA.)	7.000	VF
0400	611(G)0354	INLET (SMD-TYPE 2)	11.000	EA
0410	611(G)0358	INLET (SMD-TYPE 2A)	5.000	EA
0420	611(G)0610	PRECAST INLET PJB 6' WIDE (DES. 2 STD)	5.000	EA
0430	611(G)0614	PRECAST INLET PJB 6' WIDE (DES. 2 B)	14.000	EA
0440	611(G)0622	PRECAST INLET PJB 6' WIDE (DES. 2 D)	1.000	EA
0450	611(G)0630	PRECAST INLET PJB 6' WIDE (DES. 2 2C)	1.000	EA
0460	611(G)0638	PRECAST INLET PJB 6' WIDE (DES. 2 2D)	1.000	EA

Proposal:260149 **Let Date:**June 11, 2026 **Call Order:**135
J/P Num:27108(04) **Proj. Num:**NHPP-013N(237)FP
Counties:MUSKOGEE
Description:GRADE, DRAIN, SURFACE AND BRIDGE
US-69: FROM 0.52 MILES NORTH OF THE SH-165 INTERCHANGE,
EXTEND NORTH IN THE CITY OF MUSKOGEE.
PROJECT LENGTH = 2.463 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0470	611(G)0650	PRECAST INLET PJB 6' WIDE (DES. 3 D)	1.000	EA
0480	611(G)7700	SPECIAL INLET DRAIN	7.000	EA
0490	611(G)7864	PRECAST INLET CI DES. 2 (STD)	2.000	EA
0500	611(G)7868	PRECAST INLET CI DES. 2 (B)	6.000	EA
0510	611(G)7888	PRECAST INLET CI DES. 2 (2C)	2.000	EA
0520	611(G)7892	PRECAST INLET CI DES. 2 (2D)	1.000	EA
0530	611(G)7900	PRECAST INLET CI DES. 3 (B)	1.000	EA
0540	611(G)9020	INLET CDI RCP DES. 6	1.000	EA
0550	611(H)0414	ADD'L DEPTH IN INLET CI DES. 2	19.000	VF
0560	611(H)0458	ADD'L DEPTH IN PRECAST INLET PJB 6' WIDE	66.000	VF
0570	611(L)1610	SPECIAL JUNCTION BOX	5.000	EA
0580	613(A)5204	15" R.C.PIPE CLASS III	288.000	LF
0590	613(A)5208	18" R.C.PIPE CLASS III	1,830.000	LF
0600	613(A)5216	24" R.C.PIPE CLASS III	100.000	LF
0610	613(A)5220	30" R.C.PIPE CLASS III	132.000	LF
0620	613(A)5224	36" R.C.PIPE CLASS III	801.000	LF
0630	613(A)5228	42" R.C.PIPE CLASS III	1,082.000	LF
0640	613(A)5232	48" R.C.PIPE CLASS III	1,290.000	LF
0650	613(A)5400	14" X 23" R.C.PIPE ELL. CLASS HE-III	90.000	LF
0660	613(B)5508	18" CORR. GALV. STEEL PIPE	544.000	LF
0670	613(B)5528	36" CORR. GALV. STEEL PIPE	384.000	LF
0680	613(B)5600	17" X 13" CORR. GALV. STEEL PIPE ARCH	144.000	LF
0690	613(B)5604	21" X 15" CORR. GALV. STEEL PIPE ARCH	160.000	LF
0700	613(B)5612	28" X 20" CORR. GALV. STEEL PIPE ARCH	214.000	LF
0710	613(B)5616	35" X 24" CORR. GALV. STEEL PIPE ARCH	58.000	LF
0720	613(B)5620	42" X 29" CORR. GALV. STEEL PIPE ARCH	56.000	LF
0730	613(B)5624	49" X 33" CORR. GALV. STEEL PIPE ARCH	67.000	LF
0740	613(J)6400	EDGE DRAIN CONDUIT-PERFORATED	7,570.000	LF
0750	613(K)6500	EDGE DRAIN OUTLET LATERAL-NONPERFORATED	720.000	LF
0760	613(L)6608	21" X 15" PREFAB. CULVERT END SEC., ARCH	6.000	EA
0770	613(L)6624	28" X 20" PREFAB. CULVERT END SEC., ARCH	8.000	EA
0780	613(L)6632	35" X 24" PREFAB. CULVERT END SEC., ARCH	2.000	EA
0790	613(L)6644	42" X 29" PREFAB. CULVERT END SEC., ARCH	2.000	EA
0800	613(L)6652	49" X 33" PREFAB. CULVERT END SEC., ARCH	1.000	EA
0810	613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	26.000	EA
0820	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	6.000	EA
0830	613(L)6724	30" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0840	613(L)6728	36" PREFAB. CULVERT END SEC., ROUND	4.000	EA
0850	613(M)6960	TYPE A4 CULVERT END TREATMENT	18.000	EA
0860	613(V)8000	TRENCH EXCAVATION	3,840.000	CY
0870	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0880	619(B)6300	REMOVAL OF HEADWALL	10.000	EA
0890	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	25,528.000	SY
0900	619(B)6376	REMOVAL OF CONC.PAV.W/ASPH.OVERLAY	70,485.000	SY
0910	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	11,211.000	SY
0920	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	3,083.000	SY

Proposal:260149 **Let Date:**June 11, 2026 **Call Order:**135
J/P Num:27108(04) **Proj. Num:**NHPP-013N(237)FP
Counties:MUSKOGEE
Description:GRADE, DRAIN, SURFACE AND BRIDGE
US-69: FROM 0.52 MILES NORTH OF THE SH-165 INTERCHANGE,
EXTEND NORTH IN THE CITY OF MUSKOGEE.
PROJECT LENGTH = 2.463 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0930	619(B)6386	REMOVAL OF GRAVEL DRIVEWAY	1,129.000	SY
0940	619(C)6600	SAWING PAVEMENT	13,195.000	LF
0960	624 3110	(PL) WOOD PRIVACY FENCE	298.000	LF
0970	624(A)3200	FENCE-STYLE WWF	1,004.000	LF
0980	624(C)3400	FENCE-STYLE SWF (4 BARBED WIRE)	1,110.000	LF
0990	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	1,108.000	LF
1000	624(C)3410	FENCE-STYLE SWF (6 BARBED WIRE)	298.000	LF
1010	624(E)3600	FENCE-STYLE CLF (4'HIGH, CLASS A)	433.000	LF
1020	624(E)3610	FENCE-STYLE CLF (5'HIGH, CLASS A)	1,014.000	LF
1030	624(E)3620	FENCE-STYLE CLF (6'HIGH, CLASS A)	455.000	LF
1040	626(A)5210	REMOVE AND RESET MONUMENT	1.000	EA
1050	629(A)7200	MAILBOX INSTALLATION-SINGLE	10.000	EA
0002	WATERLINE RELOCATION			
1060	230(A)7200	SOLID SLAB SODDING	500.000	SY
1070	501(F)1700	GRANULAR BACKFILL	450.000	CY
1080	616(B)2320	2" POLYVINYL CHLORIDE (PVC) PIPE	522.000	LF
1090	616(B)2332	4" POLYVINYL CHLORIDE (PVC) PIPE	571.000	LF
1100	616(B)2336	6" POLYVINYL CHLORIDE (PVC) PIPE	360.000	LF
1110	616(B)2340	8" POLYVINYL CHLORIDE (PVC) PIPE	1,867.000	LF
1120	616(B)2352	12" POLYVINYL CHLORIDE (PVC) PIPE	8,264.000	LF
1130	616(D)2630	2" GATE VALVE	5.000	EA
1140	616(D)2642	4" GATE VALVE	9.000	EA
1150	616(D)2646	6" GATE VALVE	14.000	EA
1160	616(D)2650	8" GATE VALVE	9.000	EA
1170	616(D)2658	12" GATE VALVE	42.000	EA
1180	616(D)2800	STANDARD VALVE BOX	70.000	EA
1190	616(E)2905	1" CORPORATION STOPS	10.000	EA
1200	616(F)3005	METER INSTALLATION 5/8"	20.000	EA
1210	616(G)3100	FIRE HYDRANTS	9.000	EA
1220	616(I)3364	4" HDPE CASING	290.000	LF
1230	616(I)3369	8" HDPE CASING	418.000	LF
1240	616(I)3371	12" HDPE CASING	115.000	LF
1250	616(I)3376	16" HDPE CASING	623.000	LF
1260	616(I)3379	24" HDPE CASING	728.000	LF
1270	616(O)3901	CONNECT TO EXISTING WATER LINE	24.000	EA
1280	616(P)4101	1" POLYETHYLENE WATER SERVICE PIPE	200.000	LF
1290	616(P)4156	12" HDPE PIPE	185.000	LF
0003	SEWERLINE RELOCATION			
1300	611(A)7201	SPECIAL MANHOLE	5.000	EA
1310	611(A)7252	PRECAST CONC RND 4' DIA MANHOLE	15.000	EA
1320	612(B)3310	CONNECT TO EXISTING MANHOLE	3.000	EA
1330	615(A)1220	8" POLYVINYL CHLORIDE (PVC) PIPE	2,193.000	LF
1340	615(B)1300	SANITARY SEWER SERVICE CONNECTION	8.000	EA
1350	616(J)3425	BORE AND JACK 16" CASING	363.000	LF

Proposal:260149 **Let Date:**June 11, 2026 **Call Order:**135
J/P Num:27108(04) **Proj. Num:**NHPP-013N(237)FP
Counties:MUSKOGEE
Description:GRADE, DRAIN, SURFACE AND BRIDGE
US-69: FROM 0.52 MILES NORTH OF THE SH-165 INTERCHANGE,
EXTEND NORTH IN THE CITY OF MUSKOGEE.
PROJECT LENGTH = 2.463 MILES

Line #		Item Description	Quantity	Unit
0004	BRIDGE "A"			
1360	202(A)2210	UNCLASSIFIED EXCAVATION	1,160.000	CY
1370	501(A)1210	STRUCTURAL EXCAVATION UNCLASSIFIED	230.000	CY
1380	501(G)1800	CLSM BACKFILL	240.000	CY
1390	509(A)0210	CLASS AA CONCRETE	618.800	CY
1400	511(B)2310	EPOXY COATED REINFORCING STEEL	88,860.000	LB
0005	BRIDGE "B"			
1410	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	80.000	CY
1420	501(F)1700	GRANULAR BACKFILL	86.000	CY
1430	509(B)0320	CLASS A CONCRETE	32.400	CY
1440	510(C)1450	SLOPE WALL (5")	404.000	SY
1450	511(A)2210	REINFORCING STEEL	3,800.000	LB
1460	514(A)5210	PILES, FURNISHED (HP 10X42)	371.000	LF
1470	514(B)5310	PILES, DRIVEN (HP 10X42)	371.000	LF
1480	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
1490	542 9100	(PL)INSTALLATION OF BRIDGE ITEMS	1.000	LSUM
1500	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	68.000	LF
1510	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	36.000	LF
1520	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

Proposal:260149 **Let Date:**June 11, 2026 **Call Order:**135
J/P Num:27108(04) **Proj. Num:**NHPP-013N(237)FP
Counties:MUSKOGEE
Description:GRADE, DRAIN, SURFACE AND BRIDGE
US-69: FROM 0.52 MILES NORTH OF THE SH-165 INTERCHANGE,
EXTEND NORTH IN THE CITY OF MUSKOGEE.
PROJECT LENGTH = 2.463 MILES

Line #		Item Description	Quantity	Unit
0006	TRAFFIC SIGNAL			
1530	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	515.000	LF
1540	802(B)0328	3" PVC SCH.40 PLASTIC CONDUIT BORED	1,050.000	LF
1550	802(B)0332	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	180.000	LF
1560	803(A)1210	PULL BOX(SIZE I)	9.000	EA
1570	803(A)1220	PULL BOX(SIZE II)	3.000	EA
1580	804(A)2200	STRUCTURAL CONCRETE	68.750	CY
1590	804(B)2300	REINFORCING STEEL	10,028.800	LB
1600	805(A)3256	(PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1.000	LSUM
1610	806(A)4244	32'MH POLE,30'TS & 10'LMA(G.STL.)	1.000	EA
1620	806(A)4248	32'MH POLE 35'TS & 10'LMA(G.STL.)	2.000	EA
1630	806(A)4252	32'MH POLE 40'TS & 10'LMA(G.STL.)	1.000	EA
1640	806(A)4256	32'MH POLE 45'TS & 10'LMA(G.STL.)	3.000	EA
1650	806(A)4260	32'MH POLE 50'TS & 10'LMA(G.STL.)	1.000	EA
1660	806(A)4264	32'MH POLE,55'TS & 10'LMA(G.STL.)	1.000	EA
1670	806(A)4316	POLE & 30' TS MST.ARM(G.STL.)	3.000	EA
1680	806(B)4408	10' MTG.HT.TS PED.POLE(G.STL.)	5.000	EA
1690	809(A)7200	ROADWAY LUMINAIRE	9.000	EA
1700	810(A)8200	SERVICE POLE	3.000	EA
1710	811 9120	1/C NO.6 ELECT.COND.	600.000	LF
1720	811 9130	1/C NO.10 ELECT.COND.	6,175.000	LF
1730	825 8100	TRAFFIC SIGNAL CONTROLLER ASSEMBLY	3.000	EA
1740	825(B)8310	(SP) INTERSECTION INTEGRATION SYSTEM - NON-BIDDABLE	3.000	EA
1750	825(B)8320	(SP) INTERSECTION INTEGRATION SYSTEM SERVICE - NON-E	3.000	EA
1760	828 0100	(PL)DETECTION SYSTEM (VIDEO)	1.000	LSUM
1770	828 0110	(PL)DETECTION SYSTEM (RADAR)	1.000	LSUM
1780	830 2100	PEDESTRIAN PUSH BUTTON	10.000	EA
1790	831 3116	1WAY2SEC.ADJ.PED.SIG.HD.S-20	10.000	EA
1800	831 3120	1WAY3SEC.ADJ.SIG.HD.S-6	26.000	EA
1810	831 3124	1WAY3SEC.ADJ.SIG.HD.S-9	2.000	EA
1820	831 3128	1WAY3SEC.ADJ.SIG.HD.S-10	1.000	EA
1830	831 3144	1WAY4SEC.ADJ.SIG.HD.S-13	10.000	EA
1840	833 5100	BACKPLATE	39.000	EA
1850	834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	3,685.000	LF
1860	834(A)6210	7/C TRAFFIC SIGNAL ELECTRICAL CABLE	710.000	LF
1870	834(A)6235	21/C TRAFFIC SIGNAL ELECTRICAL CABLE	2,484.000	LF
1880	834(B)6300	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	110.000	LF
1890	840(B)0300	E.P.S. OPTICAL DETECTOR	12.000	EA
1900	840(C)0400	E.P.S. OPTICAL DETECTOR CABLE	3,405.000	LF
1910	840(D)0510	E.P.S. 4 CHANNEL PHASE SELECTOR	3.000	EA
1920	850(C)1400	MAST ARM MOUNTED SIGNS(ALUM.)	235.000	SF

Proposal:260149 **Let Date:**June 11, 2026 **Call Order:**135
J/P Num:27108(04) **Proj. Num:**NHPP-013N(237)FP
Counties:MUSKOGEE
Description:GRADE, DRAIN, SURFACE AND BRIDGE
US-69: FROM 0.52 MILES NORTH OF THE SH-165 INTERCHANGE,
EXTEND NORTH IN THE CITY OF MUSKOGEE.
PROJECT LENGTH = 2.463 MILES

Line #		Item Description	Quantity	Unit
0007	TRAFFIC SIGNING AND STRIPING			
1930	804(A)2200	STRUCTURAL CONCRETE	1.200	CY
1940	804(B)2300	REINFORCING STEEL	168.000	LB
1950	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	5.000	EA
1960	850(A)1200	SHEET ALUMINUM SIGNS	740.150	SF
1970	851(B)2325	4"@10.79 GALV.STL.PIPE POST	80.000	LF
1980	851(C)2415	2" SQUARE TUBE POST	1,364.000	LF
1990	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	8,464.000	LF
2000	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	56,022.000	LF
2010	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	855.000	LF
2020	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	660.000	LF
2030	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	1,550.000	LF
2040	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	81.000	EA
2050	856(B)8311	(SP) TRAFFIC STRIPE(PLURAL-COMP)(SYMBOLS)	2.000	EA
2060	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	10,000.000	LF
0008	TRAFFIC LIGHTING			
2070	802(B)0320	2" PVC SCH.40 PLASTIC CONDUIT BORED	4,655.000	LF
2080	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	5,845.000	LF
2090	803(A)1210	PULL BOX(SIZE I)	56.000	EA
2100	804(A)2200	STRUCTURAL CONCRETE	82.000	CY
2110	804(B)2300	REINFORCING STEEL	14,200.000	LB
2120	805(A)3228	(PL)REMOVAL OF LIGHT POLE	50.000	EA
2130	806(C)4512	40' MTG & 10' HLMA(G.STL.)	40.000	EA
2140	806(C)4524	40' MHP & TWIN H.L.MST.ARM(G.STL.)	10.000	EA
2150	807 5120	BREAKAWAY BASE (DES. B)	12.000	EA
2160	809(A)7200	ROADWAY LUMINAIRE	60.000	EA
2170	810(A)8200	SERVICE POLE	1.000	EA
2180	811 9115	1/C NO.4 ELECT.COND.	34,254.000	LF
2190	811 9160	2/C NO.12 ELECT.COND.	3,000.000	LF

Proposal:260149 **Let Date:**June 11, 2026 **Call Order:**135
J/P Num:27108(04) **Proj. Num:**NHPP-013N(237)FP
Counties:MUSKOGEE
Description:GRADE, DRAIN, SURFACE AND BRIDGE
US-69: FROM 0.52 MILES NORTH OF THE SH-165 INTERCHANGE,
EXTEND NORTH IN THE CITY OF MUSKOGEE.
PROJECT LENGTH = 2.463 MILES

Line #		Item Description	Quantity	Unit
0009	TRAFFIC CONTROL			
2200	857(A)9200	CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE)	190,000.000	LF
2210	857(C)9400	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	321,540.000	LF
2220	857(C)9420	REMOVABLE PAVEMENT MARKING TAPE(ARROWS)	50.000	EA
2230	857(E)9620	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	35,000.000	EA
2240	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	80,400.000	LF
2250	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	207,132.000	SD
2260	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	35,332.000	SD
2265	880(B)6315	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	66.000	EA
2270	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	10,697.000	SD
2290	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	19,460.000	SD
2300	880(D)6500	VERTICAL PANELS	33,750.000	SD
2310	880(E)6607	WARNING LIGHTS(TYPE B)	116,362.000	SD
2320	880(E)6610	WARNING LIGHTS(TYPE C)	54,297.000	SD
2330	880(F)6700	DRUMS	54,297.000	SD
2340	880(G)6800	TUBE CHANNELIZERS	66,070.000	SD
2350	880(G)6805	CHANNELIZER CONES	25,616.000	SD
2360	880(N)7500	(SP) TEMP. TRAFF. SIGNAL SPAN WIRE EQUIP	1.000	LSUM
2370	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	5,400.000	SD
0010	STAKING			
2380	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0011	CONSTRUCTION			
2390	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
2400	641 2110	MOBILIZATION	1.000	LSUM
0012	SPECIAL SIGNS (NON-PARTICIPATING)			
2410	850(D)1510	SPECIAL SIGNS	16.000	EA