Proposal:260156 **Let Date:**September 17, 2026 **Call Order:**803
J/P Num:34384(04) **Proj. Num:**STP-207B(129)PM
Counties:BRYAN
Description:INTERSECTION MODIFICATION
SH-78: AT THE INTERSECTION OF GERLACH DRIVE IN DURANT.
PROJECT LENGTH = 0.496 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	3,668.000	CY
0030	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0040	221(B)2300	TEMPORARY SILT FENCE	1,625.000	LF
0050	221(E)2600	TEMPORARY SILT DIKE	600.000	LF
0060	221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	5.000	EA
0070	230(A)7200	SOLID SLAB SODDING	11,138.000	SY
0080	233(A)0200	VEGETATIVE MULCHING	2.300	AC
0090	241 3100	MOWING	4.600	AC
0100	303(A)1200	AGGREGATE BASE TYPE A	2,928.000	CY
0110	325 0100	SEPARATOR FABRIC	9,542.000	SY
0120	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	661.000	TON
0130	407(B)7300	TACK COAT	1,182.000	GAL
0140	408 8100	PRIME COAT	6,191.000	GAL
0150	411(B)1320	SUPERPAVE, TYPE S3(PG 70-28 OK)	1,376.000	TON
0160	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	1,695.000	TON
0170	411(C)1420	SUPERPAVE, TYPE S4(PG 70-28 OK)	1,142.000	TON
0180	412 3100	COLD MILLING PAVEMENT	3,400.000	SY
0190	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	19.000	CY
0200	509(A)0200	CLASS AA CONCRETE	12.000	CY
0210	509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	4.000	CY
0220	509(D)0500	CLASS C CONCRETE	10.000	CY
0230	511(A)2200	REINFORCING STEEL	2,567.000	LB
0240	609(A)4230	CONC.CURB(6" BARRIER-INTEGRAL)	106.000	LF
0250	609(B)4360	2'-8" COMB.CRB.& GUT.(6" BARRIER)	1,381.000	LF
0260	610(A)5200	4" CONCRETE SIDEWALK	367.000	SY
0270	610(B)5300	6" CONCRETE DRIVEWAY (H.E.S.)	172.000	SY
0280	610(B)5310	6" CONCRETE DRIVEWAY	1,138.000	SY
0290	610(I)6000	TACTILE WARNING DEVICE-NEW	20.000	SF
0300	611(A)7215	MANHOLE (5' DIA.)	1.000	EA
0310	611(G)0264	INLET W/SMALL JCT. BOX, CI, DES.2	1.000	EA
0320	611(G)0354	INLET (SMD-TYPE 2)	1.000	EA
0330	611(G)7754	INLET CI DES. 2 (STD)	1.000	EA
0340	611(L)1600	JUNCTION BOXES	32.000	CF
0350	613(A)5208	18" R.C.PIPE CLASS III	379.000	LF
0360	613(A)5350	22" X 13" R.C.PIPE ARCH CLASS A-III	754.000	LF
0370	613(J)6400	EDGE DRAIN CONDUIT-PERFORATED	750.000	LF
0380	613(K)6500	EDGE DRAIN OUTLET LATERAL-NONPERFORATED	20.000	LF
0390	613(M)6960	TYPE A4 CULVERT END TREATMENT	27.000	EA
0400	613(Q)7500	OUTLET LATERAL HEADWALL	2.000	EA
0410	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0420	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	100.000	SY
0430	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	3,415.000	SY
0440	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	1,022.000	SY
0450	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	185.000	SY
0460	619(C)6600	SAWING PAVEMENT	4,649.000	LF
0470	629(A)7200	MAILBOX INSTALLATION-SINGLE	8.000	EA

Proposal: 260156 **Let Date:** September 17, 2026 **Call Order:** 803
J/P Num: 34384(04) **Proj. Num:** STP-207B(129)PM
Counties: BRYAN
Description: INTERSECTION MODIFICATION
SH-78: AT THE INTERSECTION OF GERLACH DRIVE IN DURANT.
PROJECT LENGTH = 0.496 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0480	629(C)7400	REMOVAL OF MAILBOX INSTALLATION	8.000	EA
0490	629(E)7600	MAILBOX	8.000	EA

Proposal:260156 **Let Date:**September 17, 2026 **Call Order:**803
J/P Num:34384(04) **Proj. Num:**STP-207B(129)PM
Counties:BRYAN
Description:INTERSECTION MODIFICATION
SH-78: AT THE INTERSECTION OF GERLACH DRIVE IN DURANT.
PROJECT LENGTH = 0.496 MILES

Line #		Item Description	Quantity	Unit
0002	WATER PIPE AND FITTINGS			
0500	221(C)2410	REINFORCED SILT FENCE	3,100.000	LF
0510	221(E)2600	TEMPORARY SILT DIKE	275.000	LF
0520	612(F)3800	SERVICE METER AND BOX RELOCATION	1.000	EA
0530	613(U)7945	BORE & JACK 54" STEEL CASING	100.000	LF
0540	616(B)2336	6" POLYVINYL CHLORIDE (PVC) PIPE	27.000	LF
0550	616(B)2341	8” PVC WATER LINE (AWWA C900 DR-18)	60.000	LF
0560	616(B)2344	10" POLYVINYL CHLORIDE (PVC) PIPE	657.000	LF
0570	616(B)2352	12" POLYVINYL CHLORIDE (PVC) PIPE	872.000	LF
0580	616(B)2356	16" POLYVINYL CHLORIDE (PVC) PIPE	1,413.000	LF
0590	616(B)2360	18" POLYVINYL CHLORIDE(PVC)PIPE	45.000	LF
0600	616(B)2372	24" POLYVINYL CHLORIDE (PVC) PIPE	897.000	LF
0610	616(B)2377	36” PVC WATER LINE (AWWA C900 DR-18)	205.000	LF
0620	616(D)2538	2" COMB.AIR RELEASE ASSEMBLY AND VAULT	2.000	EA
0630	616(D)2646	6" GATE VALVE	1.000	EA
0640	616(D)2650	8" GATE VALVE	2.000	EA
0650	616(D)2654	10" GATE VALVE	2.000	EA
0660	616(D)2658	12" GATE VALVE	1.000	EA
0670	616(D)2666	16" GATE VALVE	1.000	EA
0680	616(D)2670	18" GATE VALVE	1.000	EA
0690	616(D)2678	24" GATE VALVE	2.000	EA
0700	616(D)2679	36" GATE VALVE	3.000	EA
0710	616(D)2782	16" X 8" TAPPING SLEEVE	3.000	EA
0720	616(D)2908	12" INSERTION VALVE	1.000	EA
0730	616(D)2940	1” COMBINATION AIR RELEASE VALVE	1.000	EA
0740	616(E)3000	6” LINE STOP	1.000	EA
0750	616(E)3010	16” LINE STOP	1.000	EA
0760	616(E)3020	18” LINE STOP	1.000	EA
0770	616(E)3050	24” LINE STOP	1.000	EA
0780	616(F)3020	METER INSTALLATION 2"	1.000	EA
0790	616(G)3111	FIRE HYDRANT AND ASSEMBLY	3.000	EA
0800	616(J)3425	BORE AND JACK 16" CASING	100.000	LF
0810	616(J)3465	8” DIRECTIONAL BORE	252.000	LF
0820	616(J)3467	10” DIRECTIONAL BORE	124.000	LF
0830	616(J)3471	14” DIRECTIONAL BORE	19.000	LF
0840	616(J)3473	16” DIRECTIONAL BORE	184.000	LF
0850	616(J)3487	30” DIRECTIONAL BORE	17.000	LF
0860	616(J)3490	36” DIRECTIONAL BORE	511.000	LF
0870	616(L)3617	10" BLIND FLANGE	1.000	EA
0880	616(L)3650	16" FLANGE VALVE	1.000	EA
0890	616(N)3800	SERVICE CONNECTION (SHORT)	4.000	EA
0900	616(O)3985	6" 45 DEGREE FITTING	2.000	EA
0910	616(O)4035	12" 11 1/4 DEGREE FITTING	4.000	EA
0920	616(O)4045	12" 45 DEGREE FITTING	2.000	EA
0930	616(O)4060	16" 22 1/2 DEGREE FITTING	1.000	EA
0940	616(O)4065	16" 45 DEGREE FITTING	7.000	EA
0950	616(O)4070	16" 90 DEGREE FITTING	2.000	EA
0960	616(O)4073	18" 45 DEGREE DUCTILE IRON FITTING	2.000	EA

Proposal:260156 **Let Date:**September 17, 2026 **Call Order:**803
J/P Num:34384(04) **Proj. Num:**STP-207B(129)PM
Counties:BRYAN
Description:INTERSECTION MODIFICATION
SH-78: AT THE INTERSECTION OF GERLACH DRIVE IN DURANT.
PROJECT LENGTH = 0.496 MILES

Line #		Item Description	Quantity	Unit
0002	WATER PIPE AND FITTINGS			
0970	616(O)4076	24" 11 1/4 DEGREE FITTING	4.000	EA
0980	616(O)4078	24" 45 DEGREE FITTING	4.000	EA
0990	616(O)4100	CONNECT TO EXISTING 2" WATER LINE	1.000	EA
1000	616(O)4110	CONNECT TO EXISTING 6" WATER LINE	1.000	EA
1010	616(O)4125	CONNECT TO EXISTING 12" WATER LINE	1.000	EA
1020	616(O)4135	CONNECT TO EXISTING 16" WATER LINE	1.000	EA
1030	616(O)4140	CONNECT TO EXISTING 18" WATER LINE	1.000	EA
1040	616(O)4155	CONNECT TO EXISTING 24" WATER LINE	1.000	EA
1050	616(O)4185	CONNECT TO EXISTING 36" WATER LINE	2.000	EA
1060	616(P)4108	2" HDPE PIPE	11.000	LF
1070	616(P)4148	8" HDPE PIPE	367.000	LF
1080	616(P)4152	10" HDPE PIPE	124.000	LF
1090	616(P)4158	14” HDPE WATER LINE (AWWA C906 DR-9)	19.000	LF
1100	616(P)4159	16” HDPE WATER LINE (AWWA C906 DR-9)	184.000	LF
1110	616(P)4170	30" HDPE PIPE	17.000	LF
1120	616(P)4176	36" HDPE PIPE	511.000	LF
1130	616(Q)4229	36" 45 DEGREE BEND	2.000	EA
1140	616(R)4326	8" X 2" REDUCER	1.000	EA
1150	616(R)4360	16" X 10" REDUCER	1.000	EA
1160	616(R)4382	24" X 36" REDUCER	2.000	EA
1170	616(R)4400	36” X 10” REDUCER	1.000	EA
1180	616(R)4410	36” X 12” REDUCER	1.000	EA
1190	616(R)4420	36” X 16” REDUCER	1.000	EA
1200	616(R)4430	36” X 18” REDUCER	1.000	EA
1210	616(T)4490	2" TEE	1.000	EA
1220	616(T)4586	10" X 10" X 6" TEE	1.000	EA
1230	616(T)4587	10" X 10" X 8" TEE	1.000	EA
1240	616(T)4670	36" X 36" X 36" TEE	3.000	EA
1250	616(U)4765	8” POLY TO PVC TRANSITION W/ MJ RESTRAINT	1.000	EA
1260	616(V)4800	HYDROSTATIC PRESSURE TESTING & DISINFECT	1.000	LSUM
1270	619(B)6357	SAW-CUT, REMOVE, AND REPLACE CURB AND GUTTER	10.000	LF
1280	619(B)6361	SAW-CUT, REMOVE, AND REPLACE CONC. PAVEMENT	27.000	SY
1290	619(B)6365	REMOVE AND REPLACE ASPHALT	29.000	SY
1300	619(B)6387	REMOVAL AND REPLACE GRAVEL SURFACE	99.000	SF
1310	619(B)6520	CUT & PLUG 2" WATER LINE	1.000	EA
1320	619(B)6536	CUT & PLUG 6" WATER LINE	1.000	EA
1330	619(B)6546	ABANDON 12" WATER LINE	1.000	EA
1340	619(B)6570	CUT, PLUG & ABANDON 16" WATER LINE	2.000	EA
1350	619(B)6571	CUT, PLUG & ABANDON 18" WATER LINE	1.000	EA
1360	619(B)6572	CUT, PLUG & ABANDON 24" WATER LINE	1.000	EA
1370	619(B)6573	CUT, PLUG & ABANDON 36" WATER LINE	2.000	EA

Proposal:260156 **Let Date:**September 17, 2026 **Call Order:**803
J/P Num:34384(04) **Proj. Num:**STP-207B(129)PM
Counties:BRYAN
Description:INTERSECTION MODIFICATION
SH-78: AT THE INTERSECTION OF GERLACH DRIVE IN DURANT.
PROJECT LENGTH = 0.496 MILES

Line #		Item Description	Quantity	Unit
0003	TRAFFIC SIGNAL			
1375	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	325.000	LF
1380	802(B)0328	3" PVC SCH.40 PLASTIC CONDUIT BORED	180.000	LF
1400	802(B)0332	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	10.000	LF
1410	803(A)1210	PULL BOX(SIZE I)	7.000	EA
1420	803(A)1220	PULL BOX(SIZE II)	1.000	EA
1430	804(A)2200	STRUCTURAL CONCRETE	18.900	CY
1440	804(B)2300	REINFORCING STEEL	2,769.000	LB
1450	806(A)4216	32'MH POLE 30'TS & 8'LMA(G.STL.)	1.000	EA
1460	806(A)4220	32'MH POLE 35'TS & 8'LMA(G.STL.)	2.000	EA
1470	806(A)4224	32'MH POLE 40'TS & 8'LMA(G.STL.)	1.000	EA
1480	806(B)4408	10' MTG.HT.TS PED.POLE(G.STL.)	2.000	EA
1490	809(A)7200	ROADWAY LUMINAIRE	4.000	EA
1500	810(A)8200	SERVICE POLE	1.000	EA
1510	811 9120	1/C NO.6 ELECT.COND.	400.000	LF
1520	811 9130	1/C NO.10 ELECT.COND.	3,320.000	LF
1530	825 8100	TRAFFIC SIGNAL CONTROLLER ASSEMBLY	1.000	EA
1540	828 0100	(PL)DETECTION SYSTEM (VIDEO)	1.000	LSUM
1550	830 2100	PEDESTRIAN PUSH BUTTON	2.000	EA
1560	831 3116	1WAY2SEC.ADJ.PED.SIG.HD.S-20	2.000	EA
1570	831 3120	1WAY3SEC.ADJ.SIG.HD.S-6	8.000	EA
1580	831 3124	1WAY3SEC.ADJ.SIG.HD.S-9	2.000	EA
1590	831 3144	1WAY4SEC.ADJ.SIG.HD.S-13	1.000	EA
1600	833 5100	BACKPLATE	11.000	EA
1610	834(A)6200	2/C TRAFFIC SIGNAL ELECTRICAL CABLE	20.000	LF
1620	834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	1,000.000	LF
1630	834(A)6210	7/C TRAFFIC SIGNAL ELECTRICAL CABLE	140.000	LF
1640	834(A)6225	15/C TRAFFIC SIGNAL ELECTRICAL CABLE	660.000	LF
1650	840(A)0200	E.P.S. OPTICAL EMITTER	2.000	EA
1660	840(B)0300	E.P.S. OPTICAL DETECTOR	3.000	EA
1670	840(C)0400	E.P.S. OPTICAL DETECTOR CABLE	800.000	LF
1680	840(D)0500	E.P.S. 2 CHANNEL PHASE SELECTOR	2.000	EA
1690	850(C)1400	MAST ARM MOUNTED SIGNS(ALUM.)	87.000	SF
0004	TRAFFIC			
1700	509(D)0500	CLASS C CONCRETE	4.800	CY
1710	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	2.000	EA
1720	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	21.000	EA
1730	850(A)1200	SHEET ALUMINUM SIGNS	9.000	SF
1740	851(C)2420	2 1/4" SQUARE TUBE POST	251.000	LF
1750	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	13,217.000	LF
1760	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	550.000	LF
1770	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	160.000	LF
1780	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	25.000	EA

Proposal:260156 **Let Date:**September 17, 2026 **Call Order:**803
J/P Num:34384(04) **Proj. Num:**STP-207B(129)PM
Counties:BRYAN
Description:INTERSECTION MODIFICATION
SH-78: AT THE INTERSECTION OF GERLACH DRIVE IN DURANT.
PROJECT LENGTH = 0.496 MILES

Line #		Item Description	Quantity	Unit
0005	TRAFFIC CONTROL			
1790	854(A)6201	(SP) TRAFFIC STRIPE(PAINT)(4" WIDE)	2,800.000	LF
1800	857(C)9400	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	24,800.000	LF
1810	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	11,700.000	LF
1820	858(A)0216	PAVE.MARKERS CLASS A TYPE 2-A	670.000	EA
1830	858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	670.000	EA
1840	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	3,150.000	SD
1850	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	3,600.000	SD
1860	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,500.000	SD
1870	880(B)6330	CONSTRUCTION SIGNS 33.0 SF & OVER	900.000	SD
1880	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	2,925.000	SD
1890	880(E)6600	WARNING LIGHTS(TYPE A)	3,375.000	SD
1900	880(F)6700	DRUMS	8,310.000	SD
1910	880(G)6800	TUBE CHANNELIZERS	41,550.000	SD
1920	880(I)7000	FLAGGER	10.000	SD
1930	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	328.000	SD
0006	STAKING			
1940	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0007	CONSTRUCTION			
1950	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
1960	641 2110	MOBILIZATION	1.000	LSUM