Proposal: 260159 **Let Date:** June 18, 2026 **Call Order:** 230
J/P Num: 31267(04) **Proj. Num:** STP-235C(103)PM
Counties: JOHNSTON
Description: BRIDGE AND APPROACHES
SH-22: OVER UNNAMED CREEK,
2.10 MILES SOUTH AND EAST OF SH-78 NEAR TISHOMINGO.
PROJECT LENGTH = 0.085 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	4,955.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	2,919.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	3,038.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	42.000	LF
0070	221(F)2700	TEMPORARY ROCK FILTER DAM TYPE 1	6.000	CY
0080	221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	3.000	EA
0090	230(A)7200	SOLID SLAB SODDING	15,128.000	SY
0100	233(A)0200	VEGETATIVE MULCHING	3.130	AC
0110	241 3100	MOWING	6.260	AC
0120	303(A)1200	AGGREGATE BASE TYPE A	536.000	CY
0130	307(K)4200	STABILIZED SUBGRADE	4,374.000	SY
0140	326(C)1100	(SP) WOVEN GEOSYNTHETIC REINFORCEMENT FABRIC	2,593.000	SY
0150	402(A)2200	TRAFFIC BOUND SURFACE COURSE TYPE A	1,324.000	TON
0160	407(B)7300	TACK COAT	569.000	GAL
0170	408 8100	PRIME COAT	1,826.000	GAL
0180	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	978.000	TON
0190	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	720.000	TON
0200	412 3100	COLD MILLING PAVEMENT	2,323.000	SY
0210	601(B)1220	TYPE I-A PLAIN RIPRAP	150.000	TON
0220	601(C)1300	TYPE I-A FILTER BLANKET	75.000	TON
0230	611(G)0350	INLET (SMD-TYPE 1)	1.000	EA
0240	611(G)7930	INLET GPI TYPE 1 (DES. 1)	2.000	EA
0250	611(H)0470	ADD'L DEPTH IN INLET GPI TYPE 1	5.000	VF
0260	613(A)5208	18" R.C.PIPE CLASS III	134.000	LF
0270	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0280	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	1,065.000	SY
0290	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	890.000	LF
0002	BRIDGE 'A' - NBI NO. 32676			
0300	202(A)2210	UNCLASSIFIED EXCAVATION	3,670.000	CY
0310	501(A)1210	STRUCTURAL EXCAVATION UNCLASSIFIED	280.000	CY
0320	502 3100	TEMPORARY EARTH RETAINAGE	1.000	LSUM
0330	509(A)0210	CLASS AA CONCRETE	829.200	CY
0340	511(A)2210	REINFORCING STEEL	137,520.000	LB
0350	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0003	SIGNING AND STRIPING			
0360	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	6,000.000	LF

Proposal:260159 **Let Date:**June 18, 2026 **Call Order:**230
J/P Num:31267(04) **Proj. Num:**STP-235C(103)PM
Counties:JOHNSTON
Description:BRIDGE AND APPROACHES
SH-22: OVER UNNAMED CREEK,
2.10 MILES SOUTH AND EAST OF SH-78 NEAR TISHOMINGO.
PROJECT LENGTH = 0.085 MILES

Line #		Item Description	Quantity	Unit
0004	TRAFFIC CONTROL			
0370	823 6100	(SP)PORTABLE TRAFFIC SIGNAL SYSTEM	150.000	SD
0380	857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	2,900.000	LF
0390	871(B)2300	CONST.ZONE IMPACT ATTEN.	300.000	SD
0400	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	750.000	LF
0410	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	400.000	LF
0420	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	960.000	SD
0430	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	600.000	SD
0440	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,500.000	SD
0450	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	760.000	SD
0460	880(D)6500	VERTICAL PANELS	560.000	SD
0470	880(E)6607	WARNING LIGHTS(TYPE B)	920.000	SD
0480	880(E)6610	WARNING LIGHTS(TYPE C)	1,760.000	SD
0490	880(F)6700	DRUMS	2,020.000	SD
0500	880(G)6805	CHANNELIZER CONES	1,050.000	SD
0510	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	300.000	SD
0005	STAKING			
0520	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
0530	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0540	640(A)1210	FIELD OFFICE	1.000	EA
0550	641 2110	MOBILIZATION	1.000	LSUM