Proposal: 260160 **Let Date:** June 18, 2026 **Call Order:** 235
J/P Num: 34451(04) **Proj. Num:** STP-238D(091)CI
Counties: KIOWA
Description: BRIDGE AND APPROACHES
COUNTY ROAD (E 1440 RD): OVER PECAN CREEK,
0.92 MILES EAST OF SH-115 NEAR WICHITA MOUNTAIN WILDLIFE REFUGE.
PROJECT LENGTH = 0.189 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(H)2900	EARTHWORK	1.000	LSUM
0030	221(B)2300	TEMPORARY SILT FENCE	200.000	LF
0040	221(E)2600	TEMPORARY SILT DIKE	400.000	LF
0050	230(A)7200	SOLID SLAB SODDING	6,900.000	SY
0060	233(A)0200	VEGETATIVE MULCHING	1.430	AC
0070	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	650.000	TON
0080	509(D)0500	CLASS C CONCRETE	10.000	CY
0090	613(B)5612	28" X 20" CORR. GALV. STEEL PIPE ARCH	55.000	LF
0100	613(B)5620	42" X 29" CORR. GALV. STEEL PIPE ARCH	163.000	LF
0110	613(M)6904	TYPE B3 CULVERT END TREATMENT	2.000	EA
0120	613(M)6908	TYPE C3 CULVERT END TREATMENT	4.000	EA
0002	BRIDGE 'A'			
0130	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	210.600	CY
0140	501(F)1700	GRANULAR BACKFILL	109.600	CY
0150	503(A)4230	PRESTRESSED CONCRETE BEAMS (TYPE III)	319.000	LF
0160	504(D)5410	CONCRETE RAIL (TR3)	233.300	LF
0170	506(A)7200	STRUCTURAL STEEL	660.000	LB
0180	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	4.000	EA
0190	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	4.000	EA
0200	509(A)0210	CLASS AA CONCRETE	71.100	CY
0210	509(B)0320	CLASS A CONCRETE	78.800	CY
0220	511(A)2210	REINFORCING STEEL	29,838.000	LB
0230	514(A)5210	PILES, FURNISHED (HP 10X42)	120.000	LF
0240	514(A)5220	PILES, FURNISHED (HP 12X53)	364.000	LF
0250	514(B)5310	PILES, DRIVEN (HP 10X42)	120.000	LF
0260	514(B)5320	PILES, DRIVEN (HP 12X53)	364.000	LF
0270	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0280	601(B)1210	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	1,214.000	TON
0290	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	66.000	LF
0300	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	36.000	LF
0310	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0320	623(F)1748	GUARDRAIL ANCHOR UNIT (TYPE II)	4.000	EA
0003	TRAFFIC			
0330	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	480.000	SD
0340	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	720.000	SD
0350	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,200.000	SD
0360	880(E)6600	WARNING LIGHTS(TYPE A)	2,640.000	SD
0004	STAKING			
0370	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM

Proposal: 260160 **Let Date:** June 18, 2026 **Call Order:** 235
J/P Num: 34451(04) **Proj. Num:** STP-238D(091)CI
Counties: KIOWA
Description: BRIDGE AND APPROACHES
COUNTY ROAD (E 1440 RD): OVER PECAN CREEK,
0.92 MILES EAST OF SH-115 NEAR WICHITA MOUNTAIN WILDLIFE REFUGE.
PROJECT LENGTH = 0.189 MILES

Line #		Item Description	Quantity	Unit
0005	CONSTRUCTION			
0380	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0390	641 2100	MOBILIZATION	1.000	LSUM