Proposal:260161 **Let Date:**June 18, 2026 **Call Order:**240
J/P Num:35000(04) **Proj. Num:**STP-241D(130)CI
Counties:LINCOLN
Description:BRIDGE AND APPROACHES
COUNTY ROAD (NS-3450): OVER QUAPAW CREEK,
1.81 MILES NORTH OF US-62 NEAR MEEKER.
PROJECT LENGTH = 0.399 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	7,061.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	6,734.000	CY
0040	202(E)2600	SELECT BORROW	1,469.000	CY
0050	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0060	221(B)2300	TEMPORARY SILT FENCE	413.000	LF
0070	221(E)2600	TEMPORARY SILT DIKE	450.000	LF
0080	230(A)7200	SOLID SLAB SODDING	25,351.000	SY
0090	233(A)0200	VEGETATIVE MULCHING	5.240	AC
0100	509(A)0200	CLASS AA CONCRETE	103.000	CY
0110	509(D)0500	CLASS C CONCRETE	61.000	CY
0120	511(A)2200	REINFORCING STEEL	17,360.000	LB
0130	613(B)5516	24" CORR. GALV. STEEL PIPE	313.000	LF
0140	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	12.000	EA
0150	623(F)1704	GUARDRAIL ANCHOR UNIT (TYPE A)	2.000	EA
0160	623(F)1712	GUARDRAIL ANCHOR UNIT (TYPE B)	2.000	EA
0170	623(F)1724	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA
0002	BRIDGE 'A'			
0180	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	190.000	CY
0190	501(G)1800	CLSM BACKFILL	76.000	CY
0200	503(A)4220	PRESTRESSED CONCRETE BEAMS (TYPE II)	178.000	LF
0210	503(A)4230	PRESTRESSED CONCRETE BEAMS (TYPE III)	239.000	LF
0220	504(D)5410	CONCRETE RAIL (TR3)	357.500	LF
0230	506(A)7200	STRUCTURAL STEEL	1,220.000	LB
0240	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	6.000	EA
0250	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	12.000	EA
0260	509(A)0210	CLASS AA CONCRETE	118.500	CY
0270	509(B)0320	CLASS A CONCRETE	142.100	CY
0280	511(A)2210	REINFORCING STEEL	52,640.000	LB
0290	514(A)5210	PILES, FURNISHED (HP 10X42)	344.000	LF
0300	514(A)5220	PILES, FURNISHED (HP 12X53)	836.000	LF
0310	514(B)5310	PILES, DRIVEN (HP 10X42)	344.000	LF
0320	514(B)5320	PILES, DRIVEN (HP 12X53)	836.000	LF
0330	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0340	516(A)8240	DRILLED SHAFTS 60" DIAMETER	338.000	LF
0350	516(C)8400	CROSSHOLE SONIC LOGGING	1.000	EA
0360	518(B)0300	SEALED EXPANSION JOINTS	33.700	LF
0370	601(B)1230	TYPE I-A PLAIN RIPRAP	1,800.000	TON
0380	601(C)1310	TYPE I-A FILTER BLANKET	200.000	TON
0390	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	60.000	LF
0400	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	82.000	LF
0003	TRAFFIC SIGNING AND STRIPING			
0410	850(A)1200	SHEET ALUMINUM SIGNS	13.000	SF
0420	851(C)2405	1 1/2" SQUARE TUBE POST	24.000	LF

Proposal:260161 **Let Date:**June 18, 2026 **Call Order:**240
J/P Num:35000(04) **Proj. Num:**STP-241D(130)CI
Counties:LINCOLN
Description:BRIDGE AND APPROACHES
COUNTY ROAD (NS-3450): OVER QUAPAW CREEK,
1.81 MILES NORTH OF US-62 NEAR MEEKER.
PROJECT LENGTH = 0.399 MILES

	Line #		Item Description	Quantity	Unit
0004	TRAFFIC CONTROL				
	0430	853 5100	DELINEATORS(TYPE 1, CODE 1)	4.000	EA
	0440	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	2,640.000	SD
	0450	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	480.000	SD
	0460	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	960.000	SD
	0470	880(E)6600	WARNING LIGHTS(TYPE A)	5,040.000	SD
0005	STAKING				
	0480	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION				
	0490	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
	0500	641 2100	MOBILIZATION	1.000	LSUM