Proposal:260163 **Let Date:**May 14, 2026 **Call Order:**823
J/P Num:25067(04) **Proj. Num:**STP-262N(103)UR
Counties:PONTOTOC
Description:INTERSECTION MODIFICATION AND TRAFFIC SIGNAL
SH-99 (MISSISSIPPI AVE): AT THE INTERSECTION OF
SH-1 (ARLINGTON ST) IN THE CITY OF ADA.
PROJECT LENGTH = 0.348 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	4,977.000	CY
0030	202(B)2300	MUCK EXCAVATION	100.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	2,058.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	88.000	LF
0070	221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	38.000	EA
0080	229 6100	DITCH LINER PROTECTION	215.000	LF
0090	230(A)7200	SOLID SLAB SODDING	9,591.000	SY
0100	233(A)0200	VEGETATIVE MULCHING	1.980	AC
0110	241 3100	MOWING	3.960	AC
0120	307(K)4200	STABILIZED SUBGRADE	15,285.000	SY
0130	310(B)5300	SUBGRADE, METHOD B	853.000	SY
0140	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	182.000	TON
0150	407(B)7300	TACK COAT	89.000	GAL
0160	408 8100	PRIME COAT	5,648.000	GAL
0170	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	2,777.000	TON
0180	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	66.000	TON
0190	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	14,377.000	SY
0200	414(G)5800	P.C. CONCRETE FOR PAVEMENT	3,318.000	CY
0210	509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	6.000	CY
0220	509(D)0500	CLASS C CONCRETE	34.000	CY
0230	510(A)1200	RETAINING WALL	26.000	SY
0240	601(A)1100	TYPE I PLAIN RIPRAP	96.000	TON
0250	609(A)4230	CONC.CURB(6" BARRIER-INTEGRAL)	3,703.000	LF
0260	609(A)4270	CONC.CURB(8" BARRIER-INTEGRAL)	1,441.000	LF
0270	609(B)4330	1'-8" COMB.CRB.& GUT.(6" BARRIER)	475.000	LF
0280	609(B)4345	1'-8" COMB.CRB.& GUT.(8" BARRIER)	132.000	LF
0290	610(A)5200	4" CONCRETE SIDEWALK	2,343.000	SY
0300	610(A)5230	8" CONCRETE SIDEWALK	11.000	SY
0310	610(B)5310	6" CONCRETE DRIVEWAY	870.000	SY
0320	610(C)5410	6" CONCRETE DIVIDING STRIP	907.000	SY
0330	610(I)6000	TACTILE WARNING DEVICE-NEW	216.000	SF
0340	610(J)6100	(PL) STAMPED CONCRETE FINISH	256.000	SY
0350	611(A)7210	MANHOLE (4' DIA.)	5.000	EA
0360	611(A)7220	MANHOLE (6' DIA.)	2.000	EA
0370	611(B)7300	ADD'L.DEPTH IN MANHOLE (4' DIA.)	10.000	VF
0380	611(B)7310	ADD'L.DEPTH IN MANHOLE (6' DIA.)	7.000	VF
0390	611(C)7300	REPLACEMENT OF MANHOLE FRAME & COVER	1.000	EA
0400	611(G)0354	INLET (SMD-TYPE 2)	3.000	EA
0410	611(G)7754	INLET CI DES. 2 (STD)	2.000	EA
0420	611(G)7786	INLET CI DES. 3 (STD)	6.000	EA
0430	611(G)7790	INLET CI DES. 3 (B)	1.000	EA
0440	611(G)9000	INLET CDI RCP DES. 1	1.000	EA
0450	611(H)0414	ADD'L DEPTH IN INLET CI DES. 2	7.000	VF
0460	611(H)0422	ADD'L DEPTH IN INLET CI DES. 3	14.000	VF

Proposal:260163 **Let Date:**May 14, 2026 **Call Order:**823
J/P Num:25067(04) **Proj. Num:**STP-262N(103)UR
Counties:PONTOTOC
Description:INTERSECTION MODIFICATION AND TRAFFIC SIGNAL SH-99 (MISSISSIPPI AVE): AT THE INTERSECTION OF SH-1 (ARLINGTON ST) IN THE CITY OF ADA. PROJECT LENGTH = 0.348 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0470	611(H)0424	ADD'L DEPTH IN INLET CI DES. 3B	3.000	VF
0480	611(H)0680	ADD'L DEPTH IN INLET CDI RCP DES. 1	1.000	VF
0490	611(L)1600	JUNCTION BOXES	178.000	CF
0500	612(A)3200	MANHOLES ADJUST TO GRADE	1.000	EA
0510	613(A)5208	18" R.C.PIPE CLASS III	502.000	LF
0520	613(A)5216	24" R.C.PIPE CLASS III	616.000	LF
0530	613(A)5232	48" R.C.PIPE CLASS III	338.000	LF
0540	613(A)5350	22" X 13" R.C.PIPE ARCH CLASS A-III	156.000	LF
0550	613(G)6150	PVC DRAINAGE STRUCTURE	7.000	LF
0560	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0570	613(L)6736	48" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0580	616(P)4164	24" HDPE PIPE	74.000	LF
0590	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0600	619(B)6356	REMOVAL OF CURB AND GUTTER	53.000	LF
0610	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	8,992.000	SY
0620	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	824.000	SY
0630	619(B)6372	REMOVAL OF MANHOLES	3.000	EA
0640	619(B)6376	REMOVAL OF CONC.PAV.W/ASPH.OVERLAY	4,510.000	SY
0650	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	3,626.000	SY
0660	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	590.000	SY
0670	619(B)6404	REMOVAL OF SIDEWALK	138.000	SY
0680	619(B)6440	REMOVAL OF EXISTING PIPE	892.000	LF
0690	619(B)6464	REMOVAL OF 6" CONCRETE DIVIDING STRIP	686.000	SY
0700	805(A)3200	REMOVAL OF SIGN FOOTING	41.000	EA
0710	880(C)6425	PERMANENT BARRICADE UNIT	1.000	EA
0002	SIGNING AND STRIPING			
0720	804(A)2200	STRUCTURAL CONCRETE	15.000	CY
0730	804(B)2300	REINFORCING STEEL	1,476.000	LB
0740	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	48.000	EA
0750	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	13.000	EA
0760	850(A)1200	SHEET ALUMINUM SIGNS	467.000	SF
0770	851(B)2315	3"@7.58 GALV.STL.PIPE POST	112.500	LF
0780	851(B)2320	3 1/2"@9.11 GALV.STL.PIPE POST	162.500	LF
0790	851(B)2325	4"@10.79 GALV.STL.PIPE POST	63.000	LF
0800	851(C)2415	2" SQUARE TUBE POST	276.000	LF
0810	851(C)2430	2 1/2" SQUARE TUBE POST	159.500	LF
0820	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	1,896.000	LF
0830	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	1,612.000	LF
0840	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	347.000	LF
0850	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	363.000	LF
0860	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	917.000	LF
0870	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	19.000	EA
0880	856(B)8311	(SP) TRAFFIC STRIPE(PLURAL-COMP)(SYMBOLS)	8.000	EA
0890	856(B)8315	(SP) TRAFFIC STRIPE(PLURAL-COMP)(WORDS)	4.000	EA

Proposal:260163 **Let Date:**May 14, 2026 **Call Order:**823
J/P Num:25067(04) **Proj. Num:**STP-262N(103)UR
Counties:PONTOTOC
Description:INTERSECTION MODIFICATION AND TRAFFIC SIGNAL
SH-99 (MISSISSIPPI AVE): AT THE INTERSECTION OF
SH-1 (ARLINGTON ST) IN THE CITY OF ADA.
PROJECT LENGTH = 0.348 MILES

Line #		Item Description	Quantity	Unit
0003	TRAFFIC SIGNAL			
0900	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	500.000	LF
0910	802(B)0328	3" PVC SCH.40 PLASTIC CONDUIT BORED	465.000	LF
0920	802(B)0332	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	255.000	LF
0930	803(A)1210	PULL BOX(SIZE I)	12.000	EA
0940	803(A)1220	PULL BOX(SIZE II)	1.000	EA
0950	804(A)2200	STRUCTURAL CONCRETE	37.000	CY
0960	804(B)2300	REINFORCING STEEL	5,317.000	LB
0970	806(A)4240	32'MH POLE 25'TS & 10'LMA(G.STL.)	1.000	EA
0980	806(A)4252	32'MH POLE 40'TS & 10'LMA(G.STL.)	2.000	EA
0990	806(A)4256	32'MH POLE 45'TS & 10'LMA(G.STL.)	2.000	EA
1000	806(A)4260	32'MH POLE 50'TS & 10'LMA(G.STL.)	1.000	EA
1010	806(B)4408	10' MTG.HT.TS PED.POLE(G.STL.)	3.000	EA
1020	806(B)4420	15' MTG.HT.TS PED.POLE(G.STL.)	2.000	EA
1030	810(A)8200	SERVICE POLE	1.000	EA
1040	811 9120	1/C NO.6 ELECT.COND.	750.000	LF
1050	811 9130	1/C NO.10 ELECT.COND.	3,930.000	LF
1060	811 9135	1/C NO.12 ELECT.COND.	3,000.000	LF
1070	825 8100	TRAFFIC SIGNAL CONTROLLER ASSEMBLY	1.000	EA
1080	828 0100	(PL)DETECTION SYSTEM (VIDEO)	1.000	LSUM
1090	830 2100	PEDESTRIAN PUSH BUTTON	6.000	EA
1100	831 3116	1WAY2SEC.ADJ.PED.SIG.HD.S-20	6.000	EA
1110	831 3120	1WAY3SEC.ADJ.SIG.HD.S-6	9.000	EA
1120	831 3124	1WAY3SEC.ADJ.SIG.HD.S-9	2.000	EA
1130	831 3128	1WAY3SEC.ADJ.SIG.HD.S-10	3.000	EA
1140	831 3144	1WAY4SEC.ADJ.SIG.HD.S-13	8.000	EA
1150	833 5100	BACKPLATE	22.000	EA
1160	834(A)6200	2/C TRAFFIC SIGNAL ELECTRICAL CABLE	60.000	LF
1170	834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	4,355.000	LF
1180	834(A)6210	7/C TRAFFIC SIGNAL ELECTRICAL CABLE	155.000	LF
1190	834(A)6215	9/C TRAFFIC SIGNAL ELECTRICAL CABLE	785.000	LF
1200	834(A)6235	21/C TRAFFIC SIGNAL ELECTRICAL CABLE	1,665.000	LF
1210	840(A)0200	E.P.S. OPTICAL EMITTER	4.000	EA
1220	840(B)0300	E.P.S. OPTICAL DETECTOR	6.000	EA
1230	840(C)0400	E.P.S. OPTICAL DETECTOR CABLE	1,905.000	LF
1240	840(D)0510	E.P.S. 4 CHANNEL PHASE SELECTOR	2.000	EA
1250	850(C)1400	MAST ARM MOUNTED SIGNS(ALUM.)	129.000	SF
1260	850(D)1510	SPECIAL SIGNS	2.000	EA

Proposal:260163 **Let Date:**May 14, 2026 **Call Order:**823
J/P Num:25067(04) **Proj. Num:**STP-262N(103)UR
Counties:PONTOTOC
Description:INTERSECTION MODIFICATION AND TRAFFIC SIGNAL
SH-99 (MISSISSIPPI AVE): AT THE INTERSECTION OF
SH-1 (ARLINGTON ST) IN THE CITY OF ADA.
PROJECT LENGTH = 0.348 MILES

Line #		Item Description	Quantity	Unit
0004	TRAFFIC CONTROL			
1270	104 3250	(SP) RAILROAD FLAGGING(NON-BIDDABLE)	35.000	DAY
1280	857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	3,970.000	LF
1290	857(C)9405	REMOVABLE PAVEMENT MARKING TAPE(6" WIDE)	18,907.000	LF
1300	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	19,725.000	LF
1310	858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	169.000	EA
1320	858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	651.000	EA
1330	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	1,462.500	LF
1340	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	3,182.000	LF
1350	880(A)6220	ARROW DISPLAY(TYPE C)	445.000	SD
1360	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	4,692.000	SD
1370	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	8,948.000	SD
1380	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	4,458.000	SD
1390	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	10,050.000	SD
1400	880(E)6607	WARNING LIGHTS(TYPE B)	21,817.000	SD
1410	880(E)6616	WARNING LIGHTS(TYPE D)	48,502.000	SD
1420	880(F)6700	DRUMS	48,502.000	SD
1430	880(G)6800	TUBE CHANNELIZERS	47,039.000	SD
1440	880(G)6805	CHANNELIZER CONES	15,882.000	SD
1450	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	1,334.000	SD
0005	STAKING			
1460	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
1470	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
1480	641 2110	MOBILIZATION	1.000	LSUM

Proposal:260163 **Let Date:**May 14, 2026 **Call Order:**823
J/P Num:25067(04) **Proj. Num:**STP-262N(103)UR
Counties:PONTOTOC
Description:INTERSECTION MODIFICATION AND TRAFFIC SIGNAL SH-99 (MISSISSIPPI AVE): AT THE INTERSECTION OF SH-1 (ARLINGTON ST) IN THE CITY OF ADA. PROJECT LENGTH = 0.348 MILES

Line #		Item Description	Quantity	Unit
0007	SEWER RELOCATION (NON-PARTICIPATING)			
1490	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
1500	202(A)2200	UNCLASSIFIED EXCAVATION	917.000	CY
1510	230(A)7200	SOLID SLAB SODDING	132.000	SY
1520	303(A)1200	AGGREGATE BASE TYPE A	715.000	CY
1530	411(H)1900	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	41.000	TON
1540	411(I)2005	SUPERPAVE, TYPE S4(PATCH)(PG70-28OK)	17.000	TON
1550	414(E)5600	FULL DEPTH P.C.C. PATCH (PLACEMENT)	420.000	SY
1560	414(G)5800	P.C. CONCRETE FOR PAVEMENT	93.000	CY
1570	501(G)1800	CLSM BACKFILL	6.000	CY
1580	501(H)1900	(PL) CELLULAR CONCRETE BACKFILL	16.000	CY
1590	510(A)1240	TEMPORARY RETAINING WALL	134.000	SY
1600	600(A)0200	(PL) AS-BUILT SURVEY	1.000	LSUM
1610	609(A)4230	CONC.CURB(6" BARRIER-INTEGRAL)	32.000	LF
1620	610(B)5300	6" CONCRETE DRIVEWAY (H.E.S.)	87.000	SY
1630	611(A)7205	MANHOLE TESTING	11.000	EA
1640	611(A)7210	MANHOLE (4' DIA.)	9.000	EA
1650	611(A)7220	MANHOLE (6' DIA.)	1.000	EA
1660	611(B)7300	ADD'L.DEPTH IN MANHOLE (4' DIA.)	19.000	VF
1670	612(B)3310	CONNECT TO EXISTING MANHOLE	2.000	EA
1680	613(T)7800	STANDARD BEDDING MATERIAL, CLASS C	202.000	CY
1690	613(Y)8300	(PL)VIDEO INSPECTION OF CONDUIT	1,511.000	LF
1700	615(A)1220	8" POLYVINYL CHLORIDE (PVC) PIPE	964.000	LF
1710	615(A)1224	10" POLYVINYL CHLORIDE (PVC) PIPE	479.000	LF
1720	615(B)1300	SANITARY SEWER SERVICE CONNECTION	14.000	EA
1730	615(C)1400	SANITARY SEWER SERVICE LINE	230.000	LF
1740	615(D)1500	SEWER LEAKAGE < 24" DIAMETER	1,429.000	LF
1750	615(E)1620	DEFLECTION TEST (8" PIPE)	1.000	LSUM
1760	615(F)1700	SEWER FLOW CONTROL	1.000	LSUM
1770	616(D)2862	8" X 8" TAPPING SADDLE	1.000	EA
1780	616(I)3321	14" STEEL CASING	60.000	LF
1790	616(I)3330	20" STEEL CASING	150.000	LF
1800	616(J)3435	BORE AND JACK 20" CASING	150.000	LF
1810	616(T)4575	8" X 8" X 4" TEE	13.000	EA
1820	619(B)6356	REMOVAL OF CURB AND GUTTER	32.000	LF
1830	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	362.000	SY
1840	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	154.000	SY
1850	619(B)6372	REMOVAL OF MANHOLES	4.000	EA
1860	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	87.000	SY
1870	619(B)6440	REMOVAL OF EXISTING PIPE	755.000	LF
1880	619(B)6556	PLUGGING ABANDONED SEWER	10.000	EA
1890	619(C)6600	SAWING PAVEMENT	132.000	LF