Proposal: 260165 **Let Date:** June 18, 2026 **Call Order:** 075
J/P Num: 36914(04) **Proj. Num:** C-MC-41
Counties: PAWNEE
Description: BRIDGE REHABILITATION
US-412 CIMARRON TURNPIKE: OVER UNNAMED CREEK, 2.43 MILES EAST OF THE SH-99 INTERCHANGE NEAR HALLETT.
PROJECT LENGTH = 0.314 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(A)2200	UNCLASSIFIED EXCAVATION	260.000	CY
0020	202(D)2500	UNCLASSIFIED BORROW	109.000	CY
0030	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0040	221(B)2300	TEMPORARY SILT FENCE	3,368.000	LF
0050	230(A)7200	SOLID SLAB SODDING	2,331.000	SY
0060	303(A)1200	AGGREGATE BASE TYPE A	5.000	CY
0070	310(B)5300	SUBGRADE, METHOD B	2,680.000	SY
0080	407(B)7300	TACK COAT	364.000	GAL
0090	408 8100	PRIME COAT	1,130.000	GAL
0100	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	185.000	TON
0110	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	220.000	TON
0120	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	1,804.000	SY
0130	414(G)5800	P.C. CONCRETE FOR PAVEMENT	451.000	CY
0140	509(A)0200	CLASS AA CONCRETE	14.000	CY
0150	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	1,803.000	SY
0160	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	3,577.000	SY
0170	619(B)6396	REMOVAL OF GUARDRAIL	1,057.000	LF
0180	623 1100	(PL)GUARDRAIL CURBING	4.000	EA
0190	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	1,188.000	LF
0200	623(F)1764	GUARDRAIL TRAIL END TURNDOWN (31")	2.000	EA
0210	623(G)1820	GUARDRAIL END TREATMENT (31")	2.000	EA
0220	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	4.000	EA

Proposal:260165 **Let Date:**June 18, 2026 **Call Order:**075
J/P Num:36914(04) **Proj. Num:**C-MC-41
Counties:PAWNEE
Description:BRIDGE REHABILITATION
US-412 CIMARRON TURNPIKE: OVER UNNAMED CREEK, 2.43 MILES EAST OF THE SH-99 INTERCHANGE NEAR HALLETT.
PROJECT LENGTH = 0.314 MILES

Line #		Item Description	Quantity	Unit
0002	BRIDGE #50.83			
0230	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	20.000	CY
0240	501(G)1800	CLSM BACKFILL	432.800	CY
0250	504(A)5200	APPROACH SLAB	729.800	SY
0260	504(B)5300	SAW-CUT GROOVING	1,621.900	SY
0270	504(E)5520	42" F-SHAPED PARAPET	352.000	LF
0280	506(A)7200	STRUCTURAL STEEL	318,120.000	LB
0290	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	12.000	EA
0300	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	12.000	EA
0310	509(A)0210	CLASS AA CONCRETE	229.200	CY
0320	509(B)0320	CLASS A CONCRETE	1.000	CY
0330	509(D)0510	CLASS C CONCRETE	12.000	CY
0340	511 2100	MECHANICAL SPLICES	12.000	EA
0350	511(B)2310	EPOXY COATED REINFORCING STEEL	52,130.000	LB
0360	513(A)4200	CLASS A BRIDGE DECK REPAIR	10.000	SY
0370	513(B)4300	CLASS B BRIDGE DECK REPAIR	40.000	SY
0380	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	2,080.000	SY
0390	517 9110	ELASTOMERIC COATING	724.000	SF
0400	518(B)0310	EXPANSION JOINT SYSTEM	86.000	LF
0410	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	12.000	LF
0420	520(C)1400	EPOXY RESIN, ABOVE WATER	1.000	GAL
0430	521(A)2200	PNEUMATICALLY PLACED MORTAR	27.200	SY
0440	523(A)3200	SEALER CRACK PREPARATION	199.000	LF
0450	523(B)3300	SEALER RESIN	2.200	GAL
0460	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	34.000	SY
0470	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
0003	TRAFFIC CONTROL			
0480	413(D)4510	RUMBLE STRIP METHOD PCC-CYC	2,164.000	LF
0490	857(A)9200	CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE)	11,380.000	LF
0500	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	15,842.000	LF
0510	871(B)2300	CONST.ZONE IMPACT ATTEN.	220.000	SD
0520	871(C)2410	RELOCATION OF IMPACT ATTENUATOR	4.000	EA
0530	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	3,730.000	LF
0540	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	7,298.000	LF
0550	880(A)6220	ARROW DISPLAY(TYPE C)	80.000	SD
0560	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	5,040.000	SD
0570	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	6,320.000	SD
0580	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	6,040.000	SD
0590	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,560.000	SD
0600	880(E)6600	WARNING LIGHTS(TYPE A)	7,360.000	SD
0610	880(F)6700	DRUMS	9,400.000	SD
0620	880(G)6800	TUBE CHANNELIZERS	2,660.000	SD
0630	880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	720.000	HOUR
0640	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	388.000	SD

Proposal: 260165 **Let Date:** June 18, 2026 **Call Order:** 075
J/P Num: 36914(04) **Proj. Num:** C-MC-41
Counties: PAWNEE
Description: BRIDGE REHABILITATION
US-412 CIMARRON TURNPIKE: OVER UNNAMED CREEK, 2.43 MILES EAST OF THE SH-99 INTERCHANGE NEAR HALLETT.
PROJECT LENGTH = 0.314 MILES

Line #		Item Description	Quantity	Unit
0004	TRAFFIC SIGN AND STRIPE			
0650	619(B)6432	REMOVAL OF CABLE BARRIER	1,658.000	LF
0660	628 7100	INSTALLATION OF CABLE BARRIER SYSTEM	1,658.000	LF
0670	628(C)7400	END ANCHORS	4.000	EA
0680	628(E)7600	CABLE BARRIER TENSION METER	1.000	EA
0690	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	2.000	EA
0700	853 5170	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	28.000	EA
0710	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	14,752.000	LF
0005	STAKING			
0720	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
0730	641 2100	MOBILIZATION	1.000	LSUM