Proposal: 260169 **Let Date:** July 09, 2026 **Call Order:** 310
J/P Num: 34576(04) **Proj. Num:** STP-230C(057)CI
Counties: HARPER
Description: BRIDGE AND APPROACHES
COUNTY RD (EW-03): OVER LODGEPOLE CREEK,
6.70 MILES EAST OF US-183 NEAR BUFFALO.
PROJECT LENGTH = 0.350 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	4,894.000	CY
0030	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0040	221(B)2300	TEMPORARY SILT FENCE	3,420.000	LF
0050	221(E)2600	TEMPORARY SILT DIKE	504.000	LF
0060	230(A)7200	SOLID SLAB SODDING	13,050.000	SY
0070	233(A)0200	VEGETATIVE MULCHING	2.970	AC
0080	307(K)4200	STABILIZED SUBGRADE	5,501.000	SY
0090	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	231.000	TON
0100	408 8100	PRIME COAT	1,927.000	GAL
0110	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	1,133.000	TON
0120	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	542.000	TON
0130	509(D)0500	CLASS C CONCRETE	10.000	CY
0140	613(B)5508	18" CORR. GALV. STEEL PIPE	50.000	LF
0150	613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0160	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0170	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	4,456.000	SY
0180	619(C)6600	SAWING PAVEMENT	44.000	LF
0190	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	200.000	LF
0200	623(F)1764	GUARDRAIL TRAIL END TURNDOWN (31")	4.000	EA
0210	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	157.000	LF
0002	BRIDGE			
0220	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	120.000	CY
0230	501(F)1700	GRANULAR BACKFILL	40.000	CY
0240	503(D)6200	PRESTRESSED CONCRETE SLAB	239.500	LF
0250	504 5130	BRIDGE TRAFFIC RAIL	80.000	LF
0260	506(A)7200	STRUCTURAL STEEL	1,050.000	LB
0270	507(C)8400	ELASTOMERIC BEARING PADS	24.000	EA
0280	509(B)0320	CLASS A CONCRETE	40.400	CY
0290	511(A)2210	REINFORCING STEEL	4,620.000	LB
0300	514(A)5210	PILES, FURNISHED (HP 10X42)	400.000	LF
0310	514(B)5310	PILES, DRIVEN (HP 10X42)	400.000	LF
0320	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0330	601(B)1210	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	378.000	TON
0340	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	112.000	LF
0350	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	60.000	LF
0360	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0003	TRAFFIC			
0370	850(A)1200	SHEET ALUMINUM SIGNS	12.500	SF
0380	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	3,700.000	LF
0390	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	2,400.000	SD
0400	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	240.000	SD
0410	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,920.000	SD
0420	880(E)6600	WARNING LIGHTS(TYPE A)	4,800.000	SD

Proposal: 260169 **Let Date:** July 09, 2026 **Call Order:** 310
J/P Num: 34576(04) **Proj. Num:** STP-230C(057)CI
Counties: HARPER
Description: BRIDGE AND APPROACHES
COUNTY RD (EW-03): OVER LODGEPOLE CREEK,
6.70 MILES EAST OF US-183 NEAR BUFFALO.
PROJECT LENGTH = 0.350 MILES

Line #		Item Description	Quantity	Unit
0004	STAKING			
0430	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0440	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0450	641 2100	MOBILIZATION	1.000	LSUM