Proposal:260170 **Let Date:**July 09, 2026 **Call Order:**320
J/P Num:31804(04) **Proj. Num:**STP-234C(069)CI
Counties:JEFFERSON
Description:BRIDGE AND APPROACHES
COUNTY ROAD (EW-2150): OVER FLEETWOOD CREEK,
5.2 MILES EAST OF US-81 NEAR TERRAL.
PROJECT LENGTH = 0.184 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	730.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	965.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	282.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	336.000	LF
0070	221(F)2720	TEMPORARY ROCK FILTER DAM TYPE 3	75.000	CY
0080	230(A)7200	SOLID SLAB SODDING	6,462.000	SY
0090	233(A)0200	VEGETATIVE MULCHING	2.400	AC
0100	307(K)4200	STABILIZED SUBGRADE	2,636.000	SY
0110	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	223.000	TON
0120	408 8100	PRIME COAT	1,081.000	GAL
0130	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	569.000	TON
0140	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	305.000	TON
0150	509(D)0500	CLASS C CONCRETE	10.000	CY
0160	602(B)2310	REVETMENT MATTRESSES	1,301.000	SY
0170	613(B)5604	21" X 15" CORR. GALV. STEEL PIPE ARCH	107.000	LF
0180	613(L)6608	21" X 15" PREFAB. CULVERT END SEC., ARCH	6.000	EA
0190	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0200	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	1,539.000	SY
0210	623(F)1704	GUARDRAIL ANCHOR UNIT (TYPE A)	4.000	EA
0220	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	1,026.000	LF
0230	629(D)7500	REMOVE AND RESET MAILBOX	1.000	EA
0002	BRIDGE 'A' - NBI NO. 33110			
0240	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	840.000	CY
0250	501(E)1600	SELECT BACKFILL	570.000	CY
0260	508 9110	PRECAST ARCH CULVERT	40.000	LF
0270	509(B)0320	CLASS A CONCRETE	99.800	CY
0280	509(D)0510	CLASS C CONCRETE	10.000	CY
0290	511(A)2210	REINFORCING STEEL	9,280.000	LB
0300	514(A)5220	PILES, FURNISHED (HP 12X53)	1,410.000	LF
0310	514(B)5320	PILES, DRIVEN (HP 12X53)	1,410.000	LF
0320	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0330	601(B)1210	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	420.000	TON
0340	602(B)2320	REVETMENT MATTRESS	135.000	SY
0350	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	132.000	LF
0360	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	40.000	LF
0370	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0003	TRAFFIC			
0380	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,495.000	SD
0390	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,944.000	SD
0400	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,196.000	SD
0410	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	897.000	SD
0420	880(E)6600	WARNING LIGHTS(TYPE A)	2,990.000	SD

Proposal: 260170 **Let Date:** July 09, 2026 **Call Order:** 320
J/P Num: 31804(04) **Proj. Num:** STP-234C(069)CI
Counties: JEFFERSON
Description: BRIDGE AND APPROACHES
COUNTY ROAD (EW-2150): OVER FLEETWOOD CREEK,
5.2 MILES EAST OF US-81 NEAR TERRAL.
PROJECT LENGTH = 0.184 MILES

Line #		Item Description	Quantity	Unit
0004	STAKING			
0430	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0440	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0450	641 2100	MOBILIZATION	1.000	LSUM