Proposal: 260174 **Let Date:** July 09, 2026 **Call Order:** 380
J/P Num: 31282(04) **Proj. Num:** CIRB-264D(110)RB
Counties: PUSHMATAHA
Description: GRADE, DRAIN AND SURFACE
COUNTY ROAD (GREENWOOD ROAD/NS-418):
FROM 0.16 MILES SOUTH OF SH-3, EXTEND SOUTH NEAR ANTLERS.
PROJECT LENGTH = 2.574 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(A)2200	UNCLASSIFIED EXCAVATION	30,969.000	CY
0020	202(C)2400	ROCK EXCAVATION	1,549.000	CY
0030	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0040	221(B)2300	TEMPORARY SILT FENCE	5,431.000	LF
0050	221(E)2600	TEMPORARY SILT DIKE	784.000	LF
0060	230(A)7200	SOLID SLAB SODDING	101,500.000	SY
0070	233(A)0200	VEGETATIVE MULCHING	20.970	AC
0080	241 3100	MOWING	20.970	AC
0090	307(K)4200	STABILIZED SUBGRADE	43,721.000	SY
0095	325 0100	SEPARATOR FABRIC	47,662.000	SY
0100	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	3,910.000	TON
0110	407(B)7300	TACK COAT	5,642.000	GAL
0120	408 8100	PRIME COAT	17,394.000	GAL
0130	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	10,728.000	TON
0140	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	4,190.000	TON
0150	412 3100	COLD MILLING PAVEMENT	28,445.000	SY
0160	509(D)0500	CLASS C CONCRETE	725.000	CY
0170	601(A)1100	TYPE I PLAIN RIPRAP	134.000	TON
0180	609(B)4360	2'-8" COMB.CRB.& GUT.(6" BARRIER)	1,829.000	LF
0190	610(B)5310	6" CONCRETE DRIVEWAY	143.000	SY
0200	613(A)5216	24" R.C.PIPE CLASS III	186.000	LF
0210	613(A)5224	36" R.C.PIPE CLASS III	192.000	LF
0220	613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	22.000	EA
0230	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	24.000	EA
0240	613(L)6728	36" PREFAB. CULVERT END SEC., ROUND	6.000	EA
0250	616(P)4160	18" HDPE PIPE	272.000	LF
0260	616(P)4164	24" HDPE PIPE	406.000	LF
0270	616(P)4176	36" HDPE PIPE	86.000	LF
0280	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0290	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	110.000	SY
0300	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	116.000	SY
0310	619(C)6600	SAWING PAVEMENT	140.000	LF
0320	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	100.000	LF
0330	623(F)1724	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA
0340	623(G)1800	GUARDRAIL END TREATMENT (GET)	4.000	EA
0350	629(A)7200	MAILBOX INSTALLATION-SINGLE	5.000	EA
0360	629(C)7400	REMOVAL OF MAILBOX INSTALLATION	5.000	EA
0002	SIGNING AND STRIPING			
0370	850(A)1200	SHEET ALUMINUM SIGNS	50.000	SF
0380	851(C)2415	2" SQUARE TUBE POST	87.000	LF
0390	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	56,196.000	LF
0400	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	60.000	LF

Proposal:260174 **Let Date:**July 09, 2026 **Call Order:**380
J/P Num:31282(04) **Proj. Num:**CIRB-264D(110)RB
Counties:PUSHMATAHA
Description:GRADE, DRAIN AND SURFACE
COUNTY ROAD (GREENWOOD ROAD/NS-418):
FROM 0.16 MILES SOUTH OF SH-3, EXTEND SOUTH NEAR ANTLERS.
PROJECT LENGTH = 2.574 MILES

Line #		Item Description	Quantity	Unit
0003	TRAFFIC CONTROL			
0410	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	1.000	EA
0420	853 5110	DELINEATORS(TYPE 1, CODE 3)	4.000	EA
0430	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	3,240.000	SD
0440	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,980.000	SD
0450	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,440.000	SD
0460	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,260.000	SD
0470	880(E)6600	WARNING LIGHTS(TYPE A)	1,260.000	SD
0480	880(I)7000	FLAGGER	180.000	SD
0490	880(W)7700	PILOT CAR	1.000	LSUM
0500	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	180.000	SD
0004	STAKING			
0510	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0520	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0530	641 2110	MOBILIZATION	1.000	LSUM