Proposal:260177 **Let Date:**July 16, 2026 **Call Order:**088
J/P Num:37600(09) **Proj. Num:**WR-31703A
Counties:ROGERS
Description:GRADE, DRAIN, BRIDGE AND SURFACE
OTA ACCESS: WILL ROGERS TURNPIKE (I-44):
OVER VERDIGRIS OVERFLOW AND MOSSY CREEK,
3.4 MILES NORTHEAST OF THE US-412
INTERCHANGE NEAR CATOOSA.
PROJECT LENGTH = 1.003 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	18,872.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	183,292.000	CY
0040	202(F)2700	EMBANKMENTS	128.000	CY
0050	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0060	221(B)2300	TEMPORARY SILT FENCE	13,073.000	LF
0070	221(E)2600	TEMPORARY SILT DIKE	588.000	LF
0080	221(F)2730	TEMPORARY ROCK FILTER DAM TYPE 4	9.000	CY
0090	221(M)3400	TEMPORARY ENVIRONMENTAL FENCE	350.000	LF
0100	230(A)7200	SOLID SLAB SODDING	170,132.000	SY
0110	241 3100	MOWING	32.330	AC
0120	242 4101	STABILIZED CONSTRUCTION EXIT	4.000	EA
0130	303(A)1200	AGGREGATE BASE TYPE A	14,672.000	CY
0140	307(K)4200	STABILIZED SUBGRADE	69,748.000	SY
0150	325 0100	SEPARATOR FABRIC	77,757.000	SY
0160	326(C)1100	(SP) WOVEN GEOSYNTHETIC REINFORCEMENT FABRIC	1,149.000	SY
0170	402(D)2500	TRAFFIC BOUND SURFACE COURSE TYPE D	86.000	TON
0180	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	14,581.000	TON
0190	407(B)7300	TACK COAT	15,195.000	GAL
0200	408 8100	PRIME COAT	43,198.000	GAL
0210	411(B)1300	SUPERPAVE, TYPE S3(PG 76-28 OK)	6,788.000	TON
0220	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	28,948.000	TON
0230	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	2,504.000	TON
0240	411(F)1700	STONE MATRIX ASPHALT	4,404.000	TON
0250	411(G)1800	RICH BOTTOM LAYER	10,703.000	TON
0260	509(B)0300	CLASS A CONCRETE	107.000	CY
0270	509(D)0500	CLASS C CONCRETE	77.000	CY
0280	511(A)2200	REINFORCING STEEL	14,841.000	LB
0290	601(A)1100	TYPE I PLAIN RIPRAP	36.000	TON
0300	613(B)5536	48" CORR. GALV. STEEL PIPE	180.000	LF
0310	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0320	619(B)6352	REMOVAL OF FENCE	4,912.000	LF
0330	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	45,650.000	SY
0340	619(B)6396	REMOVAL OF GUARDRAIL	10,160.000	LF
0350	619(B)6416	REMOVAL OF CONCRETE MEDIAN BARRIER	3,950.000	LF
0360	619(B)6440	REMOVAL OF EXISTING PIPE	180.000	LF
0370	619(C)6600	SAWING PAVEMENT	4,706.000	LF
0380	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	4,775.000	LF
0390	623(F)1764	GUARDRAIL TRAIL END TURNDOWN (31")	4.000	EA
0400	623(G)1800	GUARDRAIL END TREATMENT (GET)	4.000	EA
0410	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	8.000	EA
0420	624(A)3200	FENCE-STYLE WWF	4,515.000	LF
0430	627(A)6200	CONCRETE LONGITUDINAL BARRIER, DESIGN 1	4,009.000	LF

Proposal:260177 **Let Date:**July 16, 2026 **Call Order:**088
J/P Num:37600(09) **Proj. Num:**WR-31703A
Counties:ROGERS
Description:GRADE, DRAIN, BRIDGE AND SURFACE
OTA ACCESS: WILL ROGERS TURNPIKE (I-44):
OVER VERDIGRIS OVERFLOW AND MOSSY CREEK,
3.4 MILES NORTHEAST OF THE US-412
INTERCHANGE NEAR CATOOSA.
PROJECT LENGTH = 1.003 MILES

Line #		Item Description	Quantity	Unit
0002	BRIDGE 3.30			
0440	202(A)2210	UNCLASSIFIED EXCAVATION	745.000	CY
0450	501(A)1210	STRUCTURAL EXCAVATION UNCLASSIFIED	205.000	CY
0460	502 3100	TEMPORARY EARTH RETAINAGE	1.000	LSUM
0470	509(A)0210	CLASS AA CONCRETE	448.300	CY
0480	511(A)2210	REINFORCING STEEL	61,990.000	LB
0490	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
0003	BRIDGE 3.80			
0500	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	600.000	CY
0510	501(G)1800	CLSM BACKFILL	584.000	CY
0520	502 3100	TEMPORARY EARTH RETAINAGE	1.000	LSUM
0530	504(A)5200	APPROACH SLAB	833.600	SY
0540	504(B)5300	SAW-CUT GROOVING	6,650.000	SY
0550	504(E)5520	42" F-SHAPED PARAPET	2,012.800	LF
0560	506(A)7225	STRUCTURAL STEEL M270 GRADE 50W	1,747,050.000	LB
0570	507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	56.000	EA
0580	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	56.000	EA
0590	509(A)0210	CLASS AA CONCRETE	1,529.100	CY
0600	509(B)0320	CLASS A CONCRETE	780.300	CY
0610	509(D)0510	CLASS C CONCRETE	25.000	CY
0620	511 2100	MECHANICAL SPLICES	4,058.000	EA
0630	511(A)2210	REINFORCING STEEL	4,320.000	LB
0640	511(B)2310	EPOXY COATED REINFORCING STEEL	433,900.000	LB
0650	513(B)4300	CLASS B BRIDGE DECK REPAIR	100.000	SY
0660	513(C)4400	CLASS C BRIDGE DECK REPAIR	100.000	SY
0670	514(A)5210	PILES, FURNISHED (HP 10X42)	350.000	LF
0680	514(A)5220	PILES, FURNISHED (HP 12X53)	2,874.000	LF
0690	514(B)5310	PILES, DRIVEN (HP 10X42)	350.000	LF
0700	514(B)5320	PILES, DRIVEN (HP 12X53)	2,874.000	LF
0710	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0720	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	9,919.000	SY
0730	516(A)8240	DRILLED SHAFTS 60" DIAMETER	1,278.000	LF
0740	516(C)8400	CROSSHOLE SONIC LOGGING	3.000	EA
0750	517 9110	ELASTOMERIC COATING	5,529.000	SF
0760	518(B)0310	EXPANSION JOINT SYSTEM	245.370	LF
0770	523(A)3200	SEALER CRACK PREPARATION	1,892.000	LF
0780	523(B)3300	SEALER RESIN	19.000	GAL
0790	601(B)1210	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	6,610.000	TON
0800	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	252.000	LF
0810	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	44.000	LF
0820	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

Proposal:260177 **Let Date:**July 16, 2026 **Call Order:**088
J/P Num:37600(09) **Proj. Num:**WR-31703A
Counties:ROGERS
Description:GRADE, DRAIN, BRIDGE AND SURFACE
OTA ACCESS: WILL ROGERS TURNPIKE (I-44):
OVER VERDIGRIS OVERFLOW AND MOSSY CREEK,
3.4 MILES NORTHEAST OF THE US-412
INTERCHANGE NEAR CATOOSA.
PROJECT LENGTH = 1.003 MILES

Line #		Item Description	Quantity	Unit
0004	BRIDGE 4.20			
0830	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	610.000	CY
0840	501(G)1800	CLSM BACKFILL	586.000	CY
0850	502 3100	TEMPORARY EARTH RETAINAGE	1.000	LSUM
0860	504(A)5200	APPROACH SLAB	833.600	SY
0870	504(B)5300	SAW-CUT GROOVING	11,985.000	SY
0880	504(E)5520	42" F-SHAPED PARAPET	3,627.400	LF
0890	506(A)7225	STRUCTURAL STEEL M270 GRADE 50W	3,175,990.000	LB
0900	507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	112.000	EA
0910	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	112.000	EA
0920	509(A)0210	CLASS AA CONCRETE	2,920.300	CY
0930	509(B)0320	CLASS A CONCRETE	1,553.500	CY
0940	509(D)0510	CLASS C CONCRETE	25.000	CY
0950	511 2100	MECHANICAL SPLICES	7,586.000	EA
0960	511(A)2210	REINFORCING STEEL	12,020.000	LB
0970	511(B)2310	EPOXY COATED REINFORCING STEEL	824,620.000	LB
0980	513(B)4300	CLASS B BRIDGE DECK REPAIR	200.000	SY
0990	513(C)4400	CLASS C BRIDGE DECK REPAIR	200.000	SY
1000	514(A)5210	PILES, FURNISHED (HP 10X42)	330.000	LF
1010	514(A)5220	PILES, FURNISHED (HP 12X53)	2,704.000	LF
1020	514(B)5310	PILES, DRIVEN (HP 10X42)	330.000	LF
1030	514(B)5320	PILES, DRIVEN (HP 12X53)	2,704.000	LF
1040	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
1050	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	18,107.000	SY
1060	516(A)8240	DRILLED SHAFTS 60" DIAMETER	2,544.000	LF
1070	516(C)8400	CROSSHOLE SONIC LOGGING	7.000	EA
1080	517 9110	ELASTOMERIC COATING	9,243.000	SF
1090	518(B)0310	EXPANSION JOINT SYSTEM	490.720	LF
1100	523(A)3200	SEALER CRACK PREPARATION	3,744.000	LF
1110	523(B)3300	SEALER RESIN	37.500	GAL
1120	601(B)1210	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	7,540.000	TON
1130	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	252.000	LF
1140	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	44.000	LF
1150	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0005	TRAFFIC SIGNING AND STRIPING			
1160	413(A)4200	RUMBLE STRIP-METHOD HMA-CON	17,279.000	LF
1170	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	7.000	EA
1180	853 5165	BARRIER DELINEATORS(TYPE 2, CODE 1)	99.000	EA
1190	853 5170	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	104.000	EA
1200	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	45,221.000	LF

Proposal:260177 **Let Date:**July 16, 2026 **Call Order:**088
J/P Num:37600(09) **Proj. Num:**WR-31703A
Counties:ROGERS
Description:GRADE, DRAIN, BRIDGE AND SURFACE
OTA ACCESS: WILL ROGERS TURNPIKE (I-44):
OVER VERDIGRIS OVERFLOW AND MOSSY CREEK,
3.4 MILES NORTHEAST OF THE US-412
INTERCHANGE NEAR CATOOSA.
PROJECT LENGTH = 1.003 MILES

	Line #		Item Description	Quantity	Unit
0006	TRAFFIC CONTROL				
	1210	857(C)9400	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	97,865.000	LF
	1215	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	97,865.000	LF
	1220	871(B)2300	CONST.ZONE IMPACT ATTEN.	2,260.000	SD
	1230	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	16,497.000	LF
	1240	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	12,116.000	LF
	1250	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	13,560.000	SD
	1260	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	4,520.000	SD
	1270	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	13,452.000	SD
	1280	880(E)6607	WARNING LIGHTS(TYPE B)	13,560.000	SD
	1290	880(F)6700	DRUMS	62,991.000	SD
	1300	880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	360.000	HOUR
	1310	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	1,144.000	SD
0007	STAKING				
	1320	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0008	CONSTRUCTION				
	1330	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
	1340	640(A)1200	FIELD OFFICE	1.000	EA
	1350	641 2100	MOBILIZATION	1.000	LSUM