Proposal:260178 **Let Date:**July 16, 2026 **Call Order:**400
J/P Num:31772(04) **Proj. Num:**STP-202D(085)CI
Counties:ALFALFA
Description:BRIDGE AND APPROACHES
COUNTY ROAD (NS-2720): OVER TURKEY CREEK, 1.0 MILE WEST OF THE SH-45 JUNCTION NEAR ENID.
PROJECT LENGTH = 0.233 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	716.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	4,009.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	1,150.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	728.000	LF
0070	230(A)7200	SOLID SLAB SODDING	7,986.000	SY
0080	233(A)0200	VEGETATIVE MULCHING	1.650	AC
0090	303(A)1200	AGGREGATE BASE TYPE A	497.000	CY
0100	509(D)0500	CLASS C CONCRETE	10.000	CY
0110	613(A)5208	18" R.C.PIPE CLASS III	34.000	LF
0120	613(A)5374	51" X 31" R.C.PIPE ARCH CLASS A-III	96.000	LF
0130	613(L)6656	51" X 31" PREFAB. CULVERT END SEC., ARCH	6.000	EA
0140	613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0150	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0160	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	25.000	LF
0170	623(F)1704	GUARDRAIL ANCHOR UNIT (TYPE A)	2.000	EA
0180	623(F)1724	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA
0190	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	395.000	LF
0002	BRIDGE			
0200	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	100.000	CY
0210	501(G)1800	CLSM BACKFILL	70.000	CY
0220	503(A)4200	PRESTRESSED CONCRETE BEAMS	378.630	LF
0230	504(D)5410	CONCRETE RAIL (TR3)	129.600	LF
0240	506(A)7200	STRUCTURAL STEEL	965.000	LB
0250	507(C)8400	ELASTOMERIC BEARING PADS	12.000	EA
0260	509(A)0210	CLASS AA CONCRETE	34.300	CY
0270	509(B)0320	CLASS A CONCRETE	44.200	CY
0280	511(A)2210	REINFORCING STEEL	12,570.000	LB
0290	514(A)5210	PILES, FURNISHED (HP 10X42)	1,096.000	LF
0300	514(B)5310	PILES, DRIVEN (HP 10X42)	1,096.000	LF
0310	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0320	601(B)1210	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	535.000	TON
0330	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0003	TRAFFIC			
0340	850(A)1200	SHEET ALUMINUM SIGNS	10.360	SF
0350	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	4,800.000	SD
0360	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	480.000	SD
0370	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	3,840.000	SD
0380	880(E)6600	WARNING LIGHTS(TYPE A)	9,600.000	SD
0004	STAKING			
0390	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM

Proposal: 260178 **Let Date:** July 16, 2026 **Call Order:** 400
J/P Num: 31772(04) **Proj. Num:** STP-202D(085)CI
Counties: ALFALFA
Description: BRIDGE AND APPROACHES
COUNTY ROAD (NS-2720): OVER TURKEY CREEK, 1.0 MILE WEST OF THE SH-45 JUNCTION NEAR ENID.
PROJECT LENGTH = 0.233 MILES

Line #		Item Description	Quantity	Unit
0005	CONSTRUCTION			
0400	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0410	641 2100	MOBILIZATION	1.000	LSUM