Proposal: 260180 **Let Date:** July 16, 2026 **Call Order:** 420
J/P Num: 38536(04) **Proj. Num:** STP-267C(123)PM
Counties: SEMINOLE
Description: RESURFACE (ASPHALT)
SH-9: FROM THE US-270 JUNCTION, EXTEND EAST NEAR SEMINOLE.
PROJECT LENGTH = 5.86 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(D)2500	UNCLASSIFIED BORROW	600.000	CY
0020	402(A)2200	TRAFFIC BOUND SURFACE COURSE TYPE A	60.000	TON
0030	407(B)7300	TACK COAT	10,992.000	GAL
0040	411(D)1530	SUPERPAVE, TYPE S5(PG 64-22 OK)	7,942.000	TON
0050	412 3100	COLD MILLING PAVEMENT	9,275.000	SY
0002	TRAFFIC			
0060	413(A)4210	RUMBLE STRIP-CENTERLINE HMA-CON	22,760.000	LF
0070	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	87,965.000	LF
0080	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	1,158.000	LF
0090	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	72.000	LF
0100	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	2.000	EA
0110	858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	386.000	EA
0120	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	840.000	SD
0130	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	252.000	SD
0140	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,897.000	SD
0150	880(E)6607	WARNING LIGHTS(TYPE B)	420.000	SD
0160	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	98.000	SD