Proposal:260182 **Let Date:**August 13, 2026 **Call Order:**500
J/P Num:36282(04) **Proj. Num:**SSP-013N(251)PM
Counties:ATOKA
Description:PAVEMENT REHABILITATION (ASPHALT)
US-69: FROM 2.43 MILES NORTH OF THE SH-22 INTERSECTION,
EXTEND NORTH NEAR CANEY.
PROJECT LENGTH = 4.89 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	200.000	TON
0020	407(B)7300	TACK COAT	19,815.000	GAL
0030	411(B)1310	(SP) SUPERPAVE, TYPE S3(PG 76-28 E)	15,710.000	TON
0040	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	11,815.000	TON
0050	411(C)1410	(SP) SUPERPAVE, TYPE S4(PG 76-28 E)	8,980.000	TON
0060	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	2,570.000	TON
0070	411(J)2100	(SP) RICH INTERMEDIATE LAYER	6,735.000	TON
0080	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	86,140.000	SY
0090	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	21,730.000	SY
0100	619(C)6600	SAWING PAVEMENT	25,840.000	LF
0002	TRAFFIC			
0110	413(A)4200	RUMBLE STRIP-METHOD HMA-CON	24,600.000	LF
0120	413(B)4310	RUMBLE STRIP-METHOD HMA-CYC	25,400.000	LF
0130	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	73,000.000	LF
0140	857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	203,100.000	LF
0150	857(E)9630	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-2	264.000	EA
0160	857(F)9740	PAVEMENT MARKING REMOVAL (HYDROBLASTING)	141,500.000	LF
0170	858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	323.000	EA
0180	876(A)3210	(PL)TRUCK MOUNTED ATTENUATOR	120.000	SD
0190	880(A)6220	ARROW DISPLAY(TYPE C)	120.000	SD
0200	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	2,160.000	SD
0210	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	3,360.000	SD
0220	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	2,880.000	SD
0230	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,680.000	SD
0240	880(D)6500	VERTICAL PANELS	15,840.000	SD
0250	880(E)6600	WARNING LIGHTS(TYPE A)	3,360.000	SD
0260	880(E)6607	WARNING LIGHTS(TYPE B)	8,400.000	SD
0270	880(E)6616	WARNING LIGHTS(TYPE D)	45,960.000	SD
0280	880(F)6700	DRUMS	30,120.000	SD
0290	880(K)7200	SURVEILLANCE TRAFFIC CONTROL	120.000	SD
0300	880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	300.000	HOUR
0310	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	268.000	SD
0003	CONSTRUCTION			
0320	641 2110	MOBILIZATION	1.000	LSUM