Proposal:260184 **Let Date:**August 13, 2026 **Call Order:**515
J/P Num:31962(04) **Proj. Num:**NHPP-013N(254)PM
Counties:CRAIG
Description:PAVEMENT REHABILITATION
US-69: FROM 1.07 MILES SOUTH OF THE I-44 INTERCHANGE,
EXTEND NORTH NEAR BIG CABIN.
PROJECT LENGTH = 1.513 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	32,472.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	2,922.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	7,710.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	1,918.000	LF
0070	221(F)2700	TEMPORARY ROCK FILTER DAM TYPE 1	25.000	CY
0080	221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	8.000	EA
0090	230(A)7200	SOLID SLAB SODDING	73,493.000	SY
0100	233(A)0200	VEGETATIVE MULCHING	15.180	AC
0110	241 3100	MOWING	30.360	AC
0120	242 4101	STABILIZED CONSTRUCTION EXIT	2.000	EA
0130	307(K)4200	STABILIZED SUBGRADE	53,004.000	SY
0140	317 7100	CEMENT TREATED BASE	49,079.000	SY
0150	326(C)1100	(SP) WOVEN GEOSYNTHETIC REINFORCEMENT FABRIC	55,929.000	SY
0160	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	1,006.000	TON
0170	407(B)7300	TACK COAT	4,261.000	GAL
0180	408 8100	PRIME COAT	19,560.000	GAL
0190	410(A)0220	POLYMER-MODIFIED EMULSIFIED ASPHALT	2,510.000	GAL
0195	410(C)0410	TYPE II MINERAL AGGREGATE	97.000	TON
0200	411(B)1300	SUPERPAVE, TYPE S3(PG 76-28 OK)	2,991.000	TON
0210	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	1,724.000	TON
0220	411(C)1400	SUPERPAVE, TYPE S4(PG 76-28 OK)	2,375.000	TON
0230	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	1,419.000	TON
0240	412 3100	COLD MILLING PAVEMENT	32,505.000	SY
0250	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	14,949.000	SY
0260	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	30,048.000	SY
0270	414(G)5800	P.C. CONCRETE FOR PAVEMENT	13,124.000	CY
0280	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	936.000	CY
0290	509(A)0200	CLASS AA CONCRETE	27.000	CY
0300	509(D)0500	CLASS C CONCRETE	312.000	CY
0310	511(A)2200	REINFORCING STEEL	3,996.000	LB
0320	609(A)4230	CONC.CURB(6" BARRIER-INTEGRAL)	304.000	LF
0330	610(B)5320	8" CONCRETE DRIVEWAY	619.000	SY
0340	611(G)0354	INLET (SMD-TYPE 2)	5.000	EA
0350	613(A)5208	18" R.C.PIPE CLASS III	218.000	LF
0360	613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0370	613(S)7700	STANDARD BEDDING MATERIAL, CLASS B	31.000	CY
0380	613(V)8000	TRENCH EXCAVATION	100.000	CY
0390	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0400	619(B)6356	REMOVAL OF CURB AND GUTTER	122.000	LF
0410	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	30,482.000	SY
0420	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	6,891.000	SY
0430	619(B)6376	REMOVAL OF CONC.PAV.W/ASPH.OVERLAY	9,580.000	SY
0440	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	1,642.000	SY
0450	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	1,979.000	SY

Proposal:260184 **Let Date:**August 13, 2026 **Call Order:**515
J/P Num:31962(04) **Proj. Num:**NHPP-013N(254)PM
Counties:CRAIG
Description:PAVEMENT REHABILITATION
US-69: FROM 1.07 MILES SOUTH OF THE I-44 INTERCHANGE,
EXTEND NORTH NEAR BIG CABIN.
PROJECT LENGTH = 1.513 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0460	619(B)6464	REMOVAL OF 6" CONCRETE DIVIDING STRIP	147.000	SY
0470	619(C)6600	SAWING PAVEMENT	3,489.000	LF
0480	625(D)4500	REMOVE AND RECONSTRUCT GUARDRAIL	766.000	LF
0002	TRAFFIC CONTROL			
0490	857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	131,366.000	LF
0500	857(B)9300	CONSTRUCTION TRAFFIC STR.(PAINT)(ARROWS)	116.000	EA
0510	857(E)9600	(PL)CONSTRUCTION ZONE PAVEMENT MARKERS	2,832.000	EA
0520	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	110,013.000	LF
0530	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	4,125.000	SD
0540	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	15,073.000	SD
0550	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	8,582.000	SD
0560	880(B)6330	CONSTRUCTION SIGNS 33.0 SF & OVER	1,520.000	SD
0570	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	14,092.000	SD
0580	880(E)6607	WARNING LIGHTS(TYPE B)	36,566.000	SD
0590	880(F)6700	DRUMS	700.000	SD
0600	880(G)6800	TUBE CHANNELIZERS	6,370.000	SD
0610	880(G)6805	CHANNELIZER CONES	33,461.000	SD
0620	880(I)7000	FLAGGER	58.000	SD
0630	880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	400.000	HOUR
0640	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	1,232.000	SD
0003	TRAFFIC SIGNING AND STRIPING			
0650	804(A)2200	STRUCTURAL CONCRETE	11.240	CY
0660	804(B)2300	REINFORCING STEEL	2,076.000	LB
0670	805(A)3236	(PL)REMOVAL OF OVERHEAD SIGN STRUCTURE	1.000	EA
0680	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	104.000	EA
0690	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	2.000	EA
0700	850(A)1200	SHEET ALUMINUM SIGNS	1,243.000	SF
0710	850(B)1310	EXTRUDED ALUMINUM PANEL SIGNS	530.000	SF
0720	851(A)2210	6"@20 GALV.STL.WD.FLANGE BM.POST	208.000	LF
0730	851(B)2320	3 1/2"@9.11 GALV.STL.PIPE POST	309.000	LF
0740	851(C)2415	2" SQUARE TUBE POST	423.000	LF
0750	851(C)2430	2 1/2" SQUARE TUBE POST	777.000	LF
0760	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	55,500.000	LF
0770	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	710.000	LF
0780	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	822.000	LF
0790	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	471.000	LF
0800	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	40.000	EA
0810	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	25,750.000	LF

Proposal:260184 **Let Date:**August 13, 2026 **Call Order:**515
J/P Num:31962(04) **Proj. Num:**NHPP-013N(254)PM
Counties:CRAIG
Description:PAVEMENT REHABILITATION
US-69: FROM 1.07 MILES SOUTH OF THE I-44 INTERCHANGE,
EXTEND NORTH NEAR BIG CABIN.
PROJECT LENGTH = 1.513 MILES

Line #		Item Description	Quantity	Unit
0004	TRAFFIC LIGHTING			
0820	802(B)0320	2" PVC SCH.40 PLASTIC CONDUIT BORED	100.000	LF
0830	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	350.000	LF
0840	803(A)1210	PULL BOX(SIZE I)	2.000	EA
0850	804(A)2200	STRUCTURAL CONCRETE	3.280	CY
0860	804(B)2300	REINFORCING STEEL	568.000	LB
0870	805(A)3228	(PL)REMOVAL OF LIGHT POLE	2.000	EA
0880	805(D)3504	(PL)REMOVE & RESET LIGHT POLE	16.000	EA
0890	806(C)4512	40' MTG & 10' HLMA(G.STL.)	2.000	EA
0900	807 5120	BREAKAWAY BASE (DES. B)	2.000	EA
0910	809(A)7200	ROADWAY LUMINAIRE	2.000	EA
0920	811 9110	1/C NO.2 ELECT.COND.	1,000.000	LF
0930	811 9160	2/C NO.12 ELECT.COND.	110.000	LF
0005	TRAFFIC SIGNAL			
0940	802(B)0320	2" PVC SCH.40 PLASTIC CONDUIT BORED	20.000	LF
0950	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	10.000	LF
0960	802(B)0328	3" PVC SCH.40 PLASTIC CONDUIT BORED	460.000	LF
0970	802(B)0332	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	25.000	LF
0980	803(A)1220	PULL BOX(SIZE II)	2.000	EA
0990	804(A)2200	STRUCTURAL CONCRETE	7.700	CY
1000	804(B)2300	REINFORCING STEEL	1,128.000	LB
1010	805(A)3256	(PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1.000	LSUM
1020	806(A)4276	32'MH POLE,TWIN TS & 10'LMA(G.STL.)	1.000	EA
1030	809(A)7200	ROADWAY LUMINAIRE	1.000	EA
1040	811 9120	1/C NO.6 ELECT.COND.	270.000	LF
1050	811 9130	1/C NO.10 ELECT.COND.	280.000	LF
1060	825(A)8200	SIGNAL SYSTEM CONTROLLER UPGRADE	1.000	EA
1070	828 0110	(PL)DETECTION SYSTEM (RADAR)	1.000	LSUM
1080	831 3120	1WAY3SEC.ADJ.SIG.HD.S-6	4.000	EA
1090	831 3124	1WAY3SEC.ADJ.SIG.HD.S-9	3.000	EA
1100	831 3148	1WAY4SEC.ADJ.SIG.HD.S-16	1.000	EA
1110	833 5100	BACKPLATE	8.000	EA
1120	834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	210.000	LF
1130	834(A)6210	7/C TRAFFIC SIGNAL ELECTRICAL CABLE	100.000	LF
1140	834(A)6225	15/C TRAFFIC SIGNAL ELECTRICAL CABLE	750.000	LF
1150	840(B)0300	E.P.S. OPTICAL DETECTOR	2.000	EA
1160	840(C)0400	E.P.S. OPTICAL DETECTOR CABLE	375.000	LF
1170	840(D)0500	E.P.S. 2 CHANNEL PHASE SELECTOR	1.000	EA
1180	850(C)1400	MAST ARM MOUNTED SIGNS(ALUM.)	97.500	SF
1190	880(N)7500	(SP) TEMP. TRAFF. SIGNAL SPAN WIRE EQUIP	1.000	LSUM
0006	STAKING			
1200	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM

Proposal: 260184 **Let Date:** August 13, 2026 **Call Order:** 515
J/P Num: 31962(04) **Proj. Num:** NHPP-013N(254)PM
Counties: CRAIG
Description: PAVEMENT REHABILITATION
US-69: FROM 1.07 MILES SOUTH OF THE I-44 INTERCHANGE,
EXTEND NORTH NEAR BIG CABIN.
PROJECT LENGTH = 1.513 MILES

Line #		Item Description	Quantity	Unit
0007	CONSTRUCTION			
1210	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
1220	641 2110	MOBILIZATION	1.000	LSUM