Proposal:260191 **Let Date:**August 13, 2026 **Call Order:**550
J/P Num:36121(04) **Proj. Num:**STP-270C(066)CI
Counties:TEXAS
Description:BRIDGE REHABILITATION
COUNTY ROAD (MILE 37 RD): OVER UNION PACIFIC RAILROAD,
0.04 MILES NORTHWEST OF THE US-64 JUNCTION NEAR GUYMON.
PROJECT LENGTH = 0.066 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	320.000	CY
0030	202(F)2700	EMBANKMENTS	45.000	CY
0040	221(B)2300	TEMPORARY SILT FENCE	396.000	LF
0050	230(A)7200	SOLID SLAB SODDING	423.000	SY
0060	305 2100	CALICHE BASE	334.000	CY
0070	325 0100	SEPARATOR FABRIC	1,278.000	SY
0080	408 8100	PRIME COAT	237.000	GAL
0090	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	850.000	SY
0100	414(G)5800	P.C. CONCRETE FOR PAVEMENT	189.000	CY
0110	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0120	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	801.000	SY
0130	619(B)6396	REMOVAL OF GUARDRAIL	252.000	LF
0140	619(C)6600	SAWING PAVEMENT	160.000	LF
0150	623 1100	(PL)GUARDRAIL CURBING	4.000	EA
0160	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	100.000	LF
0170	623(G)1820	GUARDRAIL END TREATMENT (31")	2.000	EA
0180	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	4.000	EA
0002	BRIDGE - NBI NO. 14394			
0190	202(A)2210	UNCLASSIFIED EXCAVATION	60.000	CY
0200	501(G)1800	CLSM BACKFILL	50.000	CY
0210	504(A)5200	APPROACH SLAB	137.800	SY
0220	504(B)5300	SAW-CUT GROOVING	452.500	SY
0230	504(E)5520	42" F-SHAPED PARAPET	343.000	LF
0240	506(A)7200	STRUCTURAL STEEL	72,260.000	LB
0250	507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	15.000	EA
0260	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	15.000	EA
0270	509(A)0210	CLASS AA CONCRETE	104.700	CY
0280	509(B)0320	CLASS A CONCRETE	33.400	CY
0290	511(B)2310	EPOXY COATED REINFORCING STEEL	43,190.000	LB
0300	518(B)0300	SEALED EXPANSION JOINTS	58.000	LF
0310	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	4.000	LF
0320	520(C)1400	EPOXY RESIN, ABOVE WATER	0.400	GAL
0330	521(A)2200	PNEUMATICALLY PLACED MORTAR	27.000	SY
0340	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	81.000	SY
0350	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
0360	624(E)3635	FENCE-STYLE CLF (7' HIGH, CLASS B)	263.000	LF

Proposal:260191 **Let Date:**August 13, 2026 **Call Order:**550
J/P Num:36121(04) **Proj. Num:**STP-270C(066)CI
Counties:TEXAS
Description:BRIDGE REHABILITATION
COUNTY ROAD (MILE 37 RD): OVER UNION PACIFIC RAILROAD,
0.04 MILES NORTHWEST OF THE US-64 JUNCTION NEAR GUYMON.
PROJECT LENGTH = 0.066 MILES

Line #		Item Description	Quantity	Unit
0003	TRAFFIC			
0370	104 3250	(SP) RAILROAD FLAGGING(NON-BIDDABLE)	180.000	DAY
0380	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	2.000	EA
0390	850(A)1200	SHEET ALUMINUM SIGNS	22.000	SF
0400	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	706.000	LF
0410	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	12.000	LF
0420	880(J)7100	(SP) CONSTRUCTION TRAFFIC CONTROL	240.000	SD
0430	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	480.000	SD
0004	STAKING			
0440	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0450	641 2110	MOBILIZATION	1.000	LSUM