Proposal:260194 **Let Date:**August 20, 2026 **Call Order:**090
J/P Num:37100(15) **Proj. Num:**EWC-28603A
Counties:CLEVELAND
Description:GRADE, DRAIN, BRIDGE, AND SURFACE
OTA ACCESS: TOBY KEITH EXPRESSWAY TURNPIKE:
AT THE INTERSECTION OF WESTERN AVE, 2.37 MILES
WEST OF I-35 IN THE CITY OF OKLAHOMA CITY.
PROJECT LENGTH = 1.440 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY-OTA			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	147,706.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	557,201.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	22,335.000	LF
0060	221(C)2400	TEMPORARY SEDIMENT FILTER	72.000	EA
0070	221(D)2500	TEMPORARY SEDIMENT BASIN	7.000	EA
0080	221(E)2600	TEMPORARY SILT DIKE	4,977.000	LF
0090	221(F)2700	TEMPORARY ROCK FILTER DAM TYPE 1	144.000	CY
0100	221(F)2730	TEMPORARY ROCK FILTER DAM TYPE 4	10.000	CY
0110	221(G)2800	TEMPORARY FIBER LOG	24,817.000	LF
0120	229 6100	DITCH LINER PROTECTION	2,204.000	LF
0130	230(A)7200	SOLID SLAB SODDING	441,140.000	SY
0140	233(E)0600	(SP) HYDROMULCH	441,140.000	SY
0150	241 3100	MOWING	179.000	AC
0160	242 4101	STABILIZED CONSTRUCTION EXIT	6.000	EA
0170	303(A)1200	AGGREGATE BASE TYPE A	373.000	CY
0180	307(K)4200	STABILIZED SUBGRADE	98,085.000	SY
0190	325 0100	SEPARATOR FABRIC	1,876.000	SY
0200	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	1,000.000	TON
0210	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	19,992.000	TON
0220	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	909.000	TON
0230	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	19,009.000	SY
0240	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	62,895.000	SY
0250	414(G)5800	P.C. CONCRETE FOR PAVEMENT	22,292.000	CY
0260	414(G)5810	(PL) P.C. CONCRETE FOR PAVEMENT, SPECIAL	277.000	CY
0270	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	1,392.000	CY
0280	504(E)5520	42" F-SHAPED PARAPET	563.000	LF
0290	509(A)0200	CLASS AA CONCRETE	3,521.000	CY
0300	509(D)0500	CLASS C CONCRETE	420.000	CY
0310	511(A)2200	REINFORCING STEEL	521,869.000	LB
0320	511(B)2300	EPOXY COATED REINFORCING STEEL	27,400.000	LB
0330	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	310.000	SY
0340	601(B)1200	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	355.000	TON
0350	609(A)4270	CONC.CURB(8" BARRIER-INTEGRAL)	871.000	LF
0360	613(A)5208	18" R.C.PIPE CLASS III	1,974.000	LF
0370	613(A)5216	24" R.C.PIPE CLASS III	1,600.000	LF
0380	613(A)5220	30" R.C.PIPE CLASS III	276.000	LF
0390	613(A)5224	36" R.C.PIPE CLASS III	1,046.000	LF
0400	613(A)5350	22" X 13" R.C.PIPE ARCH CLASS A-III	1,206.000	LF
0410	613(A)5358	28" X 18" R.C.PIPE ARCH CLASS A-III	1,790.000	LF
0420	613(A)5366	36" X 22" R.C.PIPE ARCH CLASS A-III	594.000	LF
0430	613(A)5370	43" X 26" R.C.PIPE ARCH CLASS A-III	276.000	LF
0440	613(A)5374	51" X 31" R.C.PIPE ARCH CLASS A-III	742.000	LF
0450	613(A)5440	22" X 13" R.C.PIPE ARCH CLASS A-IV	28.000	LF

Proposal:260194 **Let Date:**August 20, 2026 **Call Order:**090
J/P Num:37100(15) **Proj. Num:**EWC-28603A
Counties:CLEVELAND
Description:GRADE, DRAIN, BRIDGE, AND SURFACE
OTA ACCESS: TOBY KEITH EXPRESSWAY TURNPIKE:
AT THE INTERSECTION OF WESTERN AVE, 2.37 MILES
WEST OF I-35 IN THE CITY OF OKLAHOMA CITY.
PROJECT LENGTH = 1.440 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY-OTA			
0460	613(H)6200	6" PERFORATED PIPE UNDERDRAIN ROUND	740.000	LF
0470	613(I)6305	6" NON-PERF.PIPE UNDERDRAIN RND.	250.000	LF
0480	613(M)6904	TYPE B3 CULVERT END TREATMENT	2.000	EA
0490	613(M)6908	TYPE C3 CULVERT END TREATMENT	1.000	EA
0500	613(M)6960	TYPE A4 CULVERT END TREATMENT	21.000	EA
0510	613(M)6964	TYPE B4 CULVERT END TREATMENT	4.000	EA
0520	613(M)6980	TYPE AA4 CULVERT END TREATMENT	1.000	EA
0530	613(M)6984	TYPE BB4 CULVERT END TREATMENT	2.000	EA
0540	613(M)7004	TYPE A6 CULVERT END TREATMENT	24.000	EA
0550	613(M)7008	TYPE B6 CULVERT END TREATMENT	6.000	EA
0560	613(M)7028	TYPE BB6 CULVERT END TREATMENT	4.000	EA
0570	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0580	619(B)6300	REMOVAL OF HEADWALL	1.000	EA
0590	619(B)6352	REMOVAL OF FENCE	8,447.000	LF
0600	619(B)6356	REMOVAL OF CURB AND GUTTER	2,434.000	LF
0610	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	4,552.000	SY
0620	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	29,538.000	SY
0630	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	449.000	SY
0640	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	227.000	SY
0650	619(B)6404	REMOVAL OF SIDEWALK	1,289.000	SY
0660	619(C)6600	SAWING PAVEMENT	889.000	LF
0670	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	2,812.500	LF
0680	623(G)1820	GUARDRAIL END TREATMENT (31")	9.000	EA
0690	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	9.000	EA
0700	627(A)6200	CONCRETE LONGITUDINAL BARRIER, DESIGN 1	1,610.000	LF
0710	627(B)6300	CONCRETE LONGITUDINAL BARRIER END SEC.	6.000	EA
0720	853 5100	DELINEATORS(TYPE 1, CODE 1)	50.000	EA
0730	853 5170	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	81.000	EA
0740	871(A)2200	IMPACT ATTENUATOR	6.000	EA

Proposal:260194 **Let Date:**August 20, 2026 **Call Order:**090
J/P Num:37100(15) **Proj. Num:**EWC-28603A
Counties:CLEVELAND
Description:GRADE, DRAIN, BRIDGE, AND SURFACE
OTA ACCESS: TOBY KEITH EXPRESSWAY TURNPIKE:
AT THE INTERSECTION OF WESTERN AVE, 2.37 MILES
WEST OF I-35 IN THE CITY OF OKLAHOMA CITY.
PROJECT LENGTH = 1.440 MILES

	Line #		Item Description	Quantity	Unit
0002	ROADWAY-CITY/COUNTY				
	0750	202(A)2200	UNCLASSIFIED EXCAVATION	135,885.000	CY
	0760	202(D)2500	UNCLASSIFIED BORROW	6,633.000	CY
	0770	229 6100	DITCH LINER PROTECTION	5,386.000	LF
	0780	307(K)4200	STABILIZED SUBGRADE	96,175.000	SY
	0790	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	2,366.000	TON
	0800	407(B)7300	TACK COAT	93.000	GAL
	0810	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	14,819.000	TON
	0820	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	48.000	TON
	0830	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	81,215.000	SY
	0840	414(G)5800	P.C. CONCRETE FOR PAVEMENT	20,304.000	CY
	0850	509(B)0300	CLASS A CONCRETE	132.000	CY
	0860	509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	103.000	CY
	0870	509(D)0500	CLASS C CONCRETE	1,213.000	CY
	0880	511(B)2300	EPOXY COATED REINFORCING STEEL	14,490.000	LB
	0890	518(C)0400	RAPID CURE JOINT SEALANT	148.000	LF
	0900	609(A)4270	CONC.CURB(8" BARRIER-INTEGRAL)	24,287.000	LF
	0910	609(B)4375	2'-8" COMB.CRB.& GUT.(8" BARRIER)	516.000	LF
	0920	610(A)5200	4" CONCRETE SIDEWALK	655.000	SY
	0930	610(B)5310	6" CONCRETE DRIVEWAY	1,983.000	SY
	0940	610(C)5410	6" CONCRETE DIVIDING STRIP	1,456.000	SY
	0950	610(I)6000	TACTILE WARNING DEVICE-NEW	162.000	SF
	0960	611(A)7210	MANHOLE (4' DIA.)	6.000	EA
	0970	611(A)7215	MANHOLE (5' DIA.)	6.000	EA
	0980	611(A)7220	MANHOLE (6' DIA.)	1.000	EA
	0990	611(G)0350	INLET (SMD-TYPE 1)	2.000	EA
	1000	611(G)0354	INLET (SMD-TYPE 2)	7.000	EA
	1010	611(G)0358	INLET (SMD-TYPE 2A)	3.000	EA
	1020	611(G)0362	INLET (SMD-TYPE 2B)	1.000	EA
	1030	611(G)7754	INLET CI DES. 2 (STD)	6.000	EA
	1040	611(G)7758	INLET CI DES. 2 (B)	22.000	EA
	1050	611(G)7766	INLET CI DES. 2 (D)	14.000	EA
	1060	611(G)7770	INLET CI DES. 2 (2B)	6.000	EA
	1070	611(G)7790	INLET CI DES. 3 (B)	5.000	EA
	1080	611(G)7798	INLET CI DES. 3 (2B)	1.000	EA
	1090	611(G)7930	INLET GPI TYPE 1 (DES. 1)	3.000	EA
	1100	611(G)7958	INLET GPI TYPE 2 (DES. 8)	2.000	EA
	1110	611(L)1600	JUNCTION BOXES	970.000	CF
	1120	624(A)3200	FENCE-STYLE WWF	12,179.000	LF
	1130	624(B)3340	GATES-STYLE WWF (4.5'HIGH X 12'LONG)	5.000	EA
	1140	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	23.000	LF
	1150	629(A)7200	MAILBOX INSTALLATION-SINGLE	2.000	EA
	1160	629(C)7400	REMOVAL OF MAILBOX INSTALLATION	3.000	EA
	1170	629(E)7600	MAILBOX	2.000	EA

Proposal:260194 **Let Date:**August 20, 2026 **Call Order:**090
J/P Num:37100(15) **Proj. Num:**EWC-28603A
Counties:CLEVELAND
Description:GRADE, DRAIN, BRIDGE, AND SURFACE
OTA ACCESS: TOBY KEITH EXPRESSWAY TURNPIKE:
AT THE INTERSECTION OF WESTERN AVE, 2.37 MILES
WEST OF I-35 IN THE CITY OF OKLAHOMA CITY.
PROJECT LENGTH = 1.440 MILES

	Line #		Item Description	Quantity	Unit
0003	BRIDGE TPO 111.64 WB - NBI 33538				
	1180	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	129.000	CY
	1190	501(G)1800	CLSM BACKFILL	223.400	CY
	1200	503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	1,495.000	LF
	1210	504(A)5200	APPROACH SLAB	227.800	SY
	1220	504(B)5300	SAW-CUT GROOVING	1,480.200	SY
	1230	504(E)5520	42" F-SHAPED PARAPET	701.000	LF
	1240	506(A)7200	STRUCTURAL STEEL	1,120.000	LB
	1250	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	10.000	EA
	1260	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	20.000	EA
	1270	507(C)8400	ELASTOMERIC BEARING PADS	20.000	EA
	1280	509(A)0210	CLASS AA CONCRETE	371.500	CY
	1290	509(B)0320	CLASS A CONCRETE	197.100	CY
	1300	509(D)0510	CLASS C CONCRETE	6.900	CY
	1310	510(C)1450	SLOPE WALL (5")	1,080.000	SY
	1320	510(D)1500	GRAFFITI TREATMENT	16,495.000	SF
	1330	511(A)2210	REINFORCING STEEL	1,560.000	LB
	1340	511(B)2310	EPOXY COATED REINFORCING STEEL	143,500.000	LB
	1350	514(A)5210	PILES, FURNISHED (HP 10X42)	1,780.000	LF
	1360	514(B)5310	PILES, DRIVEN (HP 10X42)	1,780.000	LF
	1370	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
	1380	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	3,096.000	SY
	1390	516(A)8250	DRILLED SHAFTS 72" DIAMETER	304.000	LF
	1400	516(C)8400	CROSSHOLE SONIC LOGGING	1.000	EA
	1410	523(A)3200	SEALER CRACK PREPARATION	156.000	LF
	1420	523(B)3300	SEALER RESIN	2.000	GAL
	1430	535 7200	(SP) AESTHETIC TREATMENT	1.000	LSUM
	1440	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	209.000	LF
	1450	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	87.000	LF
	1460	613(Q)7500	OUTLET LATERAL HEADWALL	2.000	EA

Proposal:260194 **Let Date:**August 20, 2026 **Call Order:**090
J/P Num:37100(15) **Proj. Num:**EWC-28603A
Counties:CLEVELAND
Description:GRADE, DRAIN, BRIDGE, AND SURFACE
OTA ACCESS: TOBY KEITH EXPRESSWAY TURNPIKE:
AT THE INTERSECTION OF WESTERN AVE, 2.37 MILES
WEST OF I-35 IN THE CITY OF OKLAHOMA CITY.
PROJECT LENGTH = 1.440 MILES

	Line #		Item Description	Quantity	Unit
0004	BRIDGE TPO 111.64 EB - NBI 33537				
	1470	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	129.000	CY
	1480	501(G)1800	CLSM BACKFILL	223.400	CY
	1490	503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	1,495.000	LF
	1500	504(A)5200	APPROACH SLAB	227.800	SY
	1510	504(B)5300	SAW-CUT GROOVING	1,480.200	SY
	1520	504(E)5520	42" F-SHAPED PARAPET	701.000	LF
	1530	506(A)7200	STRUCTURAL STEEL	1,120.000	LB
	1540	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	10.000	EA
	1550	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	20.000	EA
	1560	507(C)8400	ELASTOMERIC BEARING PADS	20.000	EA
	1570	509(A)0210	CLASS AA CONCRETE	371.500	CY
	1580	509(B)0320	CLASS A CONCRETE	197.100	CY
	1590	509(D)0510	CLASS C CONCRETE	5.600	CY
	1600	510(C)1450	SLOPE WALL (5")	1,080.000	SY
	1610	510(D)1500	GRAFFITI TREATMENT	16,495.000	SF
	1620	511(A)2210	REINFORCING STEEL	1,560.000	LB
	1630	511(B)2310	EPOXY COATED REINFORCING STEEL	143,500.000	LB
	1640	514(A)5210	PILES, FURNISHED (HP 10X42)	1,720.000	LF
	1650	514(B)5310	PILES, DRIVEN (HP 10X42)	1,720.000	LF
	1660	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
	1670	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	3,096.000	SY
	1680	516(A)8250	DRILLED SHAFTS 72" DIAMETER	304.000	LF
	1690	516(C)8400	CROSSHOLE SONIC LOGGING	1.000	EA
	1700	523(A)3200	SEALER CRACK PREPARATION	156.000	LF
	1710	523(B)3300	SEALER RESIN	2.000	GAL
	1720	535 7200	(SP) AESTHETIC TREATMENT	1.000	LSUM
	1730	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	209.000	LF
	1740	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	94.000	LF
	1750	613(Q)7500	OUTLET LATERAL HEADWALL	2.000	EA

Proposal:260194 **Let Date:**August 20, 2026 **Call Order:**090
J/P Num:37100(15) **Proj. Num:**EWC-28603A
Counties:CLEVELAND
Description:GRADE, DRAIN, BRIDGE, AND SURFACE
OTA ACCESS: TOBY KEITH EXPRESSWAY TURNPIKE:
AT THE INTERSECTION OF WESTERN AVE, 2.37 MILES
WEST OF I-35 IN THE CITY OF OKLAHOMA CITY.
PROJECT LENGTH = 1.440 MILES

Line #		Item Description	Quantity	Unit
0005	TRAFFIC SIGNAL CITY/COUNTY			
1760	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	475.000	LF
1770	802(B)0336	4" PVC SCH.40 PLASTIC CONDUIT BORED	575.000	LF
1780	802(B)0340	4" PVC SCH.40 PLASTIC CONDUIT TRENCHED	200.000	LF
1790	802(C)0440	3" HIGH DENSITY PE PIPE - TRENCHED	200.000	LF
1800	803(A)1200	PULL BOX	2.000	EA
1810	803(A)1220	PULL BOX(SIZE II)	6.000	EA
1820	804(A)2200	STRUCTURAL CONCRETE	32.400	CY
1830	804(B)2300	REINFORCING STEEL	4,543.200	LB
1840	805(A)3256	(PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1.000	LSUM
1850	806(A)4244	32'MH POLE,30'TS & 10'LMA(G.STL.)	1.000	EA
1860	806(A)4252	32'MH POLE 40'TS & 10'LMA(G.STL.)	2.000	EA
1870	806(A)4320	POLE & 35' TS MST.ARM(G.STL.)	2.000	EA
1880	806(A)4324	POLE & 40' TS MST.ARM(G.STL.)	1.000	EA
1885	806(B)4408	10' MTG.HT.TS PED.POLE(G.STL.)	12.000	EA
1890	809(A)7200	ROADWAY LUMINAIRE	3.000	EA
1895	810(A)8200	SERVICE POLE	2.000	EA
1900	811 9120	1/C NO.6 ELECT.COND.	400.000	LF
1910	811 9130	1/C NO.10 ELECT.COND.	1,180.000	LF
1920	825 8100	TRAFFIC SIGNAL CONTROLLER ASSEMBLY	2.000	EA
1930	828 0100	(PL)DETECTION SYSTEM (VIDEO)	1.000	LSUM
1940	830 2100	PEDESTRIAN PUSH BUTTON	12.000	EA
1950	831 3116	1WAY2SEC.ADJ.PED.SIG.HD.S-20	12.000	EA
1960	831 3120	1WAY3SEC.ADJ.SIG.HD.S-6	14.000	EA
1970	831 3124	1WAY3SEC.ADJ.SIG.HD.S-9	2.000	EA
1980	831 3144	1WAY4SEC.ADJ.SIG.HD.S-13	2.000	EA
1990	833 5100	BACKPLATE	18.000	EA
2000	834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	5,100.000	LF
2010	834(A)6210	7/C TRAFFIC SIGNAL ELECTRICAL CABLE	200.000	LF
2020	834(A)6235	21/C TRAFFIC SIGNAL ELECTRICAL CABLE	1,025.000	LF
2030	834(B)6300	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	150.000	LF
2040	840(B)0300	E.P.S. OPTICAL DETECTOR	6.000	EA
2050	840(C)0400	E.P.S. OPTICAL DETECTOR CABLE	1,375.000	LF
2060	840(D)0510	E.P.S. 4 CHANNEL PHASE SELECTOR	2.000	EA
2070	850(C)1400	MAST ARM MOUNTED SIGNS(ALUM.)	259.000	SF

Proposal:260194 **Let Date:**August 20, 2026 **Call Order:**090
J/P Num:37100(15) **Proj. Num:**EWC-28603A
Counties:CLEVELAND
Description:GRADE, DRAIN, BRIDGE, AND SURFACE
OTA ACCESS: TOBY KEITH EXPRESSWAY TURNPIKE:
AT THE INTERSECTION OF WESTERN AVE, 2.37 MILES
WEST OF I-35 IN THE CITY OF OKLAHOMA CITY.
PROJECT LENGTH = 1.440 MILES

	Line #		Item Description	Quantity	Unit
0006	SIGNING AND STRIPING				
	2080	805(A)3248	(PL)REMOVAL OF EXISTING SIGNS	1.000	LSUM
	2090	850(A)1200	SHEET ALUMINUM SIGNS	505.660	SF
	2100	851(C)2415	2" SQUARE TUBE POST	805.000	LF
	2110	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	45,358.000	LF
	2120	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	250.000	LF
	2130	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	1,910.000	LF
	2140	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	796.000	LF
	2150	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	23.000	EA
	2160	856(B)8315	(SP) TRAFFIC STRIPE(PLURAL-COMP)(WORDS)	6.000	EA
	2170	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	7,000.000	LF
0007	TRAFFIC TOLLING				
	2180	803(A)1220	PULL BOX(SIZE II)	12.000	EA
	2190	811 9115	1/C NO.4 ELECT.COND.	500.000	LF
	2200	853 5100	DELINEATORS(TYPE 1, CODE 1)	46.000	EA
	2210	855(A)7205	(SP) TRAFFIC STRIPE(PLASTIC)(6" WIDE)	5,096.000	LF
	2220	890 1100	(PL)TRAFFIC ITEMS	1.000	LSUM
0008	TRAFFIC CONTROL				
	2230	857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	18,000.000	LF
	2240	857(C)9405	REMOVABLE PAVEMENT MARKING TAPE(6" WIDE)	4,500.000	LF
	2250	857(E)9620	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	3,000.000	EA
	2260	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	12,000.000	LF
	2270	871(B)2300	CONST.ZONE IMPACT ATTEN.	700.000	SD
	2280	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	500.000	LF
	2290	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	14,000.000	SD
	2300	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	12,020.000	SD
	2310	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	12,480.000	SD
	2320	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	6,460.000	SD
	2330	880(E)6607	WARNING LIGHTS(TYPE B)	25,400.000	SD
	2340	880(E)6616	WARNING LIGHTS(TYPE D)	7,940.000	SD
	2350	880(F)6700	DRUMS	7,940.000	SD
	2360	880(G)6805	CHANNELIZER CONES	5,680.000	SD
	2365	880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	2,800.000	HOUR
	2370	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	800.000	SD

Proposal:260194 **Let Date:**August 20, 2026 **Call Order:**090
J/P Num:37100(15) **Proj. Num:**EWC-28603A
Counties:CLEVELAND
Description:GRADE, DRAIN, BRIDGE, AND SURFACE
OTA ACCESS: TOBY KEITH EXPRESSWAY TURNPIKE:
AT THE INTERSECTION OF WESTERN AVE, 2.37 MILES
WEST OF I-35 IN THE CITY OF OKLAHOMA CITY.
PROJECT LENGTH = 1.440 MILES

	Line #		Item Description	Quantity	Unit
0009	TRAFFIC LIGHTING				
	2380	802(B)0320	2" PVC SCH.40 PLASTIC CONDUIT BORED	650.000	LF
	2390	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	2,000.000	LF
	2400	803(A)1210	PULL BOX(SIZE I)	18.000	EA
	2410	804(A)2200	STRUCTURAL CONCRETE	22.960	CY
	2420	804(B)2300	REINFORCING STEEL	3,976.000	LB
	2430	806(D)4616	40' MTG.HT.HL.PTP.(G.STL.)	14.000	EA
	2440	807 5120	BREAKAWAY BASE (DES. B)	14.000	EA
	2450	809(A)7200	ROADWAY LUMINAIRE	14.000	EA
	2460	810(A)8200	SERVICE POLE	2.000	EA
	2470	811 9115	1/C NO.4 ELECT.COND.	7,950.000	LF
	2480	811 9135	1/C NO.12 ELECT.COND.	1,500.000	LF
0010	TOLLING-MAINLINE				
	2490	506(A)7200	STRUCTURAL STEEL	2,400.000	LB
	2500	509(A)0200	CLASS AA CONCRETE	27.000	CY
	2510	511(A)2200	REINFORCING STEEL	3,060.000	LB
	2520	516(A)8230	DRILLED SHAFTS 48" DIAMETER	144.000	LF
	2530	610(A)5200	4" CONCRETE SIDEWALK	201.000	SY
	2540	648 6110	ELECTRIC SERVICE AND SERVICE CONNECTION	1.000	LSUM
	2550	650(A)8100	TOLL EQUIPMENT BUILDING FOUNDATION	2.000	EA
	2560	650(A)8110	GENERATOR PAD AND ENCLOSURE	1.000	EA
	2570	650(B)8200	TOLL EQUIPMENT BUILDING INSTALLATION	2.000	EA
	2580	650(C)8300	ELECTRICAL GENERATOR	1.000	EA
	2590	650(C)8310	ELECTRICAL EQUIPMENT	1.000	LSUM
	2600	650(C)8320	PROPANE TANK WITH PAD	1.000	EA
	2610	802(B)0308	1" PVC SCH.40 PLASTIC CONDUIT TRENCHED	1,750.000	LF
	2620	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	40.000	LF
	2630	802(B)0332	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	1,800.000	LF
	2640	803(A)1220	PULL BOX(SIZE II)	16.000	EA
	2650	811 9408	ELECTRIC WIRE 3-#3, 1-#6G	220.000	LF
	2660	811 9410	ELECTRIC WIRE 3-#3, 1-#4G	300.000	LF
	2670	852(B)3300	GALV.STEEL OVERHEAD SIGN STRUCTURE	130.000	LF

Proposal:260194 **Let Date:**August 20, 2026 **Call Order:**090
J/P Num:37100(15) **Proj. Num:**EWC-28603A
Counties:CLEVELAND
Description:GRADE, DRAIN, BRIDGE, AND SURFACE
OTA ACCESS: TOBY KEITH EXPRESSWAY TURNPIKE:
AT THE INTERSECTION OF WESTERN AVE, 2.37 MILES
WEST OF I-35 IN THE CITY OF OKLAHOMA CITY.
PROJECT LENGTH = 1.440 MILES

Line #		Item Description	Quantity	Unit
0011	TOLLING-RAMP "A"			
2680	506(A)7200	STRUCTURAL STEEL	650.000	LB
2690	516(A)8230	DRILLED SHAFTS 48" DIAMETER	36.000	LF
2700	610(A)5200	4" CONCRETE SIDEWALK	61.000	SY
2710	648 6110	ELECTRIC SERVICE AND SERVICE CONNECTION	1.000	LSUM
2720	650(C)8310	ELECTRICAL EQUIPMENT	1.000	LSUM
2730	802(B)0308	1" PVC SCH.40 PLASTIC CONDUIT TRENCHED	325.000	LF
2740	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	40.000	LF
2750	802(B)0332	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	500.000	LF
2760	803(A)1220	PULL BOX(SIZE II)	3.000	EA
2770	804(A)2200	STRUCTURAL CONCRETE	0.600	CY
2780	811 9408	ELECTRIC WIRE 3-#3, 1-#6G	500.000	LF
2790	824(C)7400	(SP)CABINET	1.000	EA
2800	852(B)3340	GALVANIZED STEEL OVERHEAD TOLL GANTRY (CANTILEVER	1.000	EA
0012	TOLLING-RAMP "B"			
2810	506(A)7200	STRUCTURAL STEEL	650.000	LB
2820	516(A)8230	DRILLED SHAFTS 48" DIAMETER	36.000	LF
2830	610(A)5200	4" CONCRETE SIDEWALK	61.000	SY
2840	648 6110	ELECTRIC SERVICE AND SERVICE CONNECTION	1.000	LSUM
2850	650(C)8310	ELECTRICAL EQUIPMENT	1.000	LSUM
2860	802(B)0308	1" PVC SCH.40 PLASTIC CONDUIT TRENCHED	325.000	LF
2870	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	40.000	LF
2880	802(B)0332	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	500.000	LF
2890	803(A)1220	PULL BOX(SIZE II)	3.000	EA
2900	804(A)2200	STRUCTURAL CONCRETE	0.600	CY
2910	811 9408	ELECTRIC WIRE 3-#3, 1-#6G	500.000	LF
2920	824(C)7400	(SP)CABINET	1.000	EA
2930	852(B)3340	GALVANIZED STEEL OVERHEAD TOLL GANTRY (CANTILEVER	1.000	EA
0013	STAKING			
2940	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0014	CONSTRUCTION			
2950	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
2960	640(A)1210	FIELD OFFICE	1.000	EA
2970	641 2110	MOBILIZATION	1.000	LSUM