Proposal:260198 **Let Date:**August 20, 2026 **Call Order:**620
J/P Num:31790(04) **Proj. Num:**STP-243D(043)CI
Counties:LOVE
Description:BRIDGE AND APPROACHES
COUNTY ROAD (NS-3266 / FREEMAN ROAD):
OVER TRIBUTARY TO RED RIVER, 2.82 MILES WEST OF I-35 NEAR MARIETTA.
PROJECT LENGTH = 0.304 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	6,118.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	23.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	210 0100	OBLITERATING ABANDONED ROAD	888.000	LF
0060	221(B)2300	TEMPORARY SILT FENCE	680.000	LF
0070	221(E)2600	TEMPORARY SILT DIKE	273.000	LF
0080	221(F)2710	TEMPORARY ROCK FILTER DAM TYPE 2	9.000	CY
0090	228 5100	EROSION CONTROL MAT	393.000	SY
0100	230(A)7200	SOLID SLAB SODDING	6,572.000	SY
0110	233(A)0200	VEGETATIVE MULCHING	1.330	AC
0120	303(A)1200	AGGREGATE BASE TYPE A	640.000	CY
0130	325 0100	SEPARATOR FABRIC	5,232.000	SY
0140	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	1,490.000	TON
0150	407(B)7300	TACK COAT	254.000	GAL
0160	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	576.000	TON
0170	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	376.000	TON
0180	509(B)0300	CLASS A CONCRETE	11.000	CY
0190	511(A)2200	REINFORCING STEEL	450.000	LB
0200	613(B)5516	24" CORR. GALV. STEEL PIPE	48.000	LF
0210	613(P)7404	24" GALV. STEEL CULVERT END SEC. RND.	2.000	EA
0220	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0230	619(B)6352	REMOVAL OF FENCE	2,618.000	LF
0240	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	2,218.000	SY
0250	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	150.000	SY
0260	619(B)6508	REMOVE AND RESET CATTLE GUARD	1.000	EA
0270	624(A)3200	FENCE-STYLE WWF	1,895.000	LF
0280	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	1,219.000	LF
0002	BRIDGE 'A' - NBI NO. 32745			
0290	202(A)2210	UNCLASSIFIED EXCAVATION	1,450.000	CY
0300	501(A)1210	STRUCTURAL EXCAVATION UNCLASSIFIED	59.000	CY
0310	502 3100	TEMPORARY EARTH RETAINAGE	1.000	LSUM
0320	509(A)0210	CLASS AA CONCRETE	621.300	CY
0330	511(A)2210	REINFORCING STEEL	93,580.000	LB
0340	601(B)1210	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	2,005.000	TON

Proposal:260198 **Let Date:**August 20, 2026 **Call Order:**620
J/P Num:31790(04) **Proj. Num:**STP-243D(043)CI
Counties:LOVE
Description:BRIDGE AND APPROACHES
COUNTY ROAD (NS-3266 / FREEMAN ROAD):
OVER TRIBUTARY TO RED RIVER, 2.82 MILES WEST OF I-35 NEAR MARIETTA.
PROJECT LENGTH = 0.304 MILES

Line #		Item Description	Quantity	Unit
0003	TRAFFIC			
0350	823 6100	(SP)PORTABLE TRAFFIC SIGNAL SYSTEM	161.000	SD
0360	850(A)1200	SHEET ALUMINUM SIGNS	5.000	SF
0370	851(C)2415	2" SQUARE TUBE POST	14.000	LF
0380	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,450.000	SD
0390	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	679.000	SD
0400	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,277.000	SD
0410	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	552.000	SD
0420	880(E)6600	WARNING LIGHTS(TYPE A)	9,396.000	SD
0430	880(F)6700	DRUMS	7,843.000	SD
0004	STAKING			
0440	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0450	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0460	641 2110	MOBILIZATION	1.000	LSUM