Proposal: 260202 **Let Date:** August 20, 2026 **Call Order:** 650
J/P Num: 31082(04) **Proj. Num:** NHPPI-4440-(011)PM
Counties: TULSA
Description: BRIDGE REHABILITATION
CITY STREET (DENVER AVE.): OVER I-444,
0.60 MILES EAST OF THE I-244 INTERCHANGE
IN THE CITY OF TULSA.
PROJECT LENGTH = 0.073 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	198.600	CY
0030	202(D)2500	UNCLASSIFIED BORROW	33.000	CY
0040	221(B)2300	TEMPORARY SILT FENCE	830.000	LF
0050	221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	2.000	EA
0060	230(A)7200	SOLID SLAB SODDING	550.000	SY
0070	303(A)1200	AGGREGATE BASE TYPE A	176.200	CY
0080	307(K)4200	STABILIZED SUBGRADE	516.000	SY
0090	325 0100	SEPARATOR FABRIC	554.100	SY
0100	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	28.000	TON
0110	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	8.000	TON
0120	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	503.300	SY
0130	414(E)5600	FULL DEPTH P.C.C. PATCH (PLACEMENT)	155.000	SY
0140	414(G)5800	P.C. CONCRETE FOR PAVEMENT	160.100	CY
0150	504(E)5520	42" F-SHAPED PARAPET	17.500	LF
0160	509(A)0200	CLASS AA CONCRETE	7.000	CY
0170	609(A)4270	CONC.CURB(8" BARRIER-INTEGRAL)	196.000	LF
0180	610(A)5200	4" CONCRETE SIDEWALK	150.400	SY
0190	610(I)6000	TACTILE WARNING DEVICE-NEW	32.000	SF
0200	613(J)6400	EDGE DRAIN CONDUIT-PERFORATED	114.200	LF
0210	613(K)6500	EDGE DRAIN OUTLET LATERAL-NONPERFORATED	256.800	LF
0220	613(Q)7500	OUTLET LATERAL HEADWALL	2.000	EA
0230	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0240	619(B)6352	REMOVAL OF FENCE	80.000	LF
0250	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	1,300.000	SY
0260	619(B)6400	REMOVAL OF CURB	400.800	LF
0270	619(B)6404	REMOVAL OF SIDEWALK	222.800	SY
0280	619(C)6600	SAWING PAVEMENT	419.200	LF
0290	623(G)1820	GUARDRAIL END TREATMENT (31")	1.000	EA
0300	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	1.000	EA
0310	624(E)3630	FENCE-STYLE CLF (6' HIGH, VINYL COATED)	80.000	LF
0320	853 5170	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	3.000	EA

Proposal:260202 **Let Date:**August 20, 2026 **Call Order:**650
J/P Num:31082(04) **Proj. Num:**NHPPI-4440-(011)PM
Counties:TULSA
Description:BRIDGE REHABILITATION
CITY STREET (DENVER AVE.): OVER I-444,
0.60 MILES EAST OF THE I-244 INTERCHANGE
IN THE CITY OF TULSA.
PROJECT LENGTH = 0.073 MILES

	Line #		Item Description	Quantity	Unit
0002	BRIDGE - NBI 19248				
	0330	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	277.000	CY
	0340	501(G)1800	CLSM BACKFILL	277.000	CY
	0350	502(B)3320	(PL)FALSEWORK JACKING	1.000	LSUM
	0360	504(A)5200	APPROACH SLAB	878.000	SY
	0370	504(B)5300	SAW-CUT GROOVING	2,637.700	SY
	0380	504(E)5520	42" F-SHAPED PARAPET	624.700	LF
	0390	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	20.000	EA
	0400	509 0100	SPECIAL CONCRETE FINISH	484.100	SY
	0410	509(A)0200	CLASS AA CONCRETE	626.200	CY
	0420	509(B)0320	CLASS A CONCRETE	7.100	CY
	0430	510(C)1430	SLOPE WALL (4")	979.000	SY
	0440	511(B)2310	EPOXY COATED REINFORCING STEEL	191,487.300	LB
	0450	512(A)3200	PAINTING EXISTING STRUCTURES	1.000	LSUM
	0460	512(B)3300	COLLECTION AND HANDLING OF WASTE	1.000	LSUM
	0470	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	1,490.100	SY
	0480	517 9110	ELASTOMERIC COATING	1,238.100	SF
	0490	518(B)0300	SEALED EXPANSION JOINTS	188.500	LF
	0500	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	200.000	LF
	0510	520(C)1400	EPOXY RESIN, ABOVE WATER	3.000	GAL
	0520	521(A)2200	PNEUMATICALLY PLACED MORTAR	29.000	SY
	0530	523(A)3200	SEALER CRACK PREPARATION	186.500	LF
	0540	523(B)3300	SEALER RESIN	3.000	GAL
	0550	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	55.000	SY
	0560	542 9111	(PL)INSTALLATION OF BRIDGE ITEMS(TYPE A)	10.000	EA
	0570	545 0111	(PL)REPLACE BRIDGE ITEM (TYPE A)	16.000	EA
	0580	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
	0590	624(E)3630	FENCE-STYLE CLF (6' HIGH, VINYL COATED)	458.000	LF
0003	TRAFFIC				
	0600	871(B)2300	CONST.ZONE IMPACT ATTEN.	720.000	SD
	0610	876(A)3210	(PL)TRUCK MOUNTED ATTENUATOR	720.000	SD
	0620	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	1,800.000	LF
	0630	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	1,800.000	LF
	0640	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	54,000.000	SD
	0650	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	6,660.000	SD
	0660	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	4,500.000	SD
	0670	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	4,500.000	SD
	0680	880(C)6420	WING BARRICADES	720.000	SD
	0690	880(E)6600	WARNING LIGHTS(TYPE A)	11,900.000	SD
	0700	880(F)6700	DRUMS	15,700.000	SD
	0710	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	360.000	SD

Proposal:260202 **Let Date:**August 20, 2026 **Call Order:**650
J/P Num:31082(04) **Proj. Num:**NHPPI-4440-(011)PM
Counties:TULSA
Description:BRIDGE REHABILITATION
CITY STREET (DENVER AVE.): OVER I-444,
0.60 MILES EAST OF THE I-244 INTERCHANGE
IN THE CITY OF TULSA.
PROJECT LENGTH = 0.073 MILES

Line #		Item Description	Quantity	Unit
0004	TRAFFIC SIGNING AND STRIPING			
0720	802(A)0240	2" GALV.STEEL ELECT.COND. EXPOSED	480.000	LF
0730	802(E)0600	JUNCTION BOX(6" X 6" X 4")	2.000	EA
0740	805(A)3200	REMOVAL OF SIGN FOOTING	1.000	EA
0750	805(D)3504	(PL)REMOVE & RESET LIGHT POLE	2.000	EA
0760	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	9.000	EA
0770	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	2,050.000	LF
0780	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	135.000	LF
0790	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	65.000	LF
0800	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	5.000	EA
0005	TRAFFIC			
0810	802(A)0240	2" GALV.STEEL ELECT.COND. EXPOSED	200.000	LF
0820	802(A)0250	2" GALV.STEEL ELECT.COND. TRENCHED	100.000	LF
0830	803(A)1200	PULL BOX	2.000	EA
0840	809(A)7200	ROADWAY LUMINAIRE	2.000	EA
0006	STAKING			
0850	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0007	CONSTRUCTION			
0860	641 2100	MOBILIZATION	1.000	LSUM