Proposal:260231 **Let Date:**September 17, 2026 **Call Order:**810
J/P Num:34367(04) **Proj. Num:**NHPP-023N(003)FP
Counties:CIMARRON
Description:BRIDGE REHABILITATION
US-56: OVER THE BNSF RAILROAD, 0.2 MILES WEST OF THE US-287 JUNCTION IN THE CITY OF BOISE CITY.
PROJECT LENGTH = 0.087 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	381.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	80.000	CY
0040	221(B)2300	TEMPORARY SILT FENCE	3,000.000	LF
0050	230(A)7200	SOLID SLAB SODDING	1,500.000	SY
0060	307(K)4200	STABILIZED SUBGRADE	794.000	SY
0070	317 7100	CEMENT TREATED BASE	794.000	SY
0080	408 8100	PRIME COAT	28.000	GAL
0090	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	1,108.000	SY
0100	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	741.000	SY
0110	414(G)5800	P.C. CONCRETE FOR PAVEMENT	343.000	CY
0120	609(A)4230	CONC.CURB(6" BARRIER-INTEGRAL)	236.000	LF
0130	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	803.000	SY
0140	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	290.000	SY
0150	619(B)6396	REMOVAL OF GUARDRAIL	2,020.000	LF
0160	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	1,612.500	LF
0170	623(G)1820	GUARDRAIL END TREATMENT (31")	4.000	EA
0180	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	4.000	EA
0190	853 5170	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	44.000	EA
0002	BRIDGE			
0200	501(G)1800	CLSM BACKFILL	729.000	CY
0210	504(A)5200	APPROACH SLAB	751.800	SY
0220	504(B)5300	SAW-CUT GROOVING	2,143.900	SY
0230	504(D)5420	CONCRETE RAIL (TR4)	689.100	LF
0240	506(A)7225	STRUCTURAL STEEL M270 GRADE 50W	332,510.000	LB
0250	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	14.000	EA
0260	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	28.000	EA
0270	509 0100	SPECIAL CONCRETE FINISH	96.000	SY
0280	509(A)0210	CLASS AA CONCRETE	344.000	CY
0290	509(B)0320	CLASS A CONCRETE	57.000	CY
0300	510(C)1450	SLOPE WALL (5")	170.000	SY
0310	511(B)2310	EPOXY COATED REINFORCING STEEL	106,710.000	LB
0320	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	973.000	SY
0330	517 9110	ELASTOMERIC COATING	1,998.000	SF
0340	518(B)0300	SEALED EXPANSION JOINTS	81.360	LF
0350	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	205.000	LF
0360	520(C)1400	EPOXY RESIN, ABOVE WATER	16.000	GAL
0370	521(A)2200	PNEUMATICALLY PLACED MORTAR	82.000	SY
0380	523(A)3200	SEALER CRACK PREPARATION	310.000	LF
0390	523(B)3300	SEALER RESIN	3.500	GAL
0400	524(A)4200	(SP) CARBON FIBER-REINFORCED POLYMER	246.000	SF
0410	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	175.000	SY
0420	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
0430	624(E)3640	FENCE-STYLE CLF (8'HIGH, CLASS A)	200.000	LF

Proposal:260231 **Let Date:**September 17, 2026 **Call Order:**810
J/P Num:34367(04) **Proj. Num:**NHPP-023N(003)FP
Counties:CIMARRON
Description:BRIDGE REHABILITATION
US-56: OVER THE BNSF RAILROAD, 0.2 MILES WEST OF THE US-287 JUNCTION IN THE CITY OF BOISE CITY.
PROJECT LENGTH = 0.087 MILES

Line #		Item Description	Quantity	Unit
0003	TRAFFIC CONTROL			
0440	104 3250	(SP) RAILROAD FLAGGING(NON-BIDDABLE)	240.000	DAY
0450	823 6100	(SP)PORTABLE TRAFFIC SIGNAL SYSTEM	120.000	SD
0460	857(C)9400	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	13,600.000	LF
0470	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	8,600.000	LF
0480	858(A)0216	PAVE.MARKERS CLASS A TYPE 2-A	60.000	EA
0490	858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	780.000	EA
0500	858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	550.000	EA
0510	871(B)2300	CONST.ZONE IMPACT ATTEN.	480.000	SD
0520	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	1,075.000	LF
0530	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	1,075.000	LF
0540	880(A)6220	ARROW DISPLAY(TYPE C)	240.000	SD
0550	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	4,320.000	SD
0560	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	9,360.000	SD
0570	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,360.000	SD
0580	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	5,040.000	SD
0590	880(E)6607	WARNING LIGHTS(TYPE B)	12,480.000	SD
0600	880(E)6610	WARNING LIGHTS(TYPE C)	19,800.000	SD
0610	880(F)6700	DRUMS	19,800.000	SD
0620	880(G)6800	TUBE CHANNELIZERS	4,800.000	SD
0630	880(G)6805	CHANNELIZER CONES	18,600.000	SD
0640	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	480.000	SD
0004	TRAFFIC SIGNING AND STRIPING			
0650	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	1.000	EA
0660	850(A)1200	SHEET ALUMINUM SIGNS	32.000	SF
0670	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	9,700.000	LF
0005	STAKING			
0680	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
0690	641 2100	MOBILIZATION	1.000	LSUM