Proposal: 260243 **Let Date:** September 17, 2026 **Call Order:** 875
J/P Num: 39200(04) **Proj. Num:** STP-272F(471)3B
Counties: TULSA
Description: JOINT SEAL/REPAIR
I-44/COUNTY ROAD (91ST STREET): OVER ARKANSAS RIVER, PEORIA AVE, AND US-75, AT MULTIPLE LOCATIONS IN DISTRICT VIII.
PROJECT LENGTH = 0.00 MILES

Line #		Item Description	Quantity	Unit
0001	BRIDGE "A"- NBI 16563			
0010	501(G)1800	CLSM BACKFILL	7.000	CY
0020	523(C)3400	DECK AREA SEALED (FLOODCOATS)	551.000	SY
0030	540 8120	(PL)REPAIR BRIDGE ITEM (TYPE A)	1.000	EA
0002	BRIDGE "B"- NBI 20580			
0040	502(B)3310	FALSEWORK AND JACKING	1.000	LSUM
0050	513(B)4300	CLASS B BRIDGE DECK REPAIR	100.000	SY
0060	513(C)4400	CLASS C BRIDGE DECK REPAIR	50.000	SY
0070	523(C)3400	DECK AREA SEALED (FLOODCOATS)	16,370.000	SY
0080	540 8136	(PL)REPAIR BRIDGE ITEM (TYPE B)	5.000	EA
0090	540 8152	(PL)REPAIR BRIDGE ITEM (TYPE C)	8.000	EA
0003	BRIDGE "C"- NBI 28775			
0100	513(B)4300	CLASS B BRIDGE DECK REPAIR	20.000	SY
0110	513(C)4400	CLASS C BRIDGE DECK REPAIR	20.000	SY
0120	515(B)7300	WATER REPELLENT (PERFORMANCE TESTED)	4,870.000	SY
0130	523(A)3200	SEALER CRACK PREPARATION	350.000	LF
0140	523(B)3300	SEALER RESIN	2.300	GAL
0150	523(C)3400	DECK AREA SEALED (FLOODCOATS)	4,870.000	SY
0160	540 8168	(PL)REPAIR BRIDGE ITEM (TYPE D)	3.000	EA
0004	TRAFFIC CONTROL			
0170	857(E)9630	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-2	1,088.000	EA
0180	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	8,000.000	LF
0190	876(A)3210	(PL)TRUCK MOUNTED ATTENUATOR	104.000	SD
0200	880(A)6220	ARROW DISPLAY(TYPE C)	66.000	SD
0210	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	742.000	SD
0220	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	317.000	SD
0230	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,237.000	SD
0240	880(E)6607	WARNING LIGHTS(TYPE B)	856.000	SD
0250	880(E)6616	WARNING LIGHTS(TYPE D)	7,035.000	SD
0260	880(F)6700	DRUMS	4,269.000	SD
0270	880(G)6805	CHANNELIZER CONES	2,770.000	SD
0280	880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	70.000	HOUR
0290	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	292.000	SD
0005	TRAFFIC SIGNING AND STRIPING			
0300	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	16,276.000	LF
0006	CONSTRUCTION			
0310	641 2100	MOBILIZATION	1.000	LSUM