Proposal:260253 **Let Date:**January 21, 2027 **Call Order:**670
J/P Num:38029(04) **Proj. Num:**TAP-249E(098)TP
Counties:MAYES
Description:PEDESTRIAN IMPROVEMENTS (SIDEWALKS)
SH-20: AT THE INTERSECTION OF CITY STREET (GRAHAM AVENUE),
IN PRYOR CREEK.
PROJECT LENGTH = 0.141

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(H)2900	EARTHWORK	1.000	LSUM
0030	221(C)2400	TEMPORARY SEDIMENT FILTER	2.000	EA
0040	221(G)2800	TEMPORARY FIBER LOG	500.000	LF
0050	303(A)1200	AGGREGATE BASE TYPE A	364.000	CY
0060	310(B)5300	SUBGRADE, METHOD B	819.000	SY
0070	325 0100	SEPARATOR FABRIC	2,029.000	SY
0080	411(C)1420	SUPERPAVE, TYPE S4(PG 70-28 OK)	85.000	TON
0090	412 3100	COLD MILLING PAVEMENT	759.000	SY
0100	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	173.000	SY
0110	414(E)5600	FULL DEPTH P.C.C. PATCH (PLACEMENT)	89.000	SY
0120	414(G)5800	P.C. CONCRETE FOR PAVEMENT	117.000	CY
0130	509(A)0200	CLASS AA CONCRETE	20.000	CY
0140	511(A)2200	REINFORCING STEEL	1,800.000	LB
0150	516(A)8215	DRILLED SHAFTS 30" DIAMETER	56.000	LF
0160	609(A)4230	CONC.CURB(6" BARRIER-INTEGRAL)	94.000	LF
0170	609(B)4310	COMBINED CURB & GUTTER(6" BARRIER)	412.000	LF
0180	610(A)5200	4" CONCRETE SIDEWALK	490.000	SY
0190	610(E)5600	BRICK OR STONE SIDEWALK	4.000	SY
0200	610(I)6000	TACTILE WARNING DEVICE-NEW	130.000	SF
0210	610(J)6100	(PL) STAMPED CONCRETE FINISH	132.000	SY
0220	612(H)3900	VALVE RESET	6.000	EA
0230	612(I)4000	WATER METER RESET	2.000	EA
0240	613(K)6500	EDGE DRAIN OUTLET LATERAL-NONPERFORATED	335.000	LF
0250	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0260	619(B)6356	REMOVAL OF CURB AND GUTTER	372.000	LF
0270	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	263.000	SY
0280	619(B)6376	REMOVAL OF CONC.PAV.W/ASPH.OVERLAY	611.000	SY
0290	619(B)6404	REMOVAL OF SIDEWALK	285.000	SY
0300	619(C)6600	SAWING PAVEMENT	768.000	LF
0310	626(A)5200	MONUMENTS	2.000	EA

Proposal:260253 **Let Date:**January 21, 2027 **Call Order:**670
J/P Num:38029(04) **Proj. Num:**TAP-249E(098)TP
Counties:MAYES
Description:PEDESTRIAN IMPROVEMENTS (SIDEWALKS)
SH-20: AT THE INTERSECTION OF CITY STREET (GRAHAM AVENUE),
IN PRYOR CREEK.
PROJECT LENGTH = 0.141

Line #		Item Description	Quantity	Unit
0002	TRAFFIC SIGNAL			
0320	802(B)0320	2" PVC SCH.40 PLASTIC CONDUIT BORED	435.000	LF
0330	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	155.000	LF
0340	802(B)0328	3" PVC SCH.40 PLASTIC CONDUIT BORED	250.000	LF
0350	802(B)0332	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	20.000	LF
0360	802(B)0340	4" PVC SCH.40 PLASTIC CONDUIT TRENCHED	90.000	LF
0370	803(A)1220	PULL BOX(SIZE II)	7.000	EA
0380	804(A)2200	STRUCTURAL CONCRETE	21.000	CY
0390	804(B)2300	REINFORCING STEEL	2,976.000	LB
0400	805(A)3256	(PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1.000	LSUM
0410	806(A)4216	32'MH POLE 30'TS & 8'LMA(G.STL.)	2.000	EA
0420	806(A)4218	32'MH POLE 25'TS & 8'LMA(G.STL.)	2.000	EA
0430	806(B)4408	10' MTG.HT.TS PED.POLE(G.STL.)	2.000	EA
0440	806(B)4420	15' MTG.HT.TS PED.POLE(G.STL.)	2.000	EA
0450	809(A)7200	ROADWAY LUMINAIRE	4.000	EA
0460	811 9120	1/C NO.6 ELECT.COND.	225.000	LF
0470	811 9130	1/C NO.10 ELECT.COND.	2,180.000	LF
0480	824(C)7400	(SP)CABINET	1.000	EA
0490	825 8100	TRAFFIC SIGNAL CONTROLLER ASSEMBLY	1.000	EA
0500	828 0110	(PL)DETECTION SYSTEM (RADAR)	1.000	LSUM
0510	830 2100	PEDESTRIAN PUSH BUTTON	8.000	EA
0520	831 3116	1WAY2SEC.ADJ.PED.SIG.HD.S-20	8.000	EA
0530	831 3120	1WAY3SEC.ADJ.SIG.HD.S-6	8.000	EA
0540	833 5100	BACKPLATE	8.000	EA
0550	834(A)6200	2/C TRAFFIC SIGNAL ELECTRICAL CABLE	1,020.000	LF
0560	834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	625.000	LF
0570	834(A)6235	21/C TRAFFIC SIGNAL ELECTRICAL CABLE	495.000	LF
0003	TRAFFIC SIGNING AND STRIPING			
0580	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	5.000	EA
0590	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	1.000	EA
0600	850(A)1200	SHEET ALUMINUM SIGNS	10.000	SF
0610	850(C)1400	MAST ARM MOUNTED SIGNS(ALUM.)	102.000	SF
0620	851(B)2300	1 1/2@2.72 GALV.STL.PIPE POST	65.000	LF
0630	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	1,018.000	LF
0640	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	102.000	LF
0650	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	76.000	LF
0660	856(B)8311	(SP) TRAFFIC STRIPE(PLURAL-COMP)(SYMBOLS)	5.000	EA
0670	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	1,425.000	LF

Proposal:260253 **Let Date:**January 21, 2027 **Call Order:**670
J/P Num:38029(04) **Proj. Num:**TAP-249E(098)TP
Counties:MAYES
Description:PEDESTRIAN IMPROVEMENTS (SIDEWALKS)
SH-20: AT THE INTERSECTION OF CITY STREET (GRAHAM AVENUE),
IN PRYOR CREEK.
PROJECT LENGTH = 0.141

Line #		Item Description	Quantity	Unit
0004	TEMPORARY TRAFFIC CONTROL			
0680	880(A)6200	ARROW DISPLAY(TYPE A)	90.000	SD
0690	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	2,250.000	SD
0700	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	810.000	SD
0710	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	810.000	SD
0720	880(E)6600	WARNING LIGHTS(TYPE A)	1,620.000	SD
0730	880(G)6800	TUBE CHANNELIZERS	4,860.000	SD
0740	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	180.000	SD
0005	STAKING			
0750	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
0760	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0770	641 2110	MOBILIZATION	1.000	LSUM