Proposal: 260255 **Let Date:** October 15, 2026 **Call Order:** 145
J/P Num: 31302(04) **Proj. Num:** STP-246C(074)CI
Counties: MCINTOSH
Description: GRADE, DRAIN, AND SURFACE
COUNTY ROAD (PIERCE ROAD/EW-109):
FROM 4.1 MILES WEST OF THE SH-150 INTERSECTION,
EXTEND EAST NEAR LAKE EUFAULA STATE PARK.
PROJECT LENGTH = 4.162 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	46,922.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	4,440.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	1,939.000	LF
0070	230(A)7200	SOLID SLAB SODDING	98,904.000	SY
0080	233(A)0200	VEGETATIVE MULCHING	21.000	AC
0090	241 3100	MOWING	42.000	AC
0100	303(A)1200	AGGREGATE BASE TYPE A	311.000	CY
0110	307(K)4200	STABILIZED SUBGRADE	69,696.000	SY
0120	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	463.000	TON
0130	407(B)7300	TACK COAT	5,034.000	GAL
0140	408 8100	PRIME COAT	24,395.000	GAL
0150	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	15,244.000	TON
0160	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	7,451.000	TON
0170	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	103.000	CY
0180	509(A)0200	CLASS AA CONCRETE	339.000	CY
0190	509(D)0500	CLASS C CONCRETE	2,090.000	CY
0200	511(A)2200	REINFORCING STEEL	28,862.000	LB
0210	601(A)1100	TYPE I PLAIN RIPRAP	4,887.000	TON
0220	613(A)5208	18" R.C.PIPE CLASS III	170.000	LF
0230	613(A)5216	24" R.C.PIPE CLASS III	146.000	LF
0240	613(A)5224	36" R.C.PIPE CLASS III	58.000	LF
0250	613(A)5358	28" X 18" R.C.PIPE ARCH CLASS A-III	128.000	LF
0260	613(B)5508	18" CORR. GALV. STEEL PIPE	1,834.000	LF
0270	613(B)5516	24" CORR. GALV. STEEL PIPE	46.000	LF
0280	613(B)5604	21" X 15" CORR. GALV. STEEL PIPE ARCH	1,216.000	LF
0290	613(B)5612	28" X 20" CORR. GALV. STEEL PIPE ARCH	66.000	LF
0300	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	6.000	EA
0310	613(L)6728	36" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0320	613(M)6900	TYPE A3 CULVERT END TREATMENT	107.000	EA
0330	613(M)6904	TYPE B3 CULVERT END TREATMENT	4.000	EA
0340	613(M)6924	TYPE BB3 CULVERT END TREATMENT	2.000	EA
0350	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0360	619(B)6352	REMOVAL OF FENCE	26,120.000	LF
0370	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	50,376.000	SY
0380	619(B)6396	REMOVAL OF GUARDRAIL	424.000	LF
0390	619(C)6600	SAWING PAVEMENT	1,221.000	LF
0400	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	75.000	LF
0410	623(G)1820	GUARDRAIL END TREATMENT (31")	12.000	EA
0420	624(A)3200	FENCE-STYLE WWF	4,886.000	LF
0430	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	18,253.000	LF
0440	624(C)3410	FENCE-STYLE SWF (6 BARBED WIRE)	2,683.000	LF
0450	629(A)7200	MAILBOX INSTALLATION-SINGLE	17.000	EA
0460	629(B)7300	MAILBOX INSTALLATION-MULTIPLE	5.000	EA

Proposal: 260255 **Let Date:** October 15, 2026 **Call Order:** 145
J/P Num: 31302(04) **Proj. Num:** STP-246C(074)CI
Counties: MCINTOSH
Description: GRADE, DRAIN, AND SURFACE
COUNTY ROAD (PIERCE ROAD/EW-109):
FROM 4.1 MILES WEST OF THE SH-150 INTERSECTION,
EXTEND EAST NEAR LAKE EUFAULA STATE PARK.
PROJECT LENGTH = 4.162 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0470	629(C)7400	REMOVAL OF MAILBOX INSTALLATION	31.000	EA
0480	629(D)7500	REMOVE AND RESET MAILBOX	1.000	EA
0490	629(E)7600	MAILBOX	31.000	EA
0002	TRAFFIC			
0500	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	1.000	EA
0510	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	1.000	EA
0520	850(A)1200	SHEET ALUMINUM SIGNS	66.260	SF
0530	851(C)2415	2" SQUARE TUBE POST	84.000	LF
0540	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	87,908.000	LF
0550	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	120.000	LF
0560	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	2,400.000	SD
0570	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	600.000	SD
0580	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	2,400.000	SD
0590	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,200.000	SD
0600	880(E)6600	WARNING LIGHTS(TYPE A)	3,600.000	SD
0003	STAKING			
0610	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0004	CONSTRUCTION			
0620	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0630	641 2110	MOBILIZATION	1.000	LSUM