Proposal:260256 **Let Date:**October 15, 2026 **Call Order:**150
J/P Num:38082(04) **Proj. Num:**STP-255N(635)AG
Counties:OKLAHOMA
Description:INTERSECTION MODIFICATION AND TRAFFIC SIGNALS
CITY STREET (S DOUGLAS BOULEVARD): AT THE INTERSECTION
OF SE 29TH ST, 0.23 MILES NORTH OF I-40 IN THE CITY OF MIDWEST CITY.
PROJECT LENGTH= 0.602 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	6,462.000	CY
0030	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0040	221(B)2300	TEMPORARY SILT FENCE	1,950.000	LF
0050	221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	14.000	EA
0060	230(A)7200	SOLID SLAB SODDING	7,819.000	SY
0070	233(A)0200	VEGETATIVE MULCHING	2.590	AC
0080	241 3100	MOWING	5.180	AC
0090	307(K)4200	STABILIZED SUBGRADE	15,779.000	SY
0100	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	246.000	TON
0110	407(C)7500	NT TACK MATERIAL	50.000	GAL
0120	408 8100	PRIME COAT	3,862.000	GAL
0130	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	149.000	TON
0140	411(C)1420	SUPERPAVE, TYPE S4(PG 70-28 OK)	1,563.000	TON
0150	412 3100	COLD MILLING PAVEMENT	11,851.000	SY
0160	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	2,927.000	SY
0170	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	11,659.000	SY
0180	414(G)5800	P.C. CONCRETE FOR PAVEMENT	3,975.000	CY
0190	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	5.000	CY
0200	509(A)0200	CLASS AA CONCRETE	12.000	CY
0210	509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	4.000	CY
0220	509(D)0500	CLASS C CONCRETE	13.000	CY
0230	511(A)2200	REINFORCING STEEL	2,114.000	LB
0240	609(A)4270	CONC.CURB(8" BARRIER-INTEGRAL)	2,351.000	LF
0250	609(B)4345	1'-8" COMB.CRB.& GUT.(8" BARRIER)	1,605.000	LF
0260	610(A)5200	4" CONCRETE SIDEWALK	1,174.000	SY
0270	610(B)5320	8" CONCRETE DRIVEWAY	1,666.000	SY
0280	610(C)5410	6" CONCRETE DIVIDING STRIP	85.000	SY
0290	610(I)6000	TACTILE WARNING DEVICE-NEW	200.000	SF
0300	610(J)6100	(PL) STAMPED CONCRETE FINISH	119.000	SY
0310	611(A)7210	MANHOLE (4' DIA.)	1.000	EA
0320	611(G)0264	INLET W/SMALL JCT. BOX, CI, DES.2	1.000	EA
0330	611(G)7754	INLET CI DES. 2 (STD)	1.000	EA
0340	611(G)7794	INLET CI DES. 3 (D)	1.000	EA
0350	611(G)7802	INLET CI DES. 3 (B-D)	1.000	EA
0360	611(G)8032	INLET CDI RCB DES. 9	1.000	EA
0370	611(L)1600	JUNCTION BOXES	195.000	CF
0380	612(A)3200	MANHOLES ADJUST TO GRADE	1.000	EA
0390	612(E)3600	VALVE BOXES ADJUST TO GRADE	5.000	EA
0400	612(I)4010	WATER METER RELOCATION	4.000	EA
0410	613(A)5208	18" R.C.PIPE CLASS III	9.000	LF
0420	613(A)5216	24" R.C.PIPE CLASS III	44.000	LF
0430	613(A)5220	30" R.C.PIPE CLASS III	79.000	LF
0440	613(A)5358	28" X 18" R.C.PIPE ARCH CLASS A-III	50.000	LF
0450	613(A)5370	43" X 26" R.C.PIPE ARCH CLASS A-III	50.000	LF
0460	613(L)6620	28" X 18" PREFAB. CULVERT END SEC., ARCH	1.000	EA

Proposal:260256 **Let Date:**October 15, 2026 **Call Order:**150
J/P Num:38082(04) **Proj. Num:**STP-255N(635)AG
Counties:OKLAHOMA
Description:INTERSECTION MODIFICATION AND TRAFFIC SIGNALS
CITY STREET (S DOUGLAS BOULEVARD): AT THE INTERSECTION
OF SE 29TH ST, 0.23 MILES NORTH OF I-40 IN THE CITY OF MIDWEST CITY.
PROJECT LENGTH= 0.602 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0470	613(L)6648	43" X 26" PREFAB. CULVERT END SEC., ARCH	2.000	EA
0480	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0490	616(D)2768	12" X 6" TAPPING SLEEVE	1.000	EA
0500	616(D)2812	6" TAPPING VALVE AND BOX	1.000	EA
0510	616(G)3111	FIRE HYDRANT AND ASSEMBLY	1.000	EA
0520	616(G)3115	FLUSH FIRE HYDRANTS	1.000	EA
0530	616(S)4405	6" PLUG	1.000	EA
0540	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0550	619(B)6356	REMOVAL OF CURB AND GUTTER	3,851.000	LF
0560	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	1,309.000	SY
0570	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	9,947.000	SY
0580	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	2,292.000	SY
0590	619(B)6404	REMOVAL OF SIDEWALK	386.000	SY
0600	619(B)6448	REMOVAL OF FIRE HYDRANT	1.000	EA
0610	619(B)6492	REMOVE WATER METER AND METER CAN	2.000	EA
0620	619(B)6496	REMOVAL OF GATE VALVE AND BOX	1.000	EA
0630	619(C)6600	SAWING PAVEMENT	3,423.000	LF

Proposal:260256 **Let Date:**October 15, 2026 **Call Order:**150
J/P Num:38082(04) **Proj. Num:**STP-255N(635)AG
Counties:OKLAHOMA
Description:INTERSECTION MODIFICATION AND TRAFFIC SIGNALS
CITY STREET (S DOUGLAS BOULEVARD): AT THE INTERSECTION
OF SE 29TH ST, 0.23 MILES NORTH OF I-40 IN THE CITY OF MIDWEST CITY.
PROJECT LENGTH= 0.602 MILES

Line #		Item Description	Quantity	Unit
0002	TRAFFIC			
0640	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	475.000	LF
0650	802(B)0328	3" PVC SCH.40 PLASTIC CONDUIT BORED	635.000	LF
0660	802(B)0332	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	150.000	LF
0670	803(A)1210	PULL BOX(SIZE I)	3.000	EA
0680	803(A)1220	PULL BOX(SIZE II)	5.000	EA
0690	804(A)2200	STRUCTURAL CONCRETE	53.870	CY
0700	804(B)2300	REINFORCING STEEL	7,694.800	LB
0710	805(A)3256	(PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1.000	LSUM
0720	805(D)3500	(PL)REMOVE & RESET TRAF.SIG.EQUIPMENT	1.000	LSUM
0730	806(A)4240	32'MH POLE 25'TS & 10'LMA(G.STL.)	1.000	EA
0740	806(A)4252	32'MH POLE 40'TS & 10'LMA(G.STL.)	1.000	EA
0750	806(A)4256	32'MH POLE 45'TS & 10'LMA(G.STL.)	1.000	EA
0760	806(A)4260	32'MH POLE 50'TS & 10'LMA(G.STL.)	1.000	EA
0770	806(A)4264	32'MH POLE,55'TS & 10'LMA(G.STL.)	1.000	EA
0780	806(A)4312	POLE & 25' TS MST.ARM(G.STL.)	1.000	EA
0790	806(A)4336	POLE & 55'T.S.MST.ARM(G.STL.)	1.000	EA
0800	806(B)4400	6' MTG.HT.TS PED.POLE(G.STL.)	2.000	EA
0810	806(B)4408	10' MTG.HT.TS PED.POLE(G.STL.)	9.000	EA
0830	811 9120	1/C NO.6 ELECT.COND.	400.000	LF
0840	811 9130	1/C NO.10 ELECT.COND.	2,700.000	LF
0850	825 8100	TRAFFIC SIGNAL CONTROLLER ASSEMBLY	2.000	EA
0860	828 0100	(PL)DETECTION SYSTEM (VIDEO)	1.000	LSUM
0870	830 2100	PEDESTRIAN PUSH BUTTON	16.000	EA
0880	831 3116	1WAY2SEC.ADJ.PED.SIG.HD.S-20	16.000	EA
0890	831 3120	1WAY3SEC.ADJ.SIG.HD.S-6	18.000	EA
0900	831 3124	1WAY3SEC.ADJ.SIG.HD.S-9	6.000	EA
0910	831 3144	1WAY4SEC.ADJ.SIG.HD.S-13	1.000	EA
0920	831 3156	1WAY5SEC.ADJ.SIG.HD.S-19	1.000	EA
0930	833 5100	BACKPLATE	28.000	EA
0940	834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	5,880.000	LF
0950	834(A)6210	7/C TRAFFIC SIGNAL ELECTRICAL CABLE	128.000	LF
0960	834(A)6235	21/C TRAFFIC SIGNAL ELECTRICAL CABLE	1,450.000	LF
0970	834(B)6300	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	200.000	LF
0980	840(B)0300	E.P.S. OPTICAL DETECTOR	6.000	EA
0990	840(C)0400	E.P.S. OPTICAL DETECTOR CABLE	1,296.000	LF
1000	840(D)0500	E.P.S. 2 CHANNEL PHASE SELECTOR	1.000	EA
1010	840(D)0510	E.P.S. 4 CHANNEL PHASE SELECTOR	1.000	EA
1020	850(A)1200	SHEET ALUMINUM SIGNS	167.500	SF

Proposal:260256 **Let Date:**October 15, 2026 **Call Order:**150
J/P Num:38082(04) **Proj. Num:**STP-255N(635)AG
Counties:OKLAHOMA
Description:INTERSECTION MODIFICATION AND TRAFFIC SIGNALS
CITY STREET (S DOUGLAS BOULEVARD): AT THE INTERSECTION
OF SE 29TH ST, 0.23 MILES NORTH OF I-40 IN THE CITY OF MIDWEST CITY.
PROJECT LENGTH= 0.602 MILES

Line #		Item Description	Quantity	Unit
0003	TRAFFIC SIGNING AND STRIPING			
1030	804(A)2200	STRUCTURAL CONCRETE	0.600	CY
1040	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	4.000	EA
1050	850(A)1200	SHEET ALUMINUM SIGNS	44.540	SF
1060	851(B)2305	2"@3.65 GALV.STL.PIPE POST	133.500	LF
1070	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	12,130.000	LF
1080	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	100.000	LF
1090	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	1,000.000	LF
1100	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	1,250.000	LF
1110	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	28.000	EA
1120	856(B)8315	(SP) TRAFFIC STRIPE(PLURAL-COMP)(WORDS)	3.000	EA
1130	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	15,000.000	LF
0004	TRAFFIC LIGHTING			
1140	802(B)0320	2" PVC SCH.40 PLASTIC CONDUIT BORED	1,550.000	LF
1150	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	3,075.000	LF
1160	803(A)1200	PULL BOX	53.000	EA
1170	804(A)2200	STRUCTURAL CONCRETE	34.440	CY
1180	804(B)2300	REINFORCING STEEL	5,964.000	LB
1190	806(D)4616	40' MTG.HT.HL.PTP.(G.STL.)	21.000	EA
1195	807 5100	BREAKAWAY BASE	21.000	EA
1200	811 9115	1/C NO.4 ELECT.COND.	16,100.000	LF
1210	811 9135	1/C NO.12 ELECT.COND.	2,100.000	LF
0005	TRAFFIC CONTROL			
1220	857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	21,500.000	LF
1230	857(B)9300	CONSTRUCTION TRAFFIC STR.(PAINT)(ARROWS)	6.000	EA
1240	857(C)9405	REMOVABLE PAVEMENT MARKING TAPE(6" WIDE)	85,798.000	LF
1250	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	90,000.000	LF
1260	858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	5,000.000	EA
1270	858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	5,000.000	EA
1280	871(B)2300	CONST.ZONE IMPACT ATTEN.	210.000	SD
1290	871(C)2410	RELOCATION OF IMPACT ATTENUATOR	17.000	EA
1300	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	665.000	LF
1310	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	1,255.000	LF
1320	880(A)6210	ARROW DISPLAY(TYPE B)	360.000	SD
1330	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	2,760.000	SD
1340	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	10,740.000	SD
1350	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,660.000	SD
1360	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	7,170.000	SD
1370	880(E)6607	WARNING LIGHTS(TYPE B)	18,000.000	SD
1380	880(E)6616	WARNING LIGHTS(TYPE D)	15,000.000	SD
1390	880(F)6700	DRUMS	15,000.000	SD
1400	880(G)6805	CHANNELIZER CONES	6,030.000	SD
1410	880(N)7500	(SP) TEMP. TRAFF. SIGNAL SPAN WIRE EQUIP	1.000	LSUM
1420	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	420.000	SD

Proposal: 260256 **Let Date:** October 15, 2026 **Call Order:** 150
J/P Num: 38082(04) **Proj. Num:** STP-255N(635)AG
Counties: OKLAHOMA
Description: INTERSECTION MODIFICATION AND TRAFFIC SIGNALS
CITY STREET (S DOUGLAS BOULEVARD): AT THE INTERSECTION
OF SE 29TH ST, 0.23 MILES NORTH OF I-40 IN THE CITY OF MIDWEST CITY.
PROJECT LENGTH= 0.602 MILES

	Line #		Item Description	Quantity	Unit
0006	STAKING				
	1430	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0007	CONSTRUCTION				
	1440	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
	1450	641 2100	MOBILIZATION	1.000	LSUM