Proposal:260259 **Let Date:**October 22, 2026 **Call Order:**270
J/P Num:19983(11) **Proj. Num:**STP-166C(202)PM
Counties:ROGERS, WAGONER
Description:INTERCHANGE
US-412: AT SH-412P, 6.6 MILES WEST OF THE SH-88 INTERCHANGE
NEAR FAIR OAKS.
PROJECT LENGTH = 1.015 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	129,830.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	235,849.000	CY
0040	202(E)2600	SELECT BORROW	500.000	CY
0050	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0060	221(B)2300	TEMPORARY SILT FENCE	17,357.000	LF
0070	221(C)2400	TEMPORARY SEDIMENT FILTER	17.000	EA
0080	221(D)2500	TEMPORARY SEDIMENT BASIN	9.000	EA
0090	221(E)2600	TEMPORARY SILT DIKE	5,488.000	LF
0100	221(F)2720	TEMPORARY ROCK FILTER DAM TYPE 3	198.000	CY
0110	229 6100	DITCH LINER PROTECTION	9,588.000	LF
0120	230(A)7200	SOLID SLAB SODDING	94,252.000	SY
0130	232(A)9200	SEEDING METHOD A	31.780	AC
0140	233(A)0200	VEGETATIVE MULCHING	31.780	AC
0150	241 3100	MOWING	254.240	AC
0160	242 4101	STABILIZED CONSTRUCTION EXIT	2.000	EA
0170	303(A)1200	AGGREGATE BASE TYPE A	14,720.000	CY
0180	307(K)4200	STABILIZED SUBGRADE	67,288.000	SY
0190	325 0100	SEPARATOR FABRIC	78,854.000	SY
0200	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	8,456.000	TON
0210	408 8100	PRIME COAT	15,437.000	GAL
0220	411(L)2404	BMD, TYPE B3 (PG 64-22 OK)	8,728.000	TON
0230	411(L)2408	BMD, TYPE B3 (PG 70-28 OK)	2,245.000	TON
0240	411(L)2424	BMD, TYPE B4 (PG 64-22 OK)	533.000	TON
0250	411(L)2428	BMD, TYPE B4 (PG 70-28 OK)	894.000	TON
0260	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	13,595.000	SY
0270	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	24,863.000	SY
0280	414(G)5800	P.C. CONCRETE FOR PAVEMENT	10,147.000	CY
0290	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	75.000	CY
0300	504(E)5520	42" F-SHAPED PARAPET	1,309.000	LF
0310	509(A)0200	CLASS AA CONCRETE	214.000	CY
0320	509(D)0500	CLASS C CONCRETE	894.000	CY
0330	511(A)2200	REINFORCING STEEL	27,570.000	LB
0340	601(B)1200	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	220.000	TON
0350	602(C)2410	FILTER FABRIC	147.000	SY
0360	610(B)5310	6" CONCRETE DRIVEWAY	36.000	SY
0370	610(C)5410	6" CONCRETE DIVIDING STRIP	997.000	SY
0380	611(A)7210	MANHOLE (4' DIA.)	1.000	EA
0390	613(A)5216	24" R.C.PIPE CLASS III	421.000	LF
0400	613(A)5220	30" R.C.PIPE CLASS III	125.000	LF
0410	613(B)5508	18" CORR. GALV. STEEL PIPE	203.000	LF
0420	613(B)5516	24" CORR. GALV. STEEL PIPE	221.000	LF
0430	613(B)5604	21" X 15" CORR. GALV. STEEL PIPE ARCH	152.000	LF
0440	613(L)6608	21" X 15" PREFAB. CULVERT END SEC., ARCH	2.000	EA
0450	613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	3.000	EA
0460	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	5.000	EA

Proposal:260259 **Let Date:**October 22, 2026 **Call Order:**270
J/P Num:19983(11) **Proj. Num:**STP-166C(202)PM
Counties:ROGERS, WAGONER
Description:INTERCHANGE
US-412: AT SH-412P, 6.6 MILES WEST OF THE SH-88 INTERCHANGE
NEAR FAIR OAKS.
PROJECT LENGTH = 1.015 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0470	613(L)6724	30" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0480	613(M)6964	TYPE B4 CULVERT END TREATMENT	2.000	EA
0490	613(M)7004	TYPE A6 CULVERT END TREATMENT	1.000	EA
0500	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0510	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	10,676.000	SY
0520	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	16,587.000	SY
0530	619(B)6400	REMOVAL OF CURB	200.000	LF
0540	619(C)6600	SAWING PAVEMENT	1,970.000	LF
0550	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	87.500	LF
0560	623(F)1764	GUARDRAIL TRAIL END TURNDOWN (31")	1.000	EA
0570	623(G)1820	GUARDRAIL END TREATMENT (31")	1.000	EA
0580	624(A)3200	FENCE-STYLE WWF	5,659.000	LF
0590	853 5170	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	6.000	EA
0600	871(A)2200	IMPACT ATTENUATOR	6.000	EA
0002	BRIDGE 'B' - NBI NO. 30082			
0610	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	110.000	CY
0620	501(G)1800	CLSM BACKFILL	198.200	CY
0630	503(A)4230	PRESTRESSED CONCRETE BEAMS (TYPE III)	701.000	LF
0640	503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	1,076.000	LF
0650	504(A)5200	APPROACH SLAB	293.400	SY
0660	504(B)5300	SAW-CUT GROOVING	1,814.900	SY
0670	504(E)5520	42" F-SHAPED PARAPET	692.000	LF
0680	506(A)7200	STRUCTURAL STEEL	2,030.000	LB
0690	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	12.000	EA
0700	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	36.000	EA
0710	507(C)8400	ELASTOMERIC BEARING PADS	36.000	EA
0720	509 0100	SPECIAL CONCRETE FINISH	2,404.000	SY
0730	509(A)0210	CLASS AA CONCRETE	499.900	CY
0740	509(B)0320	CLASS A CONCRETE	380.400	CY
0750	510(C)1450	SLOPE WALL (5")	827.000	SY
0760	511(A)2210	REINFORCING STEEL	4,120.000	LB
0770	511(B)2310	EPOXY COATED REINFORCING STEEL	237,720.000	LB
0780	514(A)5210	PILES, FURNISHED (HP 10X42)	513.000	LF
0790	514(B)5310	PILES, DRIVEN (HP 10X42)	513.000	LF
0800	514(G)5800	METAL PILE SHOES	18.000	EA
0810	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0820	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	945.000	SY
0830	516(A)8255	DRILLED SHAFTS 84" DIAMETER	328.000	LF
0840	516(C)8400	CROSSHOLE SONIC LOGGING	3.000	EA
0850	517 9110	ELASTOMERIC COATING	1,156.000	SF
0860	523(A)3200	SEALER CRACK PREPARATION	440.000	LF
0870	523(B)3300	SEALER RESIN	14.000	GAL
0880	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	240.000	LF
0890	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	80.000	LF

Proposal:260259 **Let Date:**October 22, 2026 **Call Order:**270
J/P Num:19983(11) **Proj. Num:**STP-166C(202)PM
Counties:ROGERS, WAGONER
Description:INTERCHANGE
US-412: AT SH-412P, 6.6 MILES WEST OF THE SH-88 INTERCHANGE
NEAR FAIR OAKS.
PROJECT LENGTH = 1.015 MILES

Line #		Item Description	Quantity	Unit
0003	TRAFFIC CONTROL			
0900	857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	35,046.000	LF
0910	857(B)9300	CONSTRUCTION TRAFFIC STR.(PAINT)(ARROWS)	8.000	EA
0920	857(E)9620	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	100.000	EA
0930	857(F)9710	PAVEMENT MARKING REMOVAL(ARROWS)	17.000	EA
0940	857(F)9740	PAVEMENT MARKING REMOVAL (HYDROBLASTING)	53,928.000	LF
0950	858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	5,130.000	EA
0960	858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	3,150.000	EA
0970	871(B)2300	CONST.ZONE IMPACT ATTEN.	1,200.000	SD
0980	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	2,750.000	LF
0990	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	6,890.000	LF
1000	880(A)6220	ARROW DISPLAY(TYPE C)	675.000	SD
1010	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	24,645.000	SD
1020	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	13,185.000	SD
1030	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	8,310.000	SD
1040	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	15,405.000	SD
1050	880(D)6500	VERTICAL PANELS	84,000.000	SD
1060	880(E)6607	WARNING LIGHTS(TYPE B)	39,120.000	SD
1070	880(F)6700	DRUMS	106,395.000	SD
1080	880(I)7000	FLAGGER	35.000	SD
1090	880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	840.000	HOUR
1100	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	2,038.000	SD
0004	TRAFFIC SIGNING AND STRIPING			
1110	804(A)2200	STRUCTURAL CONCRETE	21.000	CY
1120	804(B)2300	REINFORCING STEEL	2,846.000	LB
1130	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	2.000	EA
1140	850(A)1200	SHEET ALUMINUM SIGNS	346.000	SF
1150	850(B)1310	EXTRUDED ALUMINUM PANEL SIGNS	691.000	SF
1160	851(A)2200	4"@13 GALV.STL.WD.FLANGE BM.POST	29.000	LF
1170	851(A)2205	6"@15 GALV.STL.WD.FLANGE BM.POST	429.000	LF
1180	851(B)2305	2"@3.65 GALV.STL.PIPE POST	114.000	LF
1190	851(B)2310	2 1/2"@5.79 GALV.STL.PIPE POST	240.000	LF
1200	851(C)2415	2" SQUARE TUBE POST	128.000	LF
1210	851(C)2420	2 1/4" SQUARE TUBE POST	276.000	LF
1220	853 5130	DELINEATORS(TYPE 1, CODE 1, FLEXIBLE)	77.000	EA
1230	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	57,685.000	LF
1240	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	3,874.000	LF
1250	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	51.000	LF
1260	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	12.000	EA
1270	858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	164.000	EA
1280	858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	89.000	EA
0005	STAKING			
1290	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM

Proposal:260259 **Let Date:**October 22, 2026 **Call Order:**270
J/P Num:19983(11) **Proj. Num:**STP-166C(202)PM
Counties:ROGERS, WAGONER
Description:INTERCHANGE
US-412: AT SH-412P, 6.6 MILES WEST OF THE SH-88 INTERCHANGE
NEAR FAIR OAKS.
PROJECT LENGTH = 1.015 MILES

	Line #		Item Description	Quantity	Unit
0006	CONSTRUCTION				
	1300	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
	1310	640(A)1210	FIELD OFFICE	1.000	EA
	1320	641 2110	MOBILIZATION	1.000	LSUM