Proposal:260264 **Let Date:**February 18, 2027 **Call Order:**880
J/P Num:36513(04) **Proj. Num:**NHPP-273N(136)AD
Counties:WAGONER
Description:PEDESTRIAN IMPROVEMENTS (SIDEWALKS)
SH-51/US-69: FROM THE INTERSECTION OF WEST 5TH ST.,
EXTEND NORTH AND EAST IN THE CITY OF WAGONER.
PROJECT LENGTH = 1.669 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	340.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	1,580.000	CY
0040	205(A)6210	TYPE A-SALVAGED TOPSOIL	792.000	CY
0050	221(B)2300	TEMPORARY SILT FENCE	5,045.000	LF
0060	221(G)2800	TEMPORARY FIBER LOG	476.000	LF
0070	229 6100	DITCH LINER PROTECTION	10.000	LF
0080	230(A)7200	SOLID SLAB SODDING	5,696.000	SY
0090	233(A)0200	VEGETATIVE MULCHING	1.000	AC
0100	303(A)1200	AGGREGATE BASE TYPE A	851.000	CY
0110	407(B)7300	TACK COAT	56.000	GAL
0120	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	125.000	TON
0130	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	84.000	TON
0140	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	41.000	CY
0150	502 3100	TEMPORARY EARTH RETAINAGE	1.000	LSUM
0160	509(A)0200	CLASS AA CONCRETE	59.000	CY
0170	509(B)0300	CLASS A CONCRETE	46.000	CY
0180	509(D)0500	CLASS C CONCRETE	6.000	CY
0190	511(A)2200	REINFORCING STEEL	13,272.000	LB
0200	601(B)1200	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	76.000	TON
0210	609(B)4330	1'-8" COMB.CRB.& GUT.(6" BARRIER)	1,810.000	LF
0220	609(C)4410	CONCRETE HEADER CURB (8"X 18")	35.000	LF
0230	610(A)5200	4" CONCRETE SIDEWALK	7,275.000	SY
0240	610(B)5300	6" CONCRETE DRIVEWAY (H.E.S.)	3,695.000	SY
0250	610(I)6000	TACTILE WARNING DEVICE-NEW	657.000	SF
0260	611(A)7220	MANHOLE (6' DIA.)	1.000	EA
0270	611(G)7700	SPECIAL INLET DRAIN	12.000	EA
0280	611(G)7710	INLET CI DES. 1 (STD)	2.000	EA
0290	611(G)8000	INLET CDI RCB DES. 1	11.000	EA
0300	611(G)8012	INLET CDI RCB DES. 4	1.000	EA
0310	611(L)1600	JUNCTION BOXES	72.000	CF
0320	612(I)4000	WATER METER RESET	7.000	EA
0330	612(J)4100	WATER LINE LOWERED	50.000	LF
0340	613(A)5208	18" R.C.PIPE CLASS III	850.000	LF
0350	613(A)5216	24" R.C.PIPE CLASS III	101.000	LF
0360	613(A)5224	36" R.C.PIPE CLASS III	46.000	LF
0370	613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	8.000	EA
0380	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0390	619(B)6356	REMOVAL OF CURB AND GUTTER	2,045.000	LF
0400	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	3,263.000	SY
0410	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	3,971.000	SY
0420	619(B)6396	REMOVAL OF GUARDRAIL	80.000	LF
0430	619(B)6404	REMOVAL OF SIDEWALK	479.000	SY
0440	619(C)6600	SAWING PAVEMENT	7,025.000	LF
0450	622(A)0200	PIPE RAILING	553.000	LF
0460	622(A)0210	1 1/2" PIPE RAILING	122.000	LF

Proposal:260264 **Let Date:**February 18, 2027 **Call Order:**880
J/P Num:36513(04) **Proj. Num:**NHPP-273N(136)AD
Counties:WAGONER
Description:PEDESTRIAN IMPROVEMENTS (SIDEWALKS)
SH-51/US-69: FROM THE INTERSECTION OF WEST 5TH ST.,
EXTEND NORTH AND EAST IN THE CITY OF WAGONER.
PROJECT LENGTH = 1.669 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0470	629(D)7500	REMOVE AND RESET MAILBOX	1.000	EA
0002	TRAFFIC			
0480	805(D)3504	(PL)REMOVE & RESET LIGHT POLE	2.000	EA
0490	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	26.000	EA
0500	850(A)1200	SHEET ALUMINUM SIGNS	83.000	SF
0510	851(C)2420	2 1/4" SQUARE TUBE POST	143.000	LF
0520	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	2,112.000	LF
0530	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	182.000	LF
0540	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	2,097.000	LF
0550	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	6.000	EA
0560	857(F)9740	PAVEMENT MARKING REMOVAL (HYDROBLASTING)	1,182.000	LF
0003	TRAFFIC CONTROL			
0570	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,152.000	SD
0580	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,008.000	SD
0590	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,980.000	SD
0600	880(E)6607	WARNING LIGHTS(TYPE B)	3,960.000	SD
0610	880(G)6805	CHANNELIZER CONES	7,848.000	SD
0620	880(I)7000	FLAGGER	330.000	SD

Proposal:260264 **Let Date:**February 18, 2027 **Call Order:**880
J/P Num:36513(04) **Proj. Num:**NHPP-273N(136)AD
Counties:WAGONER
Description:PEDESTRIAN IMPROVEMENTS (SIDEWALKS)
SH-51/US-69: FROM THE INTERSECTION OF WEST 5TH ST.,
EXTEND NORTH AND EAST IN THE CITY OF WAGONER.
PROJECT LENGTH = 1.669 MILES

Line #		Item Description	Quantity	Unit
0004	TRAFFIC SIGNALS			
0630	802(B)0328	3" PVC SCH.40 PLASTIC CONDUIT BORED	225.000	LF
0640	802(B)0332	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	435.000	LF
0650	802(B)0336	4" PVC SCH.40 PLASTIC CONDUIT BORED	555.000	LF
0660	802(B)0340	4" PVC SCH.40 PLASTIC CONDUIT TRENCHED	120.000	LF
0670	803(A)1210	PULL BOX(SIZE I)	8.000	EA
0680	803(A)1220	PULL BOX(SIZE II)	4.000	EA
0690	804(A)2200	STRUCTURAL CONCRETE	43.000	CY
0700	804(B)2300	REINFORCING STEEL	6,004.000	LB
0710	805(A)3256	(PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1.000	LSUM
0720	806(A)4244	32'MH POLE,30'TS & 10'LMA(G.STL.)	1.000	EA
0730	806(A)4252	32'MH POLE 40'TS & 10'LMA(G.STL.)	4.000	EA
0740	806(A)4312	POLE & 25' TS MST.ARM(G.STL.)	1.000	EA
0750	806(A)4324	POLE & 40' TS MST.ARM(G.STL.)	2.000	EA
0760	806(B)4400	6' MTG.HT.TS PED.POLE(G.STL.)	2.000	EA
0770	806(B)4412	12' MTG.HT.TS PED.POLE(G.STL.)	11.000	EA
0780	809(A)7200	ROADWAY LUMINAIRE	5.000	EA
0790	810(A)8200	SERVICE POLE	1.000	EA
0800	811 9120	1/C NO.6 ELECT.COND.	750.000	LF
0810	811 9130	1/C NO.10 ELECT.COND.	3,750.000	LF
0820	819(C)5400	(SP)WIRELESS DATA-VIDEO TRANSMISSION SYS	2.000	EA
0830	825 8100	TRAFFIC SIGNAL CONTROLLER ASSEMBLY	2.000	EA
0840	828 0110	(PL)DETECTION SYSTEM (RADAR)	1.000	LSUM
0850	830 2100	PEDESTRIAN PUSH BUTTON	14.000	EA
0860	831 3116	1WAY2SEC.ADJ.PED.SIG.HD.S-20	14.000	EA
0870	831 3120	1WAY3SEC.ADJ.SIG.HD.S-6	18.000	EA
0880	831 3124	1WAY3SEC.ADJ.SIG.HD.S-9	4.000	EA
0890	831 3144	1WAY4SEC.ADJ.SIG.HD.S-13	6.000	EA
0900	833 5100	BACKPLATE	28.000	EA
0910	834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	3,040.000	LF
0920	834(A)6210	7/C TRAFFIC SIGNAL ELECTRICAL CABLE	295.000	LF
0930	834(A)6220	12/C TRAFFIC SIGNAL ELECTRICAL CABLE	65.000	LF
0940	834(A)6235	21/C TRAFFIC SIGNAL ELECTRICAL CABLE	1,590.000	LF
0950	834(B)6300	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	2,935.000	LF
0960	850(C)1400	MAST ARM MOUNTED SIGNS(ALUM.)	133.000	SF
0005	STAKING			
0970	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
0980	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0990	641 2110	MOBILIZATION	1.000	LSUM