Proposal: 260270 **Let Date:** November 19, 2026 **Call Order:** 410
J/P Num: 37989(04) **Proj. Num:** TAP-214F(205)TP
Counties: CLEVELAND
Description: PEDESTRIAN IMPROVEMENTS (SIDEWALKS)
SH-39: FROM 0.50 MILES WEST OF THE US-77 INTERSECTION, EXTEND EAST IN LEXINGTON.
PROJECT LENGTH = 0.560 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	1,407.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	323.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	2,788.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	126.000	LF
0070	221(G)2800	TEMPORARY FIBER LOG	216.000	LF
0080	227 4100	(SP)TURF REINFORCEMENT MAT	884.000	SY
0090	230(A)7200	SOLID SLAB SODDING	751.000	SY
0100	233(A)0200	VEGETATIVE MULCHING	1.000	AC
0110	303(A)1200	AGGREGATE BASE TYPE A	286.000	CY
0120	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	163.000	TON
0130	407(B)7300	TACK COAT	231.000	GAL
0140	408 8100	PRIME COAT	514.000	GAL
0150	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	419.000	TON
0160	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	140.000	TON
0170	508 9100	REMOVAL OF CULVERT END	4.000	EA
0180	510(A)1200	RETAINING WALL	255.000	SY
0190	609(B)4310	COMBINED CURB & GUTTER(6" BARRIER)	1,067.000	LF
0200	610(A)5200	4" CONCRETE SIDEWALK	1,698.000	SY
0210	610(A)5220	6" CONCRETE SIDEWALK	107.000	SY
0220	610(B)5310	6" CONCRETE DRIVEWAY	47.000	SY
0230	610(I)6000	TACTILE WARNING DEVICE-NEW	240.000	SF
0240	611(G)0350	INLET (SMD-TYPE 1)	4.000	EA
0250	611(G)7714	INLET CI DES. 1 (A)	3.000	EA
0260	611(G)8050	PRECAST INLET (CDI RCB DES. 1)	2.000	EA
0270	612(E)3600	VALVE BOXES ADJUST TO GRADE	1.000	EA
0280	612(F)3700	METER BOXES ADJUST TO GRADE	3.000	EA
0290	613(A)5208	18" R.C.PIPE CLASS III	910.000	LF
0300	613(A)5216	24" R.C.PIPE CLASS III	177.000	LF
0310	613(A)5350	22" X 13" R.C.PIPE ARCH CLASS A-III	42.000	LF
0320	613(A)5400	14" X 23" R.C.PIPE ELL. CLASS HE-III	14.000	LF
0330	613(L)6612	22" X 13" PREFAB. CULVERT END SEC., ARCH	2.000	EA
0340	613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0350	613(L)6800	14" X 23" PREFAB. CULVERT END SEC., ELLI	1.000	EA
0360	613(M)6960	TYPE A4 CULVERT END TREATMENT	4.000	EA
0370	613(M)6964	TYPE B4 CULVERT END TREATMENT	3.000	EA
0380	613(S)7700	STANDARD BEDDING MATERIAL, CLASS B	201.000	CY
0390	613(V)8000	TRENCH EXCAVATION	62.000	CY
0400	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0410	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	680.000	SY
0420	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	278.000	SY
0430	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	8.000	SY
0440	619(B)6386	REMOVAL OF GRAVEL DRIVEWAY	196.000	SY
0450	619(B)6404	REMOVAL OF SIDEWALK	335.000	SY
0460	619(B)6440	REMOVAL OF EXISTING PIPE	301.000	LF

Proposal: 260270 **Let Date:** November 19, 2026 **Call Order:** 410
J/P Num: 37989(04) **Proj. Num:** TAP-214F(205)TP
Counties: CLEVELAND
Description: PEDESTRIAN IMPROVEMENTS (SIDEWALKS)
SH-39: FROM 0.50 MILES WEST OF THE US-77 INTERSECTION,
EXTEND EAST IN LEXINGTON.
PROJECT LENGTH = 0.560 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0470	619(C)6600	SAWING PAVEMENT	1,692.000	LF
0480	622(A)0200	PIPE RAILING	395.000	LF
0002	TRAFFIC CONTROL			
0490	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	11.000	EA
0500	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	1.000	EA
0510	850(A)1200	SHEET ALUMINUM SIGNS	137.000	SF
0520	851(C)2415	2" SQUARE TUBE POST	210.000	LF
0530	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	6,480.000	SD
0540	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	3,510.000	SD
0550	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	3,915.000	SD
0560	880(E)6600	WARNING LIGHTS(TYPE A)	3,915.000	SD
0570	880(G)6805	CHANNELIZER CONES	11,340.000	SD
0003	TRAFFIC SIGNING AND STRIPING			
0580	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	958.000	LF
0585	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	933.000	LF
0590	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	552.000	LF
0004	STAKING			
0600	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0610	641 2110	MOBILIZATION	1.000	LSUM