Proposal: 260276 **Let Date:** October 22, 2026 **Call Order:** 265
J/P Num: 38035(04) **Proj. Num:** TAP-257D(097)TP
Counties: OSAGE
Description: PEDESTRIAN IMPROVEMENTS (SIDEWALKS)
CITY STREET (EAST BROADWAY): FROM THE INTERSECTION OF LAKE DRIVE, EXTEND WEST IN THE TOWN OF PRUE.
PROJECT LENGTH = 0.092 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(A)2200	UNCLASSIFIED EXCAVATION	222.000	CY
0020	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0030	221(E)2600	TEMPORARY SILT DIKE	35.000	LF
0040	230(A)7200	SOLID SLAB SODDING	1,131.000	SY
0050	303(A)1200	AGGREGATE BASE TYPE A	3.000	CY
0060	509(D)0500	CLASS C CONCRETE	7.000	CY
0070	610(A)5200	4" CONCRETE SIDEWALK	222.000	SY
0080	610(B)5310	6" CONCRETE DRIVEWAY	14.000	SY
0090	610(I)6000	TACTILE WARNING DEVICE-NEW	52.000	SF
0100	613(EE)5961	12" CORRUGATED POLYPROPYLENE PIPE	32.000	LF
0110	613(EE)5965	15" CORRUGATED POLYPROPYLENE PIPE	16.000	LF
0120	613(T)7800	STANDARD BEDDING MATERIAL, CLASS C	31.000	CY
0002	TRAFFIC - BASE BID			
0130	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	2.000	EA
0140	850(A)1200	SHEET ALUMINUM SIGNS	35.000	SF
0150	851(C)2420	2 1/4" SQUARE TUBE POST	48.000	LF
0160	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	144.000	LF
0170	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	270.000	SD
0260	880(G)6805	CHANNELIZER CONES	90.000	SD
0003	TRAFFIC - ADD ALTERNATE #1			
0180	850(A)1200	SHEET ALUMINUM SIGNS	18.000	SF
0190	851(C)2420	2 1/4" SQUARE TUBE POST	24.000	LF
0004	TRAFFIC - ADD ALTERNATE #2			
0200	850(A)1200	SHEET ALUMINUM SIGNS	18.000	SF
0210	851(C)2420	2 1/4" SQUARE TUBE POST	24.000	LF
0005	TRAFFIC - ADD ALTERNATE #3			
0220	836 7110	RECTANGULAR RAPID FLASHING BEACON	2.000	EA
0006	TRAFFIC - ADD ALTERNATE #4			
0230	836 7110	RECTANGULAR RAPID FLASHING BEACON	2.000	EA
0007	STAKING			
0240	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0008	CONSTRUCTION			
0250	641 2110	MOBILIZATION	1.000	LSUM