Proposal: 260280 **Let Date:** October 15, 2026 **Call Order:** 127
J/P Num: 35808(04) **Proj. Num:** STP-242B(131)PM
Counties: LOGAN
Description: INTERSECTION MODIFICATION
SH-33: FROM 3.8 MILES WEST OF THE US-77 INTERSECTION,
EXTEND EAST NEAR GUTHRIE.
PROJECT LENGTH = 0.366 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	8,431.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	3,231.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	2,856.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	182.000	LF
0070	221(F)2710	TEMPORARY ROCK FILTER DAM TYPE 2	36.150	CY
0080	230(A)7200	SOLID SLAB SODDING	38,890.000	SY
0090	232(B)9300	SEEDING METHOD B	8.030	AC
0100	233(E)0600	(SP) HYDROMULCH	38,888.000	SY
0110	241 3100	MOWING	16.070	AC
0120	307(K)4200	STABILIZED SUBGRADE	10,625.000	SY
0130	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	367.000	TON
0140	407(B)7300	TACK COAT	1,537.000	GAL
0150	408 8100	PRIME COAT	3,719.000	GAL
0160	409(A)9200	FABRIC REINFORCEMENT	1,721.000	SY
0170	409(B)9300	BITUMINOUS BINDER	688.400	GAL
0180	411(L)2404	BMD, TYPE B3 (PG 64-22 OK)	2,512.000	TON
0190	411(L)2408	BMD, TYPE B3 (PG 70-28 OK)	599.000	TON
0200	411(L)2424	BMD, TYPE B4 (PG 64-22 OK)	615.000	TON
0210	411(L)2428	BMD, TYPE B4 (PG 70-28 OK)	977.000	TON
0220	412 3100	COLD MILLING PAVEMENT	5,160.000	SY
0230	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	35.000	CY
0240	509(A)0200	CLASS AA CONCRETE	27.000	CY
0250	511(A)2200	REINFORCING STEEL	4,072.000	LB
0260	602(B)2310	REVETMENT MATTRESSES	1,278.000	SY
0270	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0280	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	324.000	SY
0290	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	5,484.000	SY
0300	619(B)6396	REMOVAL OF GUARDRAIL	1,510.000	LF
0310	619(B)6436	REMOVAL OF CONCRETE DITCH LINER	883.000	LF
0320	619(C)6600	SAWING PAVEMENT	3,870.000	LF
0330	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	563.000	LF
0002	SIGNING AND STRIPING			
0340	413(A)4210	RUMBLE STRIP-CENTERLINE HMA-CON	2,690.000	LF
0350	413(B)4300	RUMBLE STRIP-METHOD HMA-CYC GROUP	3.000	EAGP
0360	413(B)4310	RUMBLE STRIP-METHOD HMA-CYC	3,694.000	LF
0370	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	9.000	EA
0380	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	2.000	EA
0390	850(A)1200	SHEET ALUMINUM SIGNS	133.190	SF
0410	851(C)2420	2 1/4" SQUARE TUBE POST	140.000	LF
0420	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	13,586.000	LF
0430	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	440.000	LF
0440	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	34.000	LF
0450	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	12.000	EA

Proposal:260280 **Let Date:**October 15, 2026 **Call Order:**127
J/P Num:35808(04) **Proj. Num:**STP-242B(131)PM
Counties:LOGAN
Description:INTERSECTION MODIFICATION
SH-33: FROM 3.8 MILES WEST OF THE US-77 INTERSECTION,
EXTEND EAST NEAR GUTHRIE.
PROJECT LENGTH = 0.366 MILES

Line #		Item Description	Quantity	Unit
0003	SIGNAL (INTERSECTION CONFLICT WARNING SYSTEM)			
0460	802(A)0230	1 1/2" GALV. STEEL ELECT COND EXPOSED	10.000	LF
0470	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	1,170.000	LF
0480	802(B)0356	3" PVC SCH. 80 PLASTIC CONDUIT BORED	350.000	LF
0490	803(A)1230	PULL BOX(SIZE III)	3.000	EA
0500	811 9130	1/C NO.10 ELECT.COND.	570.000	LF
0510	824(D)7500	(SP)COMMUNICATION CABINET, POLE MOUNTED	1.000	EA
0520	828 0110	(PL)DETECTION SYSTEM (RADAR)	1.000	LSUM
0530	831 3104	1WAY1SEC.ADJ.SIG.HD.S-8	8.000	EA
0540	833 5100	BACKPLATE	8.000	EA
0550	834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	1,220.000	LF
0560	834(C)6410	UNDERGROUND COMMUNICATION CABLE	1,495.000	LF
0570	836 7100	REGULATORY OR WARNING SIGN ASSEMBLY	4.000	EA
0004	TRAFFIC LIGHTING			
0580	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	140.000	LF
0590	802(B)0356	3" PVC SCH. 80 PLASTIC CONDUIT BORED	170.000	LF
0600	803(A)1210	PULL BOX(SIZE I)	2.000	EA
0610	803(A)1230	PULL BOX(SIZE III)	2.000	EA
0620	804(A)2200	STRUCTURAL CONCRETE	3.280	CY
0630	804(B)2300	REINFORCING STEEL	568.000	LB
0640	805(A)3228	(PL)REMOVAL OF LIGHT POLE	1.000	EA
0650	806(C)4512	40' MTG & 10' HLMA(G.STL.)	2.000	EA
0660	807 5120	BREAKAWAY BASE (DES. B)	2.000	EA
0670	809(A)7200	ROADWAY LUMINAIRE	2.000	EA
0680	810(A)8200	SERVICE POLE	1.000	EA
0690	811 9120	1/C NO.6 ELECT.COND.	915.000	LF
0700	811 9135	1/C NO.12 ELECT.COND.	220.000	LF
0005	TRAFFIC CONTROL			
0710	857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	24,584.000	LF
0720	857(F)9740	PAVEMENT MARKING REMOVAL (HYDROBLASTING)	36,674.000	LF
0730	858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	265.000	EA
0740	858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	227.000	EA
0750	871(B)2300	CONST.ZONE IMPACT ATTEN.	960.000	SD
0760	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	2,091.000	LF
0770	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	2,091.000	LF
0780	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	10,410.000	SD
0790	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	9,780.000	SD
0800	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	6,090.000	SD
0810	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	480.000	SD
0820	880(E)6607	WARNING LIGHTS(TYPE B)	7,770.000	SD
0830	880(E)6616	WARNING LIGHTS(TYPE D)	6,900.000	SD
0840	880(F)6700	DRUMS	6,900.000	SD
0850	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	1,854.000	SD

Proposal: 260280 **Let Date:** October 15, 2026 **Call Order:** 127
J/P Num: 35808(04) **Proj. Num:** STP-242B(131)PM
Counties: LOGAN
Description: INTERSECTION MODIFICATION
SH-33: FROM 3.8 MILES WEST OF THE US-77 INTERSECTION,
EXTEND EAST NEAR GUTHRIE.
PROJECT LENGTH = 0.366 MILES

Line #		Item Description	Quantity	Unit
0006	STAKING			
0860	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0007	CONSTRUCTION			
0870	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0880	641 2110	MOBILIZATION	1.000	LSUM