Proposal: 260284 **Let Date:** October 22, 2026 **Call Order:** 012
J/P Num: 38973(04) **Proj. Num:** C-MC-46
Counties: NOBLE
Description: BRIDGE REHABILITATION
CIMMARON TURNPIKE / US 412 (OTA ACCESS): OVER TRIBUTARY TO RED ROCK CREEK, 1.11 MILES EAST OF US-77 NEAR PERRY.
PROJECT LENGTH= 0.413 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(A)2200	UNCLASSIFIED EXCAVATION	50.000	CY
0020	202(D)2500	UNCLASSIFIED BORROW	100.000	CY
0030	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0040	221(B)2300	TEMPORARY SILT FENCE	1,200.000	LF
0050	230(A)7200	SOLID SLAB SODDING	4,000.000	SY
0060	310(B)5300	SUBGRADE, METHOD B	1,667.000	SY
0070	408 8100	PRIME COAT	1,239.000	GAL
0080	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	93.000	TON
0090	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	1,667.000	SY
0100	414(G)5800	P.C. CONCRETE FOR PAVEMENT	417.000	CY
0110	619(B)6352	REMOVAL OF FENCE	225.000	LF
0120	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	1,948.000	SY
0130	619(B)6396	REMOVAL OF GUARDRAIL	530.000	LF
0140	619(B)6436	REMOVAL OF CONCRETE DITCH LINER	181.000	LF
0150	619(C)6600	SAWING PAVEMENT	2,000.000	LF
0160	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	475.000	LF
0170	623(G)1820	GUARDRAIL END TREATMENT (31")	2.000	EA
0180	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	2.000	EA
0190	624(C)3400	FENCE-STYLE SWF (4 BARBED WIRE)	230.000	LF
0200	853 5170	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	13.000	EA
0002	BRIDGE "A"			
0210	501(G)1800	CLSM BACKFILL	222.000	CY
0220	504(A)5200	APPROACH SLAB	731.200	SY
0230	504(B)5300	SAW-CUT GROOVING	1,637.300	SY
0240	504(E)5520	42" F-SHAPED PARAPET	355.000	LF
0250	506(A)7225	STRUCTURAL STEEL M270 GRADE 50W	348,460.000	LB
0260	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	12.000	EA
0270	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	12.000	EA
0280	509(A)0210	CLASS AA CONCRETE	222.700	CY
0290	509(D)0510	CLASS C CONCRETE	10.000	CY
0300	511(B)2310	EPOXY COATED REINFORCING STEEL	51,990.000	LB
0310	513(B)4300	CLASS B BRIDGE DECK REPAIR	15.000	SY
0320	513(C)4400	CLASS C BRIDGE DECK REPAIR	5.000	SY
0330	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	2,076.000	SY
0340	517 9110	ELASTOMERIC COATING	666.000	SF
0350	518(B)0310	EXPANSION JOINT SYSTEM	85.000	LF
0360	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	79.000	LF
0370	520(C)1400	EPOXY RESIN, ABOVE WATER	6.400	GAL
0380	521(A)2200	PNEUMATICALLY PLACED MORTAR	5.200	SY
0390	523(A)3200	SEALER CRACK PREPARATION	188.000	LF
0400	523(B)3300	SEALER RESIN	2.200	GAL
0410	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	8.200	SY
0420	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM

Proposal:260284 **Let Date:**October 22, 2026 **Call Order:**012
J/P Num:38973(04) **Proj. Num:**C-MC-46
Counties:NOBLE
Description:BRIDGE REHABILITATION
CIMMARON TURNPIKE / US 412 (OTA ACCESS): OVER TRIBUTARY TO RED ROCK CREEK, 1.11 MILES EAST OF US-77 NEAR PERRY.
PROJECT LENGTH= 0.413 MILES

Line #		Item Description	Quantity	Unit
0003	TRAFFIC			
0430	619(B)6432	REMOVAL OF CABLE BARRIER	2,427.000	LF
0440	628(B)7300	HIGH-TENSION CABLE BARRIER(TL-4)	2,370.000	LF
0450	628(C)7400	END ANCHORS	4.000	EA
0460	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	2.000	EA
0470	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	25,200.000	LF
0480	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	25,200.000	LF
0004	TRAFFIC CONTROL			
0490	857(C)9400	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	31,420.000	LF
0500	858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	469.000	EA
0510	858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	1,039.000	EA
0520	871(B)2300	CONST.ZONE IMPACT ATTEN.	40.000	SD
0530	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	2,900.000	LF
0540	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	2,000.000	LF
0550	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,850.000	SD
0560	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	2,390.000	SD
0570	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	4,010.000	SD
0580	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	940.000	SD
0600	880(E)6607	WARNING LIGHTS(TYPE B)	3,700.000	SD
0605	880(E)6610	WARNING LIGHTS(TYPE C)	14,880.000	SD
0610	880(F)6700	DRUMS	16,730.000	SD
0620	880(G)6810	TUBE CHANNELIZERS	326.000	EA
0630	880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	740.000	HOUR
0640	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	398.000	SD
0005	STAKING			
0650	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
0660	641 2100	MOBILIZATION	1.000	LSUM