Proposal:260288 **Let Date:**November 12, 2026 **Call Order:**300
J/P Num:31893(04) **Proj. Num:**NHPP-210N(113)PM
Counties:CARTER
Description:BRIDGE AND APPROACHES
SH-142: OVER THE BNSF RAILROAD, 0.5 MILES NORTH
OF THE SH-199 INTERSECTION IN THE CITY OF ARDMORE.
PROJECT LENGTH = 0.306 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	13,534.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	23,418.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(C)2410	REINFORCED SILT FENCE	2,864.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	1,722.000	LF
0070	221(F)2730	TEMPORARY ROCK FILTER DAM TYPE 4	9.000	CY
0080	221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	2.000	EA
0090	230(A)7200	SOLID SLAB SODDING	15,740.000	SY
0100	232(A)9200	SEEDING METHOD A	3.250	AC
0110	233(A)0200	VEGETATIVE MULCHING	3.250	AC
0120	241 3100	MOWING	6.500	AC
0130	242 4101	STABILIZED CONSTRUCTION EXIT	2.000	EA
0140	303(A)1200	AGGREGATE BASE TYPE A	1,103.000	CY
0150	307(K)4200	STABILIZED SUBGRADE	5,215.000	SY
0160	325 0100	SEPARATOR FABRIC	5,313.000	SY
0170	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	332.000	TON
0180	408 8100	PRIME COAT	3,322.000	GAL
0190	409(A)9200	FABRIC REINFORCEMENT	142.000	SY
0200	411(H)1900	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	1,000.000	TON
0210	411(L)2404	BMD, TYPE B3 (PG 64-22 OK)	1,128.000	TON
0220	411(L)2412	BMD, TYPE B3 (PG 76-28 OK)	852.000	TON
0230	411(L)2428	BMD, TYPE B4 (PG 70-28 OK)	2,041.000	TON
0240	411(L)2432	BMD, TYPE B4 (PG 76-28 OK)	657.000	TON
0250	412 3100	COLD MILLING PAVEMENT	19,067.000	SY
0260	502 3100	TEMPORARY EARTH RETAINAGE	1.000	LSUM
0270	504(E)5520	42" F-SHAPED PARAPET	202.250	LF
0280	509(B)0300	CLASS A CONCRETE	95.400	CY
0290	509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	2.000	CY
0300	509(D)0500	CLASS C CONCRETE	78.000	CY
0310	510(A)1200	RETAINING WALL	694.000	SY
0320	511(B)2300	EPOXY COATED REINFORCING STEEL	18,076.000	LB
0330	514(A)5220	PILES, FURNISHED (HP 12X53)	5,555.000	LF
0340	514(B)5320	PILES, DRIVEN (HP 12X53)	5,555.000	LF
0350	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0360	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	648.000	SY
0370	601(B)1200	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	64.000	TON
0380	602(C)2410	FILTER FABRIC	48.000	SY
0390	609(B)4370	2'-8" COMB.CRB.& GUT.(6" MNTBLE)	136.000	LF
0400	609(C)4420	BITUMINOUS CURBING	1,000.000	LF
0410	610(B)5310	6" CONCRETE DRIVEWAY	23.000	SY
0420	611(G)9000	INLET CDI RCP DES. 1	1.000	EA
0430	613(A)5208	18" R.C.PIPE CLASS III	158.000	LF
0440	613(A)5350	22" X 13" R.C.PIPE ARCH CLASS A-III	7.000	LF
0450	613(L)6612	22" X 13" PREFAB. CULVERT END SEC., ARCH	1.000	EA
0460	613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	1.000	EA

Proposal:260288 **Let Date:**November 12, 2026 **Call Order:**300
J/P Num:31893(04) **Proj. Num:**NHPP-210N(113)PM
Counties:CARTER
Description:BRIDGE AND APPROACHES
SH-142: OVER THE BNSF RAILROAD, 0.5 MILES NORTH
OF THE SH-199 INTERSECTION IN THE CITY OF ARDMORE.
PROJECT LENGTH = 0.306 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0470	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0480	619(B)6356	REMOVAL OF CURB AND GUTTER	145.000	LF
0490	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	74.000	SY
0500	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	5,119.000	SY
0510	619(B)6396	REMOVAL OF GUARDRAIL	2,109.000	LF
0520	619(C)6600	SAWING PAVEMENT	948.000	LF
0530	620(C)8410	CONTRACTOR HEALTH SAFETY PLAN	1.000	LSUM
0540	622(A)0200	PIPE RAILING	405.000	LF
0550	623 1100	(PL)GUARDRAIL CURBING	4.000	EA
0560	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	812.500	LF
0570	623(G)1820	GUARDRAIL END TREATMENT (31")	4.000	EA
0580	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	4.000	EA
0590	624(A)3200	FENCE-STYLE WWF	640.000	LF

Proposal:260288 **Let Date:**November 12, 2026 **Call Order:**300
J/P Num:31893(04) **Proj. Num:**NHPP-210N(113)PM
Counties:CARTER
Description:BRIDGE AND APPROACHES
SH-142: OVER THE BNSF RAILROAD, 0.5 MILES NORTH
OF THE SH-199 INTERSECTION IN THE CITY OF ARDMORE.
PROJECT LENGTH = 0.306 MILES

Line #		Item Description	Quantity	Unit
0002	BRIDGE 'A'			
0600	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	3,155.000	CY
0610	501(G)1800	CLSM BACKFILL	2,880.700	CY
0620	504(A)5200	APPROACH SLAB	1,200.400	SY
0630	504(B)5300	SAW-CUT GROOVING	3,819.200	SY
0640	504(E)5520	42" F-SHAPED PARAPET	1,351.500	LF
0650	506(A)7225	STRUCTURAL STEEL M270 GRADE 50W	1,581,650.000	LB
0660	506(A)7230	STRUCTURAL STEEL A36	332.000	LB
0670	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	16.000	EA
0680	509(A)0210	CLASS AA CONCRETE	883.000	CY
0690	509(B)0320	CLASS A CONCRETE	1,837.800	CY
0700	510(C)1450	SLOPE WALL (5")	2,070.000	SY
0710	511(A)2210	REINFORCING STEEL	43,323.000	LB
0720	511(B)2310	EPOXY COATED REINFORCING STEEL	505,050.000	LB
0730	514(A)5210	PILES, FURNISHED (HP 10X42)	332.000	LF
0740	514(A)5220	PILES, FURNISHED (HP 12X53)	3,646.000	LF
0750	514(B)5310	PILES, DRIVEN (HP 10X42)	332.000	LF
0760	514(B)5320	PILES, DRIVEN (HP 12X53)	3,646.000	LF
0770	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0780	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	2,816.000	SY
0790	516(A)8240	DRILLED SHAFTS 60" DIAMETER	210.000	LF
0800	516(A)8250	DRILLED SHAFTS 72" DIAMETER	266.000	LF
0810	516(C)8400	CROSSHOLE SONIC LOGGING	4.000	EA
0820	517 9110	ELASTOMERIC COATING	1,672.000	SF
0830	518(B)0300	SEALED EXPANSION JOINTS	273.000	LF
0840	523(A)3200	SEALER CRACK PREPARATION	819.000	LF
0850	523(B)3300	SEALER RESIN	5.400	GAL
0860	542 9111	(PL)INSTALLATION OF BRIDGE ITEMS(TYPE A)	1.000	EA
0870	542 9121	(PL)INSTALLATION OF BRIDGE ITEMS(TYPE B)	7.000	EA
0880	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	824.000	LF
0890	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	120.000	LF
0900	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0910	624(E)3640	FENCE-STYLE CLF (8'HIGH, CLASS A)	480.000	LF

Proposal:260288 **Let Date:**November 12, 2026 **Call Order:**300
J/P Num:31893(04) **Proj. Num:**NHPP-210N(113)PM
Counties:CARTER
Description:BRIDGE AND APPROACHES
SH-142: OVER THE BNSF RAILROAD, 0.5 MILES NORTH
OF THE SH-199 INTERSECTION IN THE CITY OF ARDMORE.
PROJECT LENGTH = 0.306 MILES

Line #		Item Description	Quantity	Unit
0003	TRAFFIC CONTROL			
0920	104 3250	(SP) RAILROAD FLAGGING(NON-BIDDABLE)	250.000	DAY
0930	823 6100	(SP)PORTABLE TRAFFIC SIGNAL SYSTEM	902.000	SD
0940	854(A)6201	(SP) TRAFFIC STRIPE(PAINT)(4" WIDE)	19,812.000	LF
0950	854(B)6301	(SP) TRAFFIC STRIPE(PAINT)(ARROW)	15.000	EA
0960	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	25,510.000	LF
0970	857(F)9710	PAVEMENT MARKING REMOVAL(ARROWS)	15.000	EA
0980	858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	261.000	EA
0990	858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	248.000	EA
1000	876(A)3210	(PL)TRUCK MOUNTED ATTENUATOR	66.000	SD
1010	880(A)6220	ARROW DISPLAY(TYPE C)	33.000	SD
1020	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	32,637.000	SD
1030	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	4,334.000	SD
1040	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	7,156.000	SD
1050	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	4,158.000	SD
1060	880(E)6607	WARNING LIGHTS(TYPE B)	23,947.000	SD
1070	880(F)6700	DRUMS	4,934.000	SD
1080	880(G)6805	CHANNELIZER CONES	6,270.000	SD
1090	880(I)7000	FLAGGER	17.000	SD
1100	880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	616.000	HOUR
1110	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	581.000	SD
0004	TRAFFIC SIGNING AND STRIPING			
1120	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	1.000	EA
1130	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	3.000	EA
1140	850(A)1200	SHEET ALUMINUM SIGNS	10.000	SF
1150	851(C)2430	2 1/2" SQUARE TUBE POST	31.000	LF
1160	853 5175	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	24.000	EA
1170	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	22,834.000	LF
1180	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	50.000	LF
0005	STAKING			
1190	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
1200	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
1210	641 2100	MOBILIZATION	1.000	LSUM