Proposal: 260290 **Let Date:** November 12, 2026 **Call Order:** 310
J/P Num: 30030(04) **Proj. Num:** CIRB-220D(088)RB
Counties: CUSTER
Description: BRIDGE AND APPROACHES
COUNTY ROAD (EW-094): OVER CROOKED CREEK, 7 MILES EAST OF THE SH-34 JUNCTION NEAR BUTLER.
PROJECT LENGTH = 0.217 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(H)2900	EARTHWORK	1.000	LSUM
0030	221(B)2300	TEMPORARY SILT FENCE	760.000	LF
0040	221(E)2600	TEMPORARY SILT DIKE	300.000	LF
0050	230(A)7200	SOLID SLAB SODDING	2,200.000	SY
0060	233(A)0200	VEGETATIVE MULCHING	0.460	AC
0070	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	677.000	TON
0080	509(D)0500	CLASS C CONCRETE	10.000	CY
0090	613(A)5370	43" X 26" R.C.PIPE ARCH CLASS A-III	72.000	LF
0100	613(B)5612	28" X 20" CORR. GALV. STEEL PIPE ARCH	68.000	LF
0110	613(M)6904	TYPE B3 CULVERT END TREATMENT	2.000	EA
0120	613(M)6908	TYPE C3 CULVERT END TREATMENT	2.000	EA
0130	624(C)3410	FENCE-STYLE SWF (6 BARBED WIRE)	668.000	LF
0140	625(A)4200	REMOVE AND STORE FENCE	583.000	LF
0002	BRIDGE			
0150	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	175.000	CY
0160	501(D)1500	UNCLASSIFIED BACKFILL	549.000	CY
0170	504(D)5420	CONCRETE RAIL (TR4)	120.000	LF
0180	506(A)7200	STRUCTURAL STEEL	20,514.000	LB
0190	509(A)0210	CLASS AA CONCRETE	50.400	CY
0200	511(A)2210	REINFORCING STEEL	11,270.000	LB
0210	512(A)3200	PAINTING EXISTING STRUCTURES	1.000	LSUM
0220	512(B)3300	COLLECTION AND HANDLING OF WASTE	1.000	LSUM
0230	514(A)5210	PILES, FURNISHED (HP 10X42)	1,032.000	LF
0240	514(B)5310	PILES, DRIVEN (HP 10X42)	1,032.000	LF
0250	514(H)5900	SHEET PILING, FURNISHED	344.000	SY
0260	514(I)6000	SHEET PILING, DRIVEN	344.000	SY
0270	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0280	535 7110	HAUL AND ERECT STEEL BEAMS	1.000	LSUM
0290	601(B)1210	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	1,590.000	TON
0300	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0310	623(F)1748	GUARDRAIL ANCHOR UNIT (TYPE II)	4.000	EA
0003	TRAFFIC			
0320	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	480.000	SD
0330	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	720.000	SD
0340	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,200.000	SD
0350	880(E)6600	WARNING LIGHTS(TYPE A)	2,640.000	SD
0004	STAKING			
0360	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0370	641 2100	MOBILIZATION	1.000	LSUM