Proposal: 260296 **Let Date:** November 12, 2026 **Call Order:** 350
J/P Num: 36362(04) **Proj. Num:** SBR-263N(129)SB
Counties: POTTAWATOMIE
Description: BRIDGE REHABILITATION
US-270: OVER NORTH CANADIAN RIVER, 0.4 MILES
FROM THE JUNCTION OF US-177 NEAR SHAWNEE.
PROJECT LENGTH = 0.152 MILES

Line #		Item Description	Quantity	Unit
0001	BRIDGE 'A'			
0010	201 1100	(PL)REMOVE DRIFT AND SILT	1.000	LSUM
0020	502(B)3320	(PL)FALSEWORK JACKING	1.000	LSUM
0030	506(A)7200	STRUCTURAL STEEL	3,500.000	LB
0040	512(A)3200	PAINTING EXISTING STRUCTURES	1.000	LSUM
0050	512(B)3300	COLLECTION AND HANDLING OF WASTE	1.000	LSUM
0060	512(C)3400	TREATING PACK RUST WITH PENETRAT. SEALER	140.000	EA
0070	513(B)4300	CLASS B BRIDGE DECK REPAIR	110.000	SY
0080	513(C)4400	CLASS C BRIDGE DECK REPAIR	50.000	SY
0090	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	272.000	SY
0100	515(B)7300	WATER REPELLENT (PERFORMANCE TESTED)	5,530.000	SY
0110	517 9110	ELASTOMERIC COATING	3,221.000	SF
0120	518(C)0400	RAPID CURE JOINT SEALANT	2,167.000	LF
0130	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	60.000	LF
0140	520(C)1400	EPOXY RESIN, ABOVE WATER	1.500	GAL
0150	521(A)2200	PNEUMATICALLY PLACED MORTAR	15.700	SY
0160	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	19.900	SY
0170	545 0111	(PL)REPLACE BRIDGE ITEM (TYPE A)	3.000	EA
0180	545 0121	(PL)REPLACE BRIDGE ITEM (TYPE B)	8.000	EA
0002	TRAFFIC SIGNING AND STRIPING			
0190	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	8,520.000	LF
0003	TRAFFIC CONTROL			
0200	857(C)9405	REMOVABLE PAVEMENT MARKING TAPE(6" WIDE)	16,600.000	LF
0210	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	7,140.000	LF
0220	858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	356.000	EA
0230	858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	480.000	EA
0240	871(B)2300	CONST.ZONE IMPACT ATTEN.	360.000	SD
0250	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	2,525.000	LF
0260	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	2,500.000	LF
0270	880(A)6220	ARROW DISPLAY(TYPE C)	360.000	SD
0280	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	5,760.000	SD
0290	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	3,510.000	SD
0300	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	6,930.000	SD
0310	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	900.000	SD
0320	880(E)6607	WARNING LIGHTS(TYPE B)	5,850.000	SD
0330	880(F)6700	DRUMS	11,520.000	SD
0340	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	1,122.000	SD
0004	STAKING			
0350	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0360	641 2100	MOBILIZATION	1.000	LSUM