Proposal:260297 **Let Date:**January 14, 2027 **Call Order:**570
J/P Num:31222(04) **Proj. Num:**NHPPI-4000-(265)PM
Counties:SEQUOYAH
Description:BRIDGE AND APPROACHES
I-40: OVER US-64 AND SEQUOYAH STREET (OLD US-64),
3.9 MILES WEST AND 1.9 MILES EAST OF THE
SH-64B JUNCTION NEAR MULDROW.
PROJECT LENGTH = 0.511 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	5,757.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	15,989.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	5,219.000	LF
0060	221(C)2400	TEMPORARY SEDIMENT FILTER	3.000	EA
0070	230(A)7200	SOLID SLAB SODDING	4,417.000	SY
0080	232(B)9300	SEEDING METHOD B	9.000	AC
0090	233(A)0200	VEGETATIVE MULCHING	10.000	AC
0100	241 3100	MOWING	33.000	AC
0110	303(A)1200	AGGREGATE BASE TYPE A	5,845.000	CY
0120	317 7100	CEMENT TREATED BASE	28,083.000	SY
0130	326(C)1100	(SP) WOVEN GEOSYNTHETIC REINFORCEMENT FABRIC	28,422.000	SY
0140	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	6,482.000	TON
0150	407(B)7300	TACK COAT	289.000	GAL
0160	408 8100	PRIME COAT	21,163.000	GAL
0170	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	381.000	TON
0180	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	454.000	TON
0190	412 3100	COLD MILLING PAVEMENT	1,802.000	SY
0200	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	14,223.000	SY
0210	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	10,835.000	SY
0220	414(G)5800	P.C. CONCRETE FOR PAVEMENT	7,227.000	CY
0230	509(D)0500	CLASS C CONCRETE	28.000	CY
0240	611(G)0354	INLET (SMD-TYPE 2)	3.000	EA
0250	613(A)5216	24" R.C.PIPE CLASS III	258.000	LF
0260	613(B)5508	18" CORR. GALV. STEEL PIPE	1,508.000	LF
0270	613(J)6400	EDGE DRAIN CONDUIT-PERFORATED	3,755.000	LF
0280	613(K)6500	EDGE DRAIN OUTLET LATERAL-NONPERFORATED	402.000	LF
0290	613(M)6964	TYPE B4 CULVERT END TREATMENT	2.000	EA
0300	613(M)7004	TYPE A6 CULVERT END TREATMENT	7.000	EA
0310	613(Q)7500	OUTLET LATERAL HEADWALL	18.000	EA
0320	613(S)7700	STANDARD BEDDING MATERIAL, CLASS B	768.000	CY
0330	613(V)8000	TRENCH EXCAVATION	1,515.000	CY
0340	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0350	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	16,860.000	SY
0360	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	8,954.000	SY
0370	619(B)6396	REMOVAL OF GUARDRAIL	1,740.000	LF
0380	619(B)6432	REMOVAL OF CABLE BARRIER	5,328.000	LF
0390	619(B)6436	REMOVAL OF CONCRETE DITCH LINER	867.000	LF
0400	619(C)6600	SAWING PAVEMENT	7,137.000	LF
0410	623 1100	(PL)GUARDRAIL CURBING	863.000	EA
0420	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	2,863.000	LF
0430	623(G)1820	GUARDRAIL END TREATMENT (31")	10.000	EA
0440	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	8.000	EA
0450	624(C)3400	FENCE-STYLE SWF (4 BARBED WIRE)	133.000	LF

Proposal:260297 **Let Date:**January 14, 2027 **Call Order:**570
J/P Num:31222(04) **Proj. Num:**NHPPI-4000-(265)PM
Counties:SEQUOYAH
Description:BRIDGE AND APPROACHES
I-40: OVER US-64 AND SEQUOYAH STREET (OLD US-64),
3.9 MILES WEST AND 1.9 MILES EAST OF THE
SH-64B JUNCTION NEAR MULDROW.
PROJECT LENGTH = 0.511 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0460	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	921.000	LF
0470	624(C)3410	FENCE-STYLE SWF (6 BARBED WIRE)	101.000	LF
0480	853 5175	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	77.000	EA
0002	BRIDGE A			
0490	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	265.000	CY
0500	501(G)1800	CLSM BACKFILL	369.200	CY
0510	504(A)5200	APPROACH SLAB	471.600	SY
0520	504(B)5300	SAW-CUT GROOVING	1,427.200	SY
0530	504(E)5520	42" F-SHAPED PARAPET	677.100	LF
0540	506(A)7225	STRUCTURAL STEEL M270 GRADE 50W	326,400.000	LB
0550	507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	6.000	EA
0560	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	18.000	EA
0570	509(A)0210	CLASS AA CONCRETE	251.300	CY
0580	509(B)0320	CLASS A CONCRETE	213.500	CY
0590	511(A)2210	REINFORCING STEEL	920.000	LB
0600	511(B)2310	EPOXY COATED REINFORCING STEEL	32,350.000	LB
0610	511(C)2400	GALVANIZED REINFORCING STEEL	78,900.000	LB
0620	514(A)5220	PILES, FURNISHED (HP 12X53)	766.000	LF
0630	514(B)5320	PILES, DRIVEN (HP 12X53)	766.000	LF
0640	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0650	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	616.000	SY
0660	516(A)8230	DRILLED SHAFTS 48" DIAMETER	108.000	LF
0670	516(C)8400	CROSSHOLE SONIC LOGGING	6.000	EA
0680	517 9110	ELASTOMERIC COATING	1,238.000	SF
0690	518(B)0300	SEALED EXPANSION JOINTS	125.060	LF
0700	523(A)3200	SEALER CRACK PREPARATION	241.000	LF
0710	523(B)3300	SEALER RESIN	2.700	GAL
0720	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	120.000	LF
0730	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	60.000	LF
0740	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0750	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

Proposal:260297 **Let Date:**January 14, 2027 **Call Order:**570
J/P Num:31222(04) **Proj. Num:**NHPPI-4000-(265)PM
Counties:SEQUOYAH
Description:BRIDGE AND APPROACHES
I-40: OVER US-64 AND SEQUOYAH STREET (OLD US-64),
3.9 MILES WEST AND 1.9 MILES EAST OF THE
SH-64B JUNCTION NEAR MULDROW.
PROJECT LENGTH = 0.511 MILES

Line #		Item Description	Quantity	Unit
0003	BRIDGE B			
0760	202(A)2210	UNCLASSIFIED EXCAVATION	120.000	CY
0770	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	235.000	CY
0780	501(G)1800	CLSM BACKFILL	408.500	CY
0790	504(A)5200	APPROACH SLAB	501.200	SY
0800	504(B)5300	SAW-CUT GROOVING	1,454.700	SY
0810	504(E)5500	CONCRETE PARAPET	616.100	LF
0820	504(E)5520	42" F-SHAPED PARAPET	690.100	LF
0830	506(A)7225	STRUCTURAL STEEL M270 GRADE 50W	326,400.000	LB
0840	507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	6.000	EA
0850	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	18.000	EA
0860	509(A)0210	CLASS AA CONCRETE	251.300	CY
0870	509(B)0320	CLASS A CONCRETE	339.200	CY
0880	509(D)0510	CLASS C CONCRETE	24.700	CY
0890	510(C)1450	SLOPE WALL (5")	2,684.000	SY
0900	511(A)2210	REINFORCING STEEL	13,670.000	LB
0910	511(B)2310	EPOXY COATED REINFORCING STEEL	29,770.000	LB
0920	511(C)2400	GALVANIZED REINFORCING STEEL	78,900.000	LB
0930	514(A)5220	PILES, FURNISHED (HP 12X53)	742.000	LF
0940	514(B)5320	PILES, DRIVEN (HP 12X53)	742.000	LF
0950	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0960	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	634.000	SY
0970	516(A)8230	DRILLED SHAFTS 48" DIAMETER	114.000	LF
0980	516(C)8400	CROSSHOLE SONIC LOGGING	6.000	EA
0990	517 9110	ELASTOMERIC COATING	1,321.000	SF
1000	518(B)0300	SEALED EXPANSION JOINTS	125.060	LF
1010	523(A)3200	SEALER CRACK PREPARATION	241.000	LF
1020	523(B)3300	SEALER RESIN	2.700	GAL
1030	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	120.000	LF
1040	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	60.000	LF
1050	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

Proposal:260297 **Let Date:**January 14, 2027 **Call Order:**570
J/P Num:31222(04) **Proj. Num:**NHPPI-4000-(265)PM
Counties:SEQUOYAH
Description:BRIDGE AND APPROACHES
I-40: OVER US-64 AND SEQUOYAH STREET (OLD US-64),
3.9 MILES WEST AND 1.9 MILES EAST OF THE
SH-64B JUNCTION NEAR MULDROW.
PROJECT LENGTH = 0.511 MILES

Line #		Item Description	Quantity	Unit
0004	BRIDGE C			
1060	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	90.000	CY
1070	501(G)1800	CLSM BACKFILL	196.900	CY
1080	502(A)3200	ENGINEERED FALSEWORK	1.000	LSUM
1090	504(A)5200	APPROACH SLAB	289.000	SY
1100	504(B)5300	SAW-CUT GROOVING	861.400	SY
1110	504(E)5520	42" F-SHAPED PARAPET	400.600	LF
1120	509(A)0210	CLASS AA CONCRETE	403.500	CY
1130	509(B)0320	CLASS A CONCRETE	175.700	CY
1140	511(A)2210	REINFORCING STEEL	730.000	LB
1150	511(B)2310	EPOXY COATED REINFORCING STEEL	20,210.000	LB
1160	511(C)2400	GALVANIZED REINFORCING STEEL	79,670.000	LB
1170	514(A)5210	PILES, FURNISHED (HP 10X42)	312.000	LF
1180	514(B)5310	PILES, DRIVEN (HP 10X42)	312.000	LF
1190	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
1200	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	373.000	SY
1210	516(A)8230	DRILLED SHAFTS 48" DIAMETER	64.000	LF
1220	516(C)8400	CROSSHOLE SONIC LOGGING	4.000	EA
1230	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	94.000	LF
1240	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	30.000	LF
1250	619(B)6308	REMOVAL OF BRIDGE ITEMS	4.000	EA
1260	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0005	BRIDGE D			
1270	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	90.000	CY
1280	501(G)1800	CLSM BACKFILL	202.900	CY
1290	502(A)3200	ENGINEERED FALSEWORK	1.000	LSUM
1300	504(A)5200	APPROACH SLAB	288.200	SY
1310	504(B)5300	SAW-CUT GROOVING	860.400	SY
1320	504(E)5520	42" F-SHAPED PARAPET	400.600	LF
1330	509(A)0210	CLASS AA CONCRETE	403.500	CY
1340	509(B)0320	CLASS A CONCRETE	173.300	CY
1350	510(C)1450	SLOPE WALL (5")	1,709.000	SY
1360	511(A)2210	REINFORCING STEEL	710.000	LB
1370	511(B)2310	EPOXY COATED REINFORCING STEEL	20,190.000	LB
1380	511(C)2400	GALVANIZED REINFORCING STEEL	79,690.000	LB
1390	514(A)5210	PILES, FURNISHED (HP 10X42)	312.000	LF
1400	514(B)5310	PILES, DRIVEN (HP 10X42)	312.000	LF
1410	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
1420	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	373.000	SY
1430	516(A)8230	DRILLED SHAFTS 48" DIAMETER	68.000	LF
1440	516(C)8400	CROSSHOLE SONIC LOGGING	4.000	EA
1450	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	94.000	LF
1460	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	30.000	LF
1470	619(B)6308	REMOVAL OF BRIDGE ITEMS	4.000	EA
1480	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

Proposal:260297 **Let Date:**January 14, 2027 **Call Order:**570
J/P Num:31222(04) **Proj. Num:**NHPPI-4000-(265)PM
Counties:SEQUOYAH
Description:BRIDGE AND APPROACHES
I-40: OVER US-64 AND SEQUOYAH STREET (OLD US-64),
3.9 MILES WEST AND 1.9 MILES EAST OF THE
SH-64B JUNCTION NEAR MULDROW.
PROJECT LENGTH = 0.511 MILES

	Line #		Item Description	Quantity	Unit
0006	TRAFFIC TEMPORARY				
	1490	823 6100	(SP)PORTABLE TRAFFIC SIGNAL SYSTEM	360.000	SD
	1500	857(C)9405	REMOVABLE PAVEMENT MARKING TAPE(6" WIDE)	10,300.000	LF
	1510	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	4,190.000	LF
	1520	858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	772.000	EA
	1530	858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	1,010.000	EA
	1540	871(B)2300	CONST.ZONE IMPACT ATTEN.	3,600.000	SD
	1550	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	11,537.500	LF
	1560	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	24,062.500	LF
	1570	878(B)5300	MODULAR GLARE SCREEN (TEMPORARY)	122,400.000	SD
	1580	880(A)6220	ARROW DISPLAY(TYPE C)	1,680.000	SD
	1590	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	51,000.000	SD
	1600	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	28,980.000	SD
	1610	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	28,080.000	SD
	1620	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	19,380.000	SD
	1630	880(E)6607	WARNING LIGHTS(TYPE B)	63,720.000	SD
	1640	880(E)6616	WARNING LIGHTS(TYPE D)	16,560.000	SD
	1650	880(F)6700	DRUMS	110,280.000	SD
	1660	880(G)6805	CHANNELIZER CONES	16,560.000	SD
	1670	882 8100	(SP)SMART WORK ZONE SYSTEM	420.000	SD
	1680	882 8105	(SP)SMART WK. ZONE SYS.-PORT.CHNG.MSG.SN	10,080.000	SD
	1690	882 8110	(SP)SMART WK. ZONE SYS.-PORT.TRAF.SENSOR	8,400.000	SD
	1700	882 8115	(SP)SMART WK ZONE SYS-PAN-TILT-ZOOM CMRA	1,680.000	SD
	1710	882 8120	(SP)SMART WK. ZONE SYS.-WEBSITE SYSTEM	420.000	SD
	1720	882 8125	(PL)SMART WORK ZONE SYSTEM SETUP	1.000	EA
	1730	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	3,204.000	SD
0007	TRAFFIC SIGNING AND STRIPING				
	1740	413(C)4400	RUMBLE STRIP-METHOD PCC-CON	7,500.000	LF
	1750	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	6.000	EA
	1760	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	79,505.000	LF
	1770	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	735.000	LF
	1780	858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	25.000	EA
0008	STAKING				
	1790	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0009	CONSTRUCTION				
	1800	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
	1810	641 2100	MOBILIZATION	1.000	LSUM