Proposal: 260298 **Let Date:** January 14, 2027 **Call Order:** 571
J/P Num: 38392(04) **Proj. Num:** SBR-4000(263)SB
Counties: SEQUOYAH
Description: BRIDGE REHABILITATION
I-40: OVER LITTLE SKIN BAYOU CREEK, 3.3 MILES
WEST OF OLD US-64 NEAR MULDROW.
PROJECT LENGTH = 0.056 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	2,329.000	CY
0030	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0040	221(B)2300	TEMPORARY SILT FENCE	300.000	LF
0050	221(E)2600	TEMPORARY SILT DIKE	147.000	LF
0060	221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	3.000	EA
0070	230(A)7200	SOLID SLAB SODDING	7,278.000	SY
0080	233(A)0200	VEGETATIVE MULCHING	1.500	AC
0090	241 3100	MOWING	3.000	AC
0100	303(A)1200	AGGREGATE BASE TYPE A	1,739.000	CY
0110	326(C)1100	(SP) WOVEN GEOSYNTHETIC REINFORCEMENT FABRIC	3,082.000	SY
0120	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	781.000	TON
0130	407(B)7300	TACK COAT	1,164.000	GAL
0140	408 8100	PRIME COAT	2,365.000	GAL
0150	411(B)1320	SUPERPAVE, TYPE S3(PG 70-28 OK)	127.000	TON
0160	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	2,605.000	TON
0170	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	878.000	TON
0180	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	1,452.000	SY
0190	414(G)5800	P.C. CONCRETE FOR PAVEMENT	363.000	CY
0200	509(D)0500	CLASS C CONCRETE	10.000	CY
0210	611(G)0350	INLET (SMD-TYPE 1)	3.000	EA
0220	611(H)0400	ADDITIONAL DEPTH IN INLET	6.000	VF
0230	613(A)5216	24" R.C.PIPE CLASS III	134.000	LF
0240	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0250	615(A)1249	18" POLYVINYL CHLORIDE (PVC) PIPE	918.000	LF
0260	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0270	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	1,070.000	SY
0280	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	1,492.000	SY
0290	619(B)6396	REMOVAL OF GUARDRAIL	602.000	LF
0300	619(B)6440	REMOVAL OF EXISTING PIPE	120.000	LF
0310	619(C)6600	SAWING PAVEMENT	3,658.000	LF
0320	623 1100	(PL)GUARDRAIL CURBING	4.000	EA
0330	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	600.000	LF
0340	623(G)1820	GUARDRAIL END TREATMENT (31")	4.000	EA
0350	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	4.000	EA

Proposal:260298 **Let Date:**January 14, 2027 **Call Order:**571
J/P Num:38392(04) **Proj. Num:**SBR-4000(263)SB
Counties:SEQUOYAH
Description:BRIDGE REHABILITATION
I-40: OVER LITTLE SKIN BAYOU CREEK, 3.3 MILES
WEST OF OLD US-64 NEAR MULDROW.
PROJECT LENGTH = 0.056 MILES

Line #		Item Description	Quantity	Unit
0002	BRIDGE A			
0360	501(A)1210	STRUCTURAL EXCAVATION UNCLASSIFIED	110.000	CY
0370	501(G)1800	CLSM BACKFILL	113.000	CY
0380	504(A)5200	APPROACH SLAB	325.000	SY
0390	504(B)5300	SAW-CUT GROOVING	701.600	SY
0400	504(E)5520	42" F-SHAPED PARAPET	385.700	LF
0410	506(A)7200	STRUCTURAL STEEL	83,910.000	LB
0420	507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	12.000	EA
0430	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	24.000	EA
0440	509(A)0210	CLASS AA CONCRETE	129.100	CY
0450	509(D)0510	CLASS C CONCRETE	6.000	CY
0460	511(B)2310	EPOXY COATED REINFORCING STEEL	39,390.000	LB
0470	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	598.000	SY
0480	517 9110	ELASTOMERIC COATING	608.000	SF
0490	518(B)0300	SEALED EXPANSION JOINTS	42.190	LF
0500	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	2.000	LF
0510	520(C)1400	EPOXY RESIN, ABOVE WATER	0.200	GAL
0520	521(A)2200	PNEUMATICALLY PLACED MORTAR	18.000	SY
0530	523(A)3200	SEALER CRACK PREPARATION	43.000	LF
0540	523(B)3300	SEALER RESIN	0.500	GAL
0550	524(A)4200	(SP) CARBON FIBER-REINFORCED POLYMER	940.000	SF
0560	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	75.000	SY
0570	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
0003	BRIDGE B			
0580	501(A)1210	STRUCTURAL EXCAVATION UNCLASSIFIED	110.000	CY
0590	501(G)1800	CLSM BACKFILL	113.000	CY
0600	504(A)5200	APPROACH SLAB	325.000	SY
0610	504(B)5300	SAW-CUT GROOVING	701.600	SY
0620	504(E)5520	42" F-SHAPED PARAPET	385.700	LF
0630	506(A)7200	STRUCTURAL STEEL	83,910.000	LB
0640	507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	12.000	EA
0650	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	24.000	EA
0660	509(A)0210	CLASS AA CONCRETE	128.600	CY
0670	509(D)0510	CLASS C CONCRETE	7.000	CY
0680	511(B)2310	EPOXY COATED REINFORCING STEEL	39,390.000	LB
0690	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	598.000	SY
0700	517 9110	ELASTOMERIC COATING	608.000	SF
0710	518(B)0300	SEALED EXPANSION JOINTS	42.190	LF
0720	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	7.000	LF
0730	520(C)1400	EPOXY RESIN, ABOVE WATER	0.700	GAL
0740	521(A)2200	PNEUMATICALLY PLACED MORTAR	9.000	SY
0750	523(A)3200	SEALER CRACK PREPARATION	43.000	LF
0760	523(B)3300	SEALER RESIN	0.500	GAL
0770	524(A)4200	(SP) CARBON FIBER-REINFORCED POLYMER	940.000	SF
0780	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	45.000	SY
0790	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM

Proposal:260298 **Let Date:**January 14, 2027 **Call Order:**571
J/P Num:38392(04) **Proj. Num:**SBR-4000(263)SB
Counties:SEQUOYAH
Description:BRIDGE REHABILITATION
I-40: OVER LITTLE SKIN BAYOU CREEK, 3.3 MILES
WEST OF OLD US-64 NEAR MULDROW.
PROJECT LENGTH = 0.056 MILES

Line #		Item Description	Quantity	Unit
0004	TRAFFIC SIGNING AND STRIPING			
0800	413(A)4200	RUMBLE STRIP-METHOD HMA-CON	3,420.000	LF
0810	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	2.000	EA
0820	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	6,830.000	LF
0005	TRAFFIC BARRIERS			
0830	509(A)0200	CLASS AA CONCRETE	33.000	CY
0840	619(B)6432	REMOVAL OF CABLE BARRIER	1,645.000	LF
0850	628 7100	INSTALLATION OF CABLE BARRIER SYSTEM	1,645.000	LF
0860	628(C)7400	END ANCHORS	4.000	EA
0006	TRAFFIC CONTROL			
0870	857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	15,500.000	LF
0880	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	21,900.000	LF
0890	871(B)2300	CONST.ZONE IMPACT ATTEN.	200.000	SD
0900	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	1,950.000	LF
0910	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	1,950.000	LF
0920	880(A)6220	ARROW DISPLAY(TYPE C)	520.000	SD
0930	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	3,520.000	SD
0940	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	7,760.000	SD
0950	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	5,080.000	SD
0960	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	5,160.000	SD
0970	880(E)6600	WARNING LIGHTS(TYPE A)	13,840.000	SD
0980	880(E)6610	WARNING LIGHTS(TYPE C)	33,480.000	SD
0990	880(F)6700	DRUMS	33,480.000	SD
1000	880(G)6805	CHANNELIZER CONES	9,820.000	SD
1010	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	548.000	SD
0007	STAKING			
1020	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0008	CONSTRUCTION			
1030	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
1040	641 2100	MOBILIZATION	1.000	LSUM