Proposal: 260300 **Let Date:** November 12, 2026 **Call Order:** 370
J/P Num: 35488(04) **Proj. Num:** STP-272F(390)IG
Counties: TULSA
Description: PEDESTRIAN IMPROVEMENTS (SIDEWALKS)
CITY STREETS (E. 31ST, E. 41ST, E. 61ST STREET, AND SOUTH MEMORIAL DRIVE): AT MULTIPLE LOCATIONS IN THE CITY OF TULSA.
PROJECT LENGTH = 1.17 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	1,210.000	CY
0030	221(B)2300	TEMPORARY SILT FENCE	2,833.000	LF
0040	221(C)2400	TEMPORARY SEDIMENT FILTER	12.000	EA
0050	230(A)7200	SOLID SLAB SODDING	4,101.000	SY
0060	303(A)1200	AGGREGATE BASE TYPE A	334.000	CY
0070	310(B)5300	SUBGRADE, METHOD B	1,377.000	SY
0080	325 0100	SEPARATOR FABRIC	1,925.000	SY
0090	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	570.000	SY
0100	414(G)5800	P.C. CONCRETE FOR PAVEMENT	112.000	CY
0110	509(B)0300	CLASS A CONCRETE	82.000	CY
0120	511(A)2200	REINFORCING STEEL	7,604.000	LB
0130	609(A)4230	CONC.CURB(6" BARRIER-INTEGRAL)	189.000	LF
0140	610(A)5200	4" CONCRETE SIDEWALK	2,307.000	SY
0150	610(A)5240	4" DECORATIVE CONCRETE SIDEWALK	248.000	SY
0160	610(B)5300	6" CONCRETE DRIVEWAY (H.E.S.)	686.000	SY
0170	610(I)6000	TACTILE WARNING DEVICE-NEW	216.000	SF
0180	612(A)3200	MANHOLES ADJUST TO GRADE	2.000	EA
0190	612(E)3600	VALVE BOXES ADJUST TO GRADE	2.000	EA
0200	612(F)3700	METER BOXES ADJUST TO GRADE	2.000	EA
0210	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0220	619(B)6356	REMOVAL OF CURB AND GUTTER	364.000	LF
0230	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	566.000	SY
0240	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	327.000	SY
0250	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	390.000	SY
0260	619(B)6404	REMOVAL OF SIDEWALK	203.000	SY
0270	624(E)3620	FENCE-STYLE CLF (6'HIGH, CLASS A)	153.000	LF
0002	PERMANENT TRAFFIC			
0280	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	42.000	EA
0290	805(B)3300	(PL)RESET OF PULL BOX	1.000	EA
0300	805(D)3536	(PL)REMOVE & RESET GROUND MOUNTED SIGN	3.000	EA
0310	850(A)1200	SHEET ALUMINUM SIGNS	180.000	SF
0320	851(C)2405	1 1/2" SQUARE TUBE POST	8.000	LF
0330	851(C)2410	1 3/4" SQUARE TUBE POST	174.000	LF
0340	851(C)2415	2" SQUARE TUBE POST	51.000	LF
0350	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	445.000	LF
0360	856(B)8311	(SP) TRAFFIC STRIPE(PLURAL-COMP)(SYMBOLS)	6.000	EA

Proposal: 260300 **Let Date:** November 12, 2026 **Call Order:** 370
J/P Num: 35488(04) **Proj. Num:** STP-272F(390)IG
Counties: TULSA
Description: PEDESTRIAN IMPROVEMENTS (SIDEWALKS)
CITY STREETS (E. 31ST, E. 41ST, E. 61ST STREET, AND SOUTH MEMORIAL DRIVE): AT MULTIPLE LOCATIONS IN THE CITY OF TULSA.
PROJECT LENGTH = 1.17 MILES

Line #		Item Description	Quantity	Unit
0003	TEMPORARY TRAFFIC			
0370	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,125.000	SD
0380	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,125.000	SD
0390	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	450.000	SD
0400	880(E)6600	WARNING LIGHTS(TYPE A)	900.000	SD
0410	880(E)6610	WARNING LIGHTS(TYPE C)	2,050.000	SD
0420	880(F)6700	DRUMS	2,050.000	SD
0430	880(G)6800	TUBE CHANNELIZERS	1,500.000	SD
0440	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	120.000	SD
0004	STAKING			
0450	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0460	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0470	641 2110	MOBILIZATION	1.000	LSUM