Proposal: 260302 **Let Date:** November 19, 2026 **Call Order:** 042
J/P Num: 37100(17) **Proj. Num:** EWC-28803B
Counties: CLEVELAND
Description: GRADE, DRAIN AND BRIDGE
TOBY KEITH EXPRESSWAY TURNPIKE(OTA ACCESS) / INDIAN HILLS ROAD/
36TH AVENUE NW: FROM 0.3 MILES WEST OF I-35 INTERSECTION,
EXTEND WEST NEAR NORMAN.
PROJECT LENGTH = 0.078 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	9,405.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	240,376.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(C)2400	TEMPORARY SEDIMENT FILTER	4.000	EA
0060	221(C)2410	REINFORCED SILT FENCE	3,341.000	LF
0070	221(E)2600	TEMPORARY SILT DIKE	210.000	LF
0080	221(G)2800	TEMPORARY FIBER LOG	6,340.000	LF
0090	230(A)7200	SOLID SLAB SODDING	60,582.000	SY
0100	233(E)0600	(SP) HYDROMULCH	60,582.000	SY
0110	242 4101	STABILIZED CONSTRUCTION EXIT	2.000	EA
0120	509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	4.000	CY
0130	611(G)0354	INLET (SMD-TYPE 2)	1.000	EA
0140	611(G)0362	INLET (SMD-TYPE 2B)	1.000	EA
0150	611(L)1600	JUNCTION BOXES	250.000	CF
0160	613(A)5314	24" R.C.PIPE CLASS V	318.000	LF
0170	613(A)5316	30" R.C.PIPE CLASS V	868.000	LF
0180	613(A)5358	28" X 18" R.C.PIPE ARCH CLASS A-III	106.000	LF
0190	613(A)5374	51" X 31" R.C.PIPE ARCH CLASS A-III	204.000	LF
0200	613(L)6620	28" X 18" PREFAB. CULVERT END SEC., ARCH	1.000	EA
0210	613(M)6904	TYPE B3 CULVERT END TREATMENT	1.000	EA
0220	613(M)6928	TYPE CC3 CULVERT END TREATMENT	3.000	EA
0230	613(Q)7500	OUTLET LATERAL HEADWALL	8.000	EA
0240	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM

Proposal:260302 **Let Date:**November 19, 2026 **Call Order:**042
J/P Num:37100(17) **Proj. Num:**EWC-28803B
Counties:CLEVELAND
Description:GRADE, DRAIN AND BRIDGE
TOBY KEITH EXPRESSWAY TURNPIKE(OTA ACCESS) / INDIAN HILLS ROAD/
36TH AVENUE NW: FROM 0.3 MILES WEST OF I-35 INTERSECTION,
EXTEND WEST NEAR NORMAN.
PROJECT LENGTH = 0.078 MILES

Line #		Item Description	Quantity	Unit
0002	BRIDGE TPO 113.64 WB			
0250	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	200.000	CY
0260	501(G)1800	CLSM BACKFILL	188.400	CY
0270	504(A)5200	APPROACH SLAB	273.400	SY
0280	504(B)5300	SAW-CUT GROOVING	1,742.500	SY
0290	504(E)5520	42" F-SHAPED PARAPET	824.700	LF
0300	506(A)7200	STRUCTURAL STEEL	524,680.000	LB
0310	507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	15.000	EA
0320	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	15.000	EA
0330	509(A)0210	CLASS AA CONCRETE	370.800	CY
0340	509(B)0320	CLASS A CONCRETE	228.600	CY
0350	509(D)0510	CLASS C CONCRETE	11.000	CY
0360	510(C)1450	SLOPE WALL (5")	1,202.000	SY
0370	510(D)1500	GRAFFITI TREATMENT	18,303.000	SF
0380	511(A)2210	REINFORCING STEEL	1,930.000	LB
0390	511(B)2310	EPOXY COATED REINFORCING STEEL	121,310.000	LB
0400	514(A)5210	PILES, FURNISHED (HP 10X42)	168.000	LF
0410	514(A)5220	PILES, FURNISHED (HP 12X53)	832.000	LF
0420	514(B)5310	PILES, DRIVEN (HP 10X42)	168.000	LF
0430	514(B)5320	PILES, DRIVEN (HP 12X53)	832.000	LF
0440	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0450	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	2,895.000	SY
0460	516(A)8250	DRILLED SHAFTS 72" DIAMETER	104.000	LF
0470	516(C)8400	CROSSHOLE SONIC LOGGING	2.000	EA
0480	517 9110	ELASTOMERIC COATING	1,162.400	SF
0490	518(B)0310	EXPANSION JOINT SYSTEM	80.350	LF
0500	535 7200	(SP) AESTHETIC TREATMENT	1.000	LSUM
0510	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	218.000	LF
0520	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	95.000	LF

Proposal:260302 **Let Date:**November 19, 2026 **Call Order:**042
J/P Num:37100(17) **Proj. Num:**EWC-28803B
Counties:CLEVELAND
Description:GRADE, DRAIN AND BRIDGE
TOBY KEITH EXPRESSWAY TURNPIKE(OTA ACCESS) / INDIAN HILLS ROAD/
36TH AVENUE NW: FROM 0.3 MILES WEST OF I-35 INTERSECTION,
EXTEND WEST NEAR NORMAN.
PROJECT LENGTH = 0.078 MILES

Line #		Item Description	Quantity	Unit
0003	BRIDGE TPO 113.64 EB			
0530	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	200.000	CY
0540	501(G)1800	CLSM BACKFILL	188.400	CY
0550	504(A)5200	APPROACH SLAB	273.400	SY
0560	504(B)5300	SAW-CUT GROOVING	1,742.500	SY
0570	504(E)5520	42" F-SHAPED PARAPET	824.700	LF
0580	506(A)7200	STRUCTURAL STEEL	524,680.000	LB
0590	507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	15.000	EA
0600	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	15.000	EA
0610	509(A)0210	CLASS AA CONCRETE	370.800	CY
0620	509(B)0320	CLASS A CONCRETE	228.600	CY
0630	509(D)0510	CLASS C CONCRETE	5.000	CY
0640	510(C)1450	SLOPE WALL (5")	1,204.000	SY
0650	510(D)1500	GRAFFITI TREATMENT	18,360.000	SF
0660	511(A)2210	REINFORCING STEEL	1,930.000	LB
0670	511(B)2310	EPOXY COATED REINFORCING STEEL	121,310.000	LB
0680	514(A)5210	PILES, FURNISHED (HP 10X42)	172.000	LF
0690	514(A)5220	PILES, FURNISHED (HP 12X53)	854.000	LF
0700	514(B)5310	PILES, DRIVEN (HP 10X42)	172.000	LF
0710	514(B)5320	PILES, DRIVEN (HP 12X53)	854.000	LF
0720	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0730	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	2,895.000	SY
0740	516(A)8250	DRILLED SHAFTS 72" DIAMETER	102.000	LF
0750	516(C)8400	CROSSHOLE SONIC LOGGING	2.000	EA
0760	517 9110	ELASTOMERIC COATING	1,162.400	SF
0770	518(B)0310	EXPANSION JOINT SYSTEM	80.350	LF
0780	535 7200	(SP) AESTHETIC TREATMENT	1.000	LSUM
0790	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	218.000	LF
0800	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	95.000	LF
0004	TRAFFIC SIGNING AND STRIPING			
0810	850(A)1200	SHEET ALUMINUM SIGNS	56.000	SF
0005	TRAFFIC CONTROL			
0820	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	2,960.000	SD
0830	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	3,060.000	SD
0840	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	840.000	SD
0850	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	840.000	SD
0860	880(E)6607	WARNING LIGHTS(TYPE B)	2,640.000	SD
0870	880(I)7000	FLAGGER	20.000	SD
0880	880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	1,680.000	HOUR
0890	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	448.000	SD
0006	STAKING			
0900	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM

Proposal:260302 **Let Date:**November 19, 2026 **Call Order:**042
J/P Num:37100(17) **Proj. Num:**EWC-28803B
Counties:CLEVELAND
Description:GRADE, DRAIN AND BRIDGE
TOBY KEITH EXPRESSWAY TURNPIKE(OTA ACCESS) / INDIAN HILLS ROAD/
36TH AVENUE NW: FROM 0.3 MILES WEST OF I-35 INTERSECTION,
EXTEND WEST NEAR NORMAN.
PROJECT LENGTH = 0.078 MILES

Line #		Item Description	Quantity	Unit
0007	CONSTRUCTION			
0910	108 7180	(SP) CRITICAL PATH METHOD SCHEDULE	1.000	LSUM
0920	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0930	641 2100	MOBILIZATION	1.000	LSUM